OF, 20	E DAUPHIN COUNTY PLANNING COMMISSION THIS DAY
., 20.	21.
SECRETARY	
DIRECTOR	(SEAL)
SUSQUEHANNA TOWNSHI	P BOARD OF COMMISSIONERS
	E SUSQUEHANNA TOWNSHIP BOARD OF COMMISSIONERS THIS DAY
OF, 20	21.
SECRETARY	
PRESIDENT	(SEAL)
SUSQUEHANNA TOWNSHI	
OF , 202	E SUSQUEHANNA TOWNSHIP PLANNING COMMISSION THIS DAY
., 20	21.
SECRETARY	
CHAIRMAN	(SEAL)
THE FOLLOWING SIGNATURE DEVELOPMENT PLAN:	BLOCK CERTIFIES THAT THE TOWNSHIP ENGINEER HAS REVIEWED THE
I,, A	REGISTERED PROFESSIONAL ENGINEER OF THE TOWNSHIP OF CERTIFY THAT THIS DEVELOPMENT PLAN MEETS ALL THE ENGINEERING
AND DESIGN REQUIREMENTS	CERTIFY THAT THIS DEVELOPMENT PLAN MEETS ALL THE ENGINEERING OF THE TOWNSHIP SUBDIVISION AND ZONING ORDINANCE, EXCEPT AS THORIZED BY THE APPROVAL AUTHORITY.
DATE	TOWNSHIP ENGINEER
	REGISTRATION NO.
SUSQUEHANNA, DAUPHIN COU PLAN OF LOTS OF THEIR PROF COUNTY, COMMONWEALTH OF HEREBY DEDICATE FOREVER,	ESENTS, THAT, OF THE TOWNSHIP OF UNTY, PENNSYLVANIA, THEREOF, DO HEREBY ADOPT THIS PLAN AS OUR PERTIES SITUATED IN THE TOWNSHIP OF SUSQUEHANNA, DAUPHIN F PENNSYLVANIA, AND FOR DIVERS ADVANTAGES ACCRUING TO ME, DO , FOR PUBLIC USE FOR HIGHWAY PURPOSES ALL SLOPE AREAS AND ALL NES, WAYS AND OTHER PUBLIC HIGHWAYS SHOWN UPON THE PLAN, WITH
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONY	CTS AS IF THE SAME HAD BEEN THROUGH LEGAL PROCEEDINGS, AND IN ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC VEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPP	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA.	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC WEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA.	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC VEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA.	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC VEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF OWNER SIGNATURE PRINTED NAME OF OWNER
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA. WITNESS DATE SURVEYOR'S CERTIFICATI I, DAVID RUSSEL BOYER, A RE DO HEREBY CERTIFY TO THE I CORRECTLY REPRESENTS TH	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC WEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF OWNER SIGNATURE PRINTED NAME OF OWNER ION EGISTERED LAND SURVEYOR FOR THE COMMONWEALTH OF PENNSYLVANIA, BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THIS PLAN HE LOTS, LANDS STREETS AND HIGHWAYS AS SURVEYED AND PLOTTED BY
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA. WITNESS DATE SURVEYOR'S CERTIFICATI I, DAVID RUSSEL BOYER, A RE DO HEREBY CERTIFY TO THE I CORRECTLY REPRESENTS TH	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC WEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF OWNER SIGNATURE PRINTED NAME OF OWNER ION EGISTERED LAND SURVEYOR FOR THE COMMONWEALTH OF PENNSYLVANIA, BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THIS PLAN HE LOTS, LANDS STREETS AND HIGHWAYS AS SURVEYED AND PLOTTED BY
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA. WITNESS DATE SURVEYOR'S CERTIFICATI I, DAVID RUSSEL BOYER, A RE DO HEREBY CERTIFY TO THE I CORRECTLY REPRESENTS TH ME FOR THE OWNERS OR AGE DATE	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC WEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF OWNER SIGNATURE PRINTED NAME OF OWNER ION GISTERED LAND SURVEYOR FOR THE COMMONWEALTH OF PENNSYLVANIA, BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THIS PLAN HE LOTS, LANDS STREETS AND HIGHWAYS AS SURVEYED AND PLOTTED BY ENTS. DAVID RUSSEL BOYER, PLS REGISTRATION NO. SU-XXXXXX
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA. WITNESS DATE DATE SURVEYOR'S CERTIFICATI I, DAVID RUSSEL BOYER, A RE DO HEREBY CERTIFY TO THE I CORRECTLY REPRESENTS TH ME FOR THE OWNERS OR AGE DATE DATE DATE DATE	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC WEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF OWNER SIGNATURE PRINTED NAME OF OWNER ION GISTERED LAND SURVEYOR FOR THE COMMONWEALTH OF PENNSYLVANIA, BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THIS PLAN HE LOTS, LANDS STREETS AND HIGHWAYS AS SURVEYED AND PLOTTED BY ENTS. DAVID RUSSEL BOYER, PLS REGISTRATION NO. SU-XXXXXX
THE SAME FORCE AND EFFEC CONSIDERATION OF THE APPF HIGHWAYS BY THE COMMONV SUSQUEHANNA. WITNESS DATE SURVEYOR'S CERTIFICATI I, DAVID RUSSEL BOYER, A RE DO HEREBY CERTIFY TO THE I CORRECTLY REPRESENTS TH ME FOR THE OWNERS OR AGE DATE DATE DATE	ROVAL OF SAID PLAN, ANY FUTURE ACCEPTANCE OF SAID PUBLIC WEALTH OF PENNSYLVANIA, COUNTY OF DAUPHIN, AND THE TOWNSHIP OF OWNER SIGNATURE PRINTED NAME OF OWNER PRINTED NAME OF OWNER ON GISTERED LAND SURVEYOR FOR THE COMMONWEALTH OF PENNSYLVANIA, BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THIS PLAN HE LOTS, LANDS STREETS AND HIGHWAYS AS SURVEYED AND PLOTTED BY ENTS. DAVID RUSSEL BOYER, PLS REGISTRATION NO. SU-XXXXXX DN OFESSIONAL ENGINEER FOR THE COMMONWEALTH OF PENNSYLVANIA, DO

FINAL SUBDIVISION AND LAND DEVELOPMEN



Scale: 1" = 1000'

NPDES INFO

PERMIT NO: XXXXXXXXXXX EXPIRATION DATE: XXXXXXXXX

3405 AND 3401 NORTH FRONT STREET

SUSQUEHANNA TOWNSHIP, DAUPHIN COUNTY, PENNSYLVANIA MARCH 5, 2021

PREPARED FOR: OWNER/DEVELOPER LINLO MONTROSE PARK, LLC


150 CORPORATE CIRCLE, SUITE 100 LEMOYNE, PENNSYLVANIA 17043

McCormicks Island PROJECT LOCATION VAUGHN ST LEWIS ST EDWARD ST GRAHAM ST.

LOCATION MAP

USGS MAP Scale: 1" = 1000'

PREPARED BY: **PENNONI ASSOCIATES INC.**



5072 Ritter Road, Suite 102 Mechanicsburg, PA 17055 **T** 717.975.6481 **F** 717.975.6480

	SHEET LIST TABLE				
SHEET	PAGE	SHEET TITLE			
CS0001	1	COVER SHEET			
CS0201	2	EXISTING CONDITIONS AND SITE DEMOLITION PLAN			
CS0301	3	EASEMENT PLAN			
CS0901	4	LOT CONSOLIDATION PLAN			
CS1001	5	SITE LAYOUT PLAN			
CS1501	6	GRADING PLAN			
CS1701	7	UTILITY PLAN			
CS2001	8	LANDSCAPE PLAN			
CS4001	9	STORM SEWER PROFILES			
CS6001	10	SITE DETAILS			
CS6002	11	SITE DETAILS			
CS6041	12	UTILITY DETAILS			
CS6061	13	LANDSCAPE DETAILS AND NOTES			
CS8001	14	EROSION AND SEDIMENTATION CONTROL PLAN			
CS8501	15	EROSION AND SEDIMENTATION CONTROL NOTES			
CS8502	16	EROSION AND SEDIMENTATION CONTROL DETAILS			
CS8503	17	EROSION AND SEDIMENTATION CONTROL DETAILS			
CS9001	18	POST CONSTRUCTION STORMWATER MANAGEMENT PLAN			
CS9501	19	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS			
CS9502	20	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS			
CS9503	21	POST CONSTRUCTION STORMWATER MANAGEMENT DETAILS			

ZONING INFORMATION

THE SUBJECT PREMISES LIES WITHIN THE BOR (BUSINESS OFFICE RESIDENTIAL) ZONING DISTRIC

ZONING DISTRICT:	BOR
	REQUIRED
MIN. LOT AREA:	15,000 SQ. FT.
MIN. LOT WIDTH:	150 FEET
MAX. IMPERVIOUS	
SURFACE COVERAGE:	80%
MAX. BUILDING COVERAGE:	35%
MIN. FRONT YARD:	25 FEET
	65 FEET (N FRONT ST)
MIN. SIDE YARD:	10 FEET
MIN. REAR YARD:	25 FEET
MAX. BUILDING HEIGHT:	42 FEET

PARKING INFORMATION:

	REQUIRED
3401 N FRONT ST (EXISTING BUILDING	G)
3405 N FRONT ST (PROPOSED BUILDI	ING)
5090 SF OFFICE 1 SPACE PER 250 SF	5090SF/250SF = 21 SPACES
7243 SF MEDICAL (DIALYSIS CLINIC) 5 SPACES PER DOCTOR	1 VISITING DOCTOR AT SITE = 5 SPACES

187.625 SQ. F 62% 14% >25 FEET >65 FEET >10 FEET 25 FEET 20 FEET

PROVIDED


122 (NO SPACES TO BE ADDED)

56 (49 ONSITE/7 ON MONTROSE ST)

CALL BEFORE YOU DIG

BEFORE YOU DIG ANYWHERE IN PENNSYLVANIA CALL 1-800-242-1776 PA. ACT 287 OF 1974 REQUIRES THREE WORKING DAYS NOTICE TO UTILITIES BEFORE YOU EXCAVATE, DRILL OR BLAST PENNSYLVANIA ONE-CALL SYSTEM, INC. SERIAL NUMBER(S): 20210050687





INLET

ASPHALT

3ERGI (50' R

Ϋ́Я

STR

27.17



- LOCATION: THE PROJECT SITE IS LOCATED AT 3405 & 3401 NORTH FRONT STREET, SUSQUEHANNA TOWNSHIP, DAUPHIN COUNTY, PA.
- 2. THE FIELD SURVEY WAS PERFORMED BY PENNONI ASSOCIATES INC., 5072 RITTER ROAD, SUITE 102, MECHANICSBURG, PA 17055, ON FEBRUARY 8, 9, & 12, 2021. SITE WAS SNOW-COVERED FOR THE DURATION OF THE SURVEY.
- 3. PROPERTY BOUNDARY INFORMATION DEPICTED ON THIS PLAN IS BASED UPON RECORD DEED & PLAN INFORMATION AS IT RELATES TO FOUND MONUMENTATION.
- 4. EXISTING TOPOGRAPHY AND PLAIMETRIC FEATURES SHOWN ON THIS PLAN ARE BASED ON AN ON-THE-GROUND FIELD SURVEY, DERIVED FROM GPS OBSERVATIONS AND TRADITIONAL SURVEY METHODS.
- 5. THE SITE IS COMPRISED OF THE FOLLOWING TWO (2) PARCELS: 3405 NORTH FRONT STREET PID# 62-017-198 INSTRUMENT #20190005610 3401 NORTH FRONT STREET PID# 62-017-207 INSTRUMENT #20080044620
- 6. PLAN IS TIED HORIZONTALLY TO THE PENNSYLVANIA STATE PLANE COORDINATE SYSTEM (NAD83) AND VERICALLY TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88).

7. SITE BENCHMARK


CONTROL POINT #4 - "MAG" NAIL SET IN THE REAR 3401 NORTH FRONT STREET PARKING LOT, EST OF THE DUMPSTER ENCLOSURE, AS SHOWN - ELEVATION 323.90' (NAVD88).


8. <u>REFERENCE PLANS:</u>


- PLAN OF "BERGNER FARM" PREPARED BY GANNETT, SEELY & FLEMING, ENGINEERS, INC. IN MAY 1928 AND RECORDED IN THE DAUPHIN COUNTY RECORDER OF DEEDS OFFICE ON 8/5/1929 IN PLAN BOOK J-1 PAGE 23.
- PLAN OF "SECTION A MONTROSE PARK" RECORDED IN THE DAUPHIN COUNTY RECORDER OF DEEDS OFFICE ON 4/10/1923 IN PLAN BOOK H-1 PAGE 56.
- 9. THE SITE IS LOCATED PARTLY WITHIN ZONE X AND ZONE AE AS SHOWN ON THE FEMA FLOOD INSURANCE RATE MAP FOR DAUPHIN COUNTY, PA, MAP NUMBER 42043C0317D, PANEL 317 OF 501, HAVING AN EFFECTIVE DATE OF AUGUST 2, 2012.
- 10. THE NATIONAL WETLANDS INVENTORY MAP DOES NOT INDICATE THE PRESENCE OF WETLANDS ON THE SUBJECT PREMISES. AN INDEPENDENT ABSENCE/PRESENCE WETLAND DETERMINATION BY A WETLAND SCIENTIST HAS NOT BEEN PERFORMED.
- 11. THE SITE DOES NOT APPEAR TO BE PRESENT OF ANY ARCHAEOLOGICAL RESOURCES, HISTORICAL FEATURES, AND IMPORTANT NATURAL HABITAT.
- 12. THIS PLAN HAS BEEN PREPARED WITH THE BENEFIT OF A CLIENT SUPPLIED TITLE REPORT PREPARED BY FIDELITY NATIONAL TITLE INSURANCE COMPANY FOR THE 3405 NORTH FRONT STREET PROPERTY - HAVING A COMMITMENT NUMBER OF 2020-1966-CLT AND A COMMITMENT DATE OF 12/10/2020. A TITLE REPORT WAS NOT PROVIDED FOR 3401 NORTH FRONT STREET WHICH MAY BE SUBJECT TO EASEMENTS, RIGHT-OF-WAYS, COVENANTS AND OTHER RESTRICTIONS, EITHER RECORDED OR UNRECORDED. THE SURVEYOR HAS NOT PERFORMED ANY INDEPENDENT RESEARCH FOR ENCUMBERANCES OR TITLE EVIDENCE AFFECTING THE 3401 NORTH FRONT STREET PROPERTY THAT A CURRENT AND ACCURATE TITLE REPORT WOULD DISCLOSE.
- 13. THE WORD "CERTIFY" AS USED IN ITS VARIOUS FORMS HEREON, IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL OPINION BY THE SURVEYOR, WHICH IS BASED ON HIS BEST KNOWLEDGE, INFORMATION AND BELIEF. AS SUCH. IT CONSTITUTES NEITHER A GUARANTEE OR WARRANTY, EITHER EXPRESSED OR IMPLIED.

UTILITY NOTES:

- 1. IN ACCORDANCE WITH PA ACT 287 (1974), AS CURRENTLY AMENDED, THE CONTRACTOR SHALL NOTIFY ALL UTILITIES WITHIN THE WORK AREA VIA THE PENNSYLVANIA ONE CALL SYSTEM. INC. (800-242-1776) A MINIMUM OF 3 WORKING DAYS BEFORE THE START OF EXCAVATION. A PRELIMINARY DESIGN PA ONE CALL HAS BEEN PLACED FOR THIS PROJECT - SERIAL NUMBER 20210050687.
- 2. THE UNDERGROUND UTILITIES SHOWN ON THIS PLAN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS (SUE ASCE STANDARD 38-02 QUALITY LEVEL C). SITE WAS SNOW-COVERED FOR THE DURATION OF THE FIELD SURVEY. THE SURVEYOR MAKES NO GUARANTEES THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT ARE ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.
- 3. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE LOCATIONS AND DEPTHS OF ALL EXISTING UNDERGROUND UTILITIES AND STRUCTURES BEFORE THE START OF WORK AND TO TAKE WHATEVER STEPS NECESSARY TO PROVIDE FOR THEIR PROTECTION. THE CONTRACTOR SHALL HAND DIG TO LOCATE ALL SHOWN UTILITIES. THE PROFESSIONAL HAS ATTEMPTED TO LOCATE AND INDICATE EXISTING FACILITIES ON THESE PLANS; HOWEVER, THIS INFORMATION IS SHOWN FOR THE CONTRACTOR'S CONVENIENCE ONLY. THE PROFESSIONAL ASSUMES NO RESPONSIBILITY FOR THE LOCATIONS OF UTILITIES SHOWN OR NOT SHOWN. COMPLETENESS OR ACCURACY OF LOCATION AND DEPTH OF UNDERGROUND UTILITES AND STRUCTURES IS NOT GUARANTEED. IF CONFLICTS ARE FOUND THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER AND DESIGN ENGINEER FOR INSTRUCTION BEFORE PROCEEDING WITH WORK.
- 4. THE LOCATION OF EXISTING OVERHEAD UTILITIES SHOWN ON THIS PLAN HAVE BEEN TAKEN FROM FIELD OBSERVATION.








SPHALT

INLET



VAUGHN ST LEWIS EDWARD ST LOCATION MAP

SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO PENNONI ASSOCIATES; AND OWNER

SHALL INDEMNIFY AND HOLD HARMLESS PENNONI

ASSOCIATES FROM ALL CLAIMS, DAMAGES, LOSSES AN

EXPENSES ARISING OUT OF OR RESULTING THEREFRO

CS0901

SHEET 4 OF 21

PROJECT

DRAWING SCALE

DRAWN BY

APPROVED BY

DATE

LINLO20003


2021-03-05


AS SHOWN

CRH/TLR


PGD

Scale: 1" = 1000'









----- 1121 -----1120 1121

1.5%

EXISTING MAJOR CONTOUR EXISTING MINOR CONTOUR PROPOSED MAJOR CONTOUR PROPOSED MINOR CONTOUR SPOT ELEVATION

TOP OF CURB ELEVATION

BOTTOM OF CURB ELEVATION

PROPOSED SLOPE


GRADING PLAN GENERAL NOTES:

- THE CONTRACTOR MUST PERFORM A ONE CALL (1-800-242-1776) AT LEAST THREE (3) WORKING DAYS PRIOR TO PERFORMING ANY CONSTRUCTION ACTIVITIES IN ACCORDANCE WITH ACT 287 - 1974, OR AS AMENDED WITH ACT 287.
- THE EXACT LOCATION AND DEPTH OF ALL UTILITIES MUST BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.
- COORDINATE PAVING LAYOUT WITH SITE PLANS. CONTRACTOR IS TO ADJUST AND/OR CUT EXISTING PAVEMENT AS NECESSARY TO ASSURE A SMOOTH FIT AND CONTINUOUS GRADE.
- ALL UNSURFACED AREAS DISTURBED BY GRADING OPERATIONS ARE TO RECEIVE FOUR INCHES (4") OF TOPSOIL AND SEEDED/MULCHED PER THE E&S PLANS.

PRE-CONSTRUCTION MEETING

CONTRACTOR SHALL CALL TOWNSHIP AT 717-545-4751 TO SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE TOWNSHIP ENGINEER PRIOR TO THE START OF SITE CONSTRUCTION.

INSPECTION DURING CONSTRUCTION




THE TOWNSHIP SHALL INSPECT THE IMPROVEMENTS DURING CONSTRUCTION. THE DEVELOPER SHALL PAY THE COST OF ANY SUCH INSPECTION IN ACCORDANCE WITH THE PROVISIONS OF ARTICLE V OF THE MUNICIPALITIES PLANNING CODE. THE DEVELOPER SHALL PROVIDE AT LEAST TWENTY-FOUR (24) HOURS NOTICE PRIOR TO THE START OF CONSTRUCTION OF ANY IMPROVEMENTS THAT ARE SUBJECT TO INSPECTION. ALL INSPECTIONS OF COMPLETED ITEMS SHALL BE REQUESTED, IN WRITING, AT LEAST FORTY-EIGHT (48) HOURS IN ADVANCE OF THE INSPECTION TIME AND DATE

IT IS GENERALLY REQUIRED THAT THE FOLLOWING PHASES OF SITE CONSTRUCTION HAVE MANDATORY INSPECTION. THIS GENERAL LIST OF PHRASES MAY BE AMENDED BY MUTUAL AGREEMENT OF THE TOWNSHIP AND DEVELOPER WHEN THE SITE REQUIRES SPECIAL CONSTRUCTION PROCEDURES. THE INSPECTION SCHEDULE MUST BE RECORDED WITH THE FINAL PLAN OR SHOWN ON THE APPROVED IMPROVEMENT CONSTRUCTION PLAN.


- A.GENERAL SITE CONSTRUCTION
- 1. UPON COMPLETION OF PRELIMINARY SITE PREPARATION INCLUDING STRIPPING OF VEGETATION, STOCKPILING OF TOPSOIL, AND CONSTRUCTION OF TEMPORARY EROSION AND SEDIMENTATION CONTROL DEVICES.
- 2. UPON COMPLETION OF ROUGH GRADING, BUT PRIOR TO PLACING TOPSOIL, PERMANENT DRAINAGE, OR OTHER SITE DEVELOPMENT IMPROVEMENTS AND GROUND COVERS.
- 3. DURING THE CONSTRUCTION OF PERMANENT STORMWATER MANAGEMENT AND BMP FACILITIES. 4. UPON THE FINAL COMPLETION OF PERMANENT STORMWATER
- MANAGEMENT AND BMP FACILITIES, INCLUDING THE ESTABLISHMENT OF GROUND COVERS AND PLANTINGS.
- 5. AFTER REVIEW OF THE AS-BUILT DRAWINGS, REQUIRED IN THIS CHAPTER, BUT PRIOR TO FINAL RELEASE OF THE FINANCIAL GUARANTEE FOR COMPLETION OF FINAL GRADING, VEGETATIVE CONTROLS REQUIRED BY THE BMP STANDARDS, OR OTHER SITE RESTORATION WORK.


B.IN ADDITION TO THE ABOVE OUTLINED OBSERVATIONS, ADDITIONAL OBSERVATIONS WILL BE MADE AT THE REQUEST OF THE DEVELOPER FOR REDUCTION OF FINANCIAL SECURITIES. RANDOM OBSERVATIONS SHOULD BE MADE AT THE FREQUENCY DESIRED BY THE MUNICIPALITY. AT THE TIME OF ANY OF THE ABOVE LISTED OBSERVATIONS, ALL ONGOING CONSTRUCTION (I.E. STORM DRAINAGE, SANITARY SEWER, WATER, EROSION CONTROL, ETC.) SHOULD ALSO BE CHECKED FOR COMPLIANCE WITH THE APPROVED PLANS AND THE FINDINGS REPORTED. SINCE THE ABOVE INSPECTIONS ARE MANDATORY, IT IS RECOMMENDED THAT REQUESTS FOR REDUCTION OF FINANCIAL GUARANTEE TO BE SUBMITTED TO COINCIDE WITH THE ABOVE INSPECTIONS.



CS1501

SHEET 6 OF 21






	SIZE	ROOT	MATURE SIZE	COMMENTS
				1
	2.5-3" CAL.;12-14' HGT.	B&B	35-40' HGT; 25-30' WD	FULL
	2.5-3" CAL.;12-14' HGT.	B&B	40-60' HGT; 30-40' WD	FULL
	2.5-3" CAL.;12-14' HGT.	B&B	40-60' HGT; 30-40' WD	FULL
	2.5-3" CAL.;12-14' HGT.	B&B	40-60' HGT; 30-40' WD	FULL
	6-7' HGT.	B&B	20-25' HGT; 10-12' WD	FULL; UNIFORM SPECIMENS
	18 - 24" HGT.	#3 CONT.	3-4' HGT; 3-4' WD	FULL; 4.5' SPACING
	24 - 30" HGT.	#3 CONT.	3-4' HGT; 3-4' WD	FULL; 4' SPACING
	24 - 30" HGT.	#3 CONT.	2-3' HGT; 2-3' WD	FULL; 3' SPACING
	30 - 36" HGT.	#5 CONT.	3' HGT; 5-6' WD	FULL; 4.5' SPACING
	18 - 24" HGT.	#3 CONT.	2-3' HGT; 5-6' WD	FULL; 4' SPACING
	24 - 30" HGT.	#3 CONT.	3-4' HGT; 3-4' WD	FULL; 4.5' SPACING
	30 - 36" HGT.	#5 CONT.	6-7' HGT; 6-7' WD	FULL; 6' SPACING
	30 - 36" HGT.	#5 CONT.	5-6' HGT; 5-6' WD	FULL; 4.5' SPACING
	15-18" HGT.	#3 CONT.	3' HGT; 3' WD	3' O.C. SPACING
				•
_	8-12" HGT.	#1 CONT.	15" HGT; 15" WD	18" O.C. SPACING

LANDSCAPE COMPLIANCE SUMMARY					
ODE REF.	DESCRIPTION	REQUIRED QTY	PROVIDED QTY		
	BUFFER YARDS AND SCREENING				
7-2106 (5)	MINIMUM BUFFER WIDTH: 15 FT. ADJACENT TO RESIDENTIAL ZONE OR USE MINIMUM SCREENING: 1 SHADE TREE PER 50 LINEAR FEET AND 1 EVERGREEN TREE PER 40 LINEAR FEET OF BUFFER YARD SCREEN	3 EVERGREEN AND 3 SHADE TREES BASED ON 125 LF FRONTAGE	3 EVERGREEN AND 3 SHADE TREES		
	INTERIOR PARKING LOT LANDSCAPING				
7-2306 (3)D	ONE (1) SHADE TREE PER ISLAND	3 SHADE TREES	3 SHADE TREES		
	STREET TREES				
2-1009 (3)	ONE (1) SHADE TREE FOR EVERY 40 LF OF RIGHT-OF-WAY	12 SHADE TREES BASED ON 451 L.F. OF R.O.W.	12 SHADE TREES		
	PARKING BUFFER				
27-2306	40% OF PARKING BUFFER AREA SHALL BE LANDSCAPED	2680 SF OF PARKING BUFFER x 0.40 = 1072 SF	1170 SF BASED ON 48 LARGE SHRUBS 38 SMALL SHRUBS 12 GRASSES		

LEGEND



PROPOSED SHADE TREE

PROPOSED EVERGREEN TREE

PROPOSED SHRUBS

PROPOSED ORNAMENTAL GRASS

PROPOSED PERENNIALS

SEE SHEET CS6061 FOR LANDSCAPE DETAILS AND NOTES

11 Ш Ŕ S ()RON AN Δ Ш Ш T ⊿ ⊿ Ľ \mathbf{O} Ο S ž AND $\overline{}$ 340^{*} AND S 0 34 ALL DOCUMENTS PREPARED BY PENNONI ASSOCIATES ARE INSTRUMENTS OF SERVICE IN RESPECT OF THE PROJECT. THEY ARE NOT INTENDED OR REPRESENTED TO BE SUITABLE FOR REUSE BY OWNER OR OTHERS O THE EXTENSIONS OF THE PROJECT OR ON ANY OTHER PROJECT. ANY REUSE WITHOUT WRITTEN VERIFICATIO OR ADAPTATION BY PENNONI ASSOCIATES FOR THE SPECIFIC PURPOSE INTENDED WILL BE AT OWNERS SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO PENNONI ASSOCIATES; AND OWNER SHALL INDEMNIFY AND HOLD HARMLESS PENNONI ASSOCIATES FROM ALL CLAIMS, DAMAGES, LOSSES ANI EXPENSES ARISING OUT OF OR RESULTING THEREFROM LINLO20003 PROJECT DATE 2021-03-05 DRAWING SCALE AS NOTED DRAWN BY CRH/TLR

PPROVED BY

CS2001

SHEET 8 OF 21

PGD

S S


Suite

SOCI


AS


215 Mai Mark

0









ANY SINKHOLES ENCOUNTERED DURING CONSTRUCTION SHOULD BE REMEDIATED ON A CASE-BY-CASE BASES. THE GEOTECHNICAL ENGINEER SHOULD BE CONTACTED FOR SITE-SPECIFIC RECOMMENDATIONS IF SINKHOLES ARE OBSERVED. ANY SINKHOLES THAT ARE ENCOUNTERED DURING SITE DEVELOPMENT SHOULD BE REMEDIATED BY CONSTRUCTING AN INVERTED ROCK FILTER PER THE DETAIL SHOWN ON

-SOIL MATERIAL


9" OF FILTER MATERIAL


-18" OF FILTER MATERIAL (R-3 ROCK)

(TYPE A SAND) 9" OF FILTER MATERIAL (AASHTO #57 STONE)


5


CONCRETE CURB NOSE DOWN







NOT TO SCALE
















SEEDING NOTES

ETC.

PLANTING NOTES

- 1. ALL PLANT LOCATIONS SHALL BE STAKED IN THE FIELD AND LOCATIONS APPROVED BY LANDSCAPE ARCHITECT PRIOR TO PLANTING.
- 2. TOPSOIL WITH A QUALITY ORGANIC SOIL AMENDMENT SHALL BE USED FOR ALL PLANTING AND SEEDING OPERATIONS. 3. INSTALL 12" MINIMUM TOPSOIL MIXTURE IN GROUNDCOVER BEDS AND 24" IN SHRUB BEDS AND ISLANDS. 6" OF TOPSOIL
- ARE TO REMAIN ON ALL DISTURBED AREAS TO RECEIVE SOD OR SEED.
- 4. NOTIFY ALL UTILITY COMPANIES AND LOCATE ALL UTILITIES PRIOR TO EXCAVATING PLANT PITS. PLANT LOCATIONS MAY BE ADJUSTED IN THE FIELD TO AVOID INTERFERENCE WITH UNDERGROUND UTILITIES.
- 5. SHOULD ANY DISCREPANCY ARISE BETWEEN THE PLANTING PLAN AND THE PLANTING SCHEDULE, THE DEVELOPER IS RESPONSIBLE FOR THE QUANTITIES SHOWN ON THE LANDSCAPE PLAN.
- 6. ALL PLANT MATERIAL SHALL BE OF NURSERY STOCK QUALITY AS DEFINED BY THE AMERICAN ASSOCIATION OF NURSERYMAN STANDARDS AND SHALL BE FIRST QUALITY NURSERY GROWN STOCK FREE OF DISEASE AND OBJECTIONABLE DISFIGUREMENTS AND PLANTED IN CONFORMANCE WITH SOUND NURSERY PRACTICE AND APPLICABLE CITY STANDARDS.
- 7. ALL NON-BIODEGRADABLE ROOT WRAPPING TO BE REMOVED COMPLETELY BEFORE PLANTING.
- ALL TREES SHALL BE BALLED AND BULLAPED, NURSERY GROWN STOCK.
- 9. ALL PLANT MATERIAL AND LAWNS SHALL BE PLANTED WITHIN THE RECOMMENDED SEASONAL TIME PERIODS A S PRESCRIBED BY ACCEPTED HORTICULTURAL PRACTICE. RECOMMENDED PLANTING TIMES ARE BETWEEN APRIL 15TH THRU MAY 31ST OR AUGUST 17TH THRU OCTOBER 15TH. FALL DIGGING AND TRANSPLANT HAZARD TREE SPECIES (OAKS, ETC.) SHALL BE ONLY BE DUG AND PLANTED IN SPRING.
- 10. ALL PLANT MATERIAL SHALL BE APPROVED UPON ARRIVAL TO THE SITE, UNLESS OTHERWISE NOTIFIED.
- 11. PROPOSED PLANT MATERIAL MAY BE SUBSTITUTED BY SIMILAR PLANTS PRIOR TO INSTALLATION, SUBJECT TO APPROVAL BY THE CITY ENGINEER.
- 12. A TEMPORARY FENCE, SUCH AS SNOW FENCE, SHALL BE ERECTED AT THE PERIMETER OF THE DRIPLINE OF ALL EXISTING VEGETATION INDICATED TO REMAIN. PRIOR TO EXCAVATION, CONSTRUCTION OR SITE WORK. THIS FENCE SHALL BE REMOVED ONLY AT THE TIME OF COMPLETION OF ALL CONSTRUCTION AND FINAL GRADING.
- 13. EXISTING TREES TO BE RELOCATED SHALL BE HANDLED ACCORDING TO ACCEPTABLE HORTICULTURE PRACTICE.
- 14. ALL DISTURBED AREAS NOT SHOWN AS PLANTED OR LAWN SHALL BE TOPSOILED AND SEEDED OR RETURNED TO THEIR ORIGINAL STATE BEFORE DISTURBANCE AS DIRECTED BY THE CITY ENGINEER.
- 15. ALL AREAS NOT RELATED TO HE PROPOSED DEVELOPMENT SHALL REMAIN IN THEIR NATURAL STATE. DISTURBANCE OF EXISTING VEGETATION SHALL BE LIMITED TO WORK AREA AND AS DEFINED ON DWGS. CS0501-04 AND CS8001.
- 16. ADDITIONAL LANDSCAPING APPROVED BY THE CITY ENGINEER SHALL BE PROVIDED BY THE APPLICANT TO REPALCE ANY VEGETATION IN ADVERTENTLY REMOVED OUTSIDE THE LIMIT OF DISTURBANCE LINE AS SHOWN ON THE APPROVED GRADING PLAN DURING CONSTRUCTION.
- 17. PROPOSED TREES SHALL NOT BE PLANTED WITHIN EASEMENTS, DRIVEWAYS AND SITE TRIANGLES. THEREFORE, THE TREE LOCATIONS SHALL BE APPROXIMATE AND SHALL BE ADJUSTED IN THE FIELD AS REQUIRED.
- 18. ALL SHADE TREES IN PEDESTRIAN WALKS AREAS SHALL HAVE AN INITIAL LIMBS PRUNED STARTING AT A MINIMUM OF 7 FT. ABOVE FINISHED GRADE.
- 19. ALL TREES SHALL BE MULCHED WITH A THREE INCH (3") MINIMUM DEPTH OF SHREDDED HARDWOOD BARK.
- 20. PLANTS ARRANGED IN CONTINUOUS GROUPINGS SHALL BE SET IN MULCHED BEDS.
- 21. PLANTING DEBRIS SHALL BE REMOVED FROM THE PROPERTY.
- 22. ANY LIVE TREE WHICH IS SUBSTANTIALLY DAMAGED AS A RESULT FO GRADING OR GENERAL CONSTRUCTION MUST BE REMOVED AND REPLACED WITH ANOTHER TREE OR TREES AS APPROVED BY THE CITY ENGINEER.
- 23. TREE REMOVAL FROM ANY SLOPE OR ENVIRONMENTALLY SENSITIVE AREA IS PROHIBITED IF IT WILL CONTRIBUTE, IN THE OPINION OF THE CITY ENGINEER, TO EXTRA RUNOFF OF SURFACE WATER ONTO ADJOINING PROPERTY AND EROSION AND SILTING, UNLESS OTHER MEANS APPROVED BY THE CITY ENGINEER ARE PROVIDED TO PREVENT RUNOFF AND EROSION.
- 24. NO HEALTHY TREE THAT IS SPECIAL BY VIRTUE OF HISTORY, UNUSUAL SIZE, OR AGE OR OF RAE SPECIES, SHALL BE REMOVED EXCEPT AS MAY BE REQUIRED FOR PROTECTION OF PUBLIC HEALTH, SAFETY AND WELFARE.
- 25. SELECTED EXISTING HEALTHY TREES SIX (6) INCHES IN CALIPER OR LESS MEASURED FOUR (4) FEET ABOVE THE GROUND SHALL BE RELOCATED ON-SITE UNDER THE DIRECTION AND APPROVAL OF THE CITY ENGINEER.
- 26. NEWLY INSTALLED PLANT MATERIAL SHALL BE WATERED AT THE TIME OF PLANTING. REGULAR WATERING SHALL BE PROVIDED TO ENSURE THE ESTABLISHMENT AND REGULAR GROWTH OF PLANTS.
- 27. ALL SHRUBS SPACED 7 FT. O.C. OR CLOSER SHALL BE IN CONTINUOUS MULCHED BEDS.
- 28. SEED ALL DISTURBED AREAS WITH REQUIRED SEED MIX (SEE DWG. CS8501 FOR SEEDING MIX SCHEDULE).
- 29. TREES SHOULD BE PLANTED A MIN. OF FIVE (5) FEET FROM SIDEWALKS UNLESS IN TREE PITS.
- 30. GUY WIRES AND STAKES WILL ONLY BE UTILIZED IF CONDITIONS MERIT AND WILL BE REMOVED BY THE DEVELOPER AT THE END OF THE GUARANTEE PERIOD.

SEE PLANT LIST FOR SPACING
PLANT SPACING DIAGRAM

REMOVE EXCESS SOIL FROM -TOP OF ROOT BALL AND COLLAR; SET BOTTOM OF COLLAR 1 INCH ABOVE ADJACENT GRADE

3" MIN. SHREDDED HARDWOOD MULCH

FOLD DOWN AND/OR REMOVE BURLAP FROM TOP 1/2 OF ROOT-BALL. COMPLETELY REMOVE WIRE BASKETS.

SPECIFIED PLANT MIX: 1/4 COMPOST AND 3/4 TOPSOIL, COMPACT TO 80% AND WATER THOROUGHLY TO ELIMINATE AIR POCKETS.

EVERGREEN
NOT TO SCALE

NOT TO SCALE

1. SEED ALL AREAS DISTURBED BY CONSTRUCTION NOT OTHERWISE CONTAINING PLANTING BEDS, SIDEWALKS, BUILDINGS,

2. BEFORE SEEDING, CONTRACTOR SHALL PROVIDE SOIL TESTS AND INCORPORATE NECESSARY SOIL AMENDMENTS PER SOIL TEST RECOMMENDATIONS.

3. PERFORM ALL FINISH GRADING, WITHIN AREAS OF DISTURBANCE, NECESSARY TO BRING SITE TO REQUIRED FINISHED ELEVATIONS. FINISH GRADING SHALL CONSIST OF PREPARING SUBGRADE AND SPREADING TOPSOIL READY FOR SEEDING OPERATIONS.

4. TOPSOIL SHALL BE UNIFORMLY SPREAD IN DISTURBED AREAS WITH BLADE GRADER, OR BY ANY OTHER APPROVED METHOD, TO A MINIMUM DEPTH OF 6 INCHES TO PERMIT 1 INCH OF SETTLEMENT. CORRECT ANY SURFACE IRREGULARITIES TO PREVENT FORMATION OF LOW SPOTS AND POCKETS THAT WOULD RETAIN WATER. PRIOR TO FINE GRADING, REMOVE ALL EXISTING ANNUAL TYPE VEGETATION.

5. SOW SEED AT THE RECOMMENDED SEEDING RATE AS SHOWN IN THE SEEDING MIX SCHEDULE AS NOTED ON EROSION CONTROL PLANS.

6. SEED SHALL BE APPLIED APRIL 15TH THRU MAY 31ST OR AUGUST 17TH THRU OCTOBER 15TH.

7. ON ALL SLOPES 3:1 OR GREATER, USE AN ORGANIC SOIL STABILIZER SUCH AS 'CON-TACK' OR EQUAL AT THE RATE OF 25 LBS PER 1,000 GALLONS OR AT RATES RECOMMENDED BY THE MANUFACTURER.

8. KEEP NEWLY SEEDED GRASS AREAS MOISTENED DURING SEED GERMINATION AND UNTIL THE GRASS COVERS AT LEAST 75% OF THE SEEDED AREAS TO A HEIGHT OF 2 TO 3 INCHES.

9. ALL AREAS AND SPOTS, WHICH DO NOT SHOW A PROMPT CATCH OF GRASS, SHALL THEN BE RE-SEEDED. AND THE OPERATION REPEATED UNTIL COMPLETE COVERAGE IS OBTAINED.

10. SEE DWG. CS8501 FOR SEEDING SPECIFICATIONS AND RATES.

LANDSCAPE MAINTENANCE NOTES

PLANT MATERIAL GUARANTEE

MAINTENANCE

ALL PLANT MATERIAL SHALL BE GUARANTEED FOR ONE (1) YEAR BY THE CONTRACTOR TO BE IN HEALTHY AND VIGOROUS CONDITION FROM THE DATE OF ACCEPTANCE LANDSCAPE ARCHITECT, OWNER AND CITY INSPECTOR. ANY AND ALL PLANT MATERIAL THAT DIES OR FAILS TO THRIVE SHALL BE IMMEDIATELY REPLACED WITH LIKE SPECIES. IT IS UNDERSTOOD THAT THE CONTRACTOR WILL PROVIDE ADEQUATE AND TIMELY CARE DURING THE GUARANTEE PERIOD TO THE HIGHEST HORTICULTURAL STANDARDS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF SITE VEGETATION DURING THE GUARANTEE PERIOD TO INCLUDE BUT NOT BE LIMITED TO:

1. FERTILIZER: SPRING AND FALL FERTILIZER APPLICATIONS.

2. PRUNING: PRUNING SHALL BE LIMITED OR REMOVAL OF DEAD WOOD OR BRANCHES FOR TREES OR FOR SIGHT DIFFERENCES/SAFETY REASONS. PRUNING OF SHRUBS AND TREES SHALL BE LIMITED TO THE PRUNING NECESSARY TO MAINTAIN THE NATURAL SHAPE OF THE PLANT EXCEPT FOR SHEARED HEDGES.

3. PEST CONTROL: PRE-EMERGENT WEED CONTROL FOR MOWN LAWNS AND SHRUB BEDS MAY BE APPLIED IN FEBRUARY. CHEMICAL TREATMENT FOR INSECT INFESTATION AND DISEASE MAY BE APPLIED AND SHALL BE SPECIFIC TO THE PROBLEM.

4. MULCHING: MULCHING SHALL BE MAINTAINED AT A DEPTH OF 3" IN PLANT BEDS AND AROUND BASE OF TREES.

5. MOWING: MOWN LAWN SEED MIX SHALL BE MOWN AT REGULAR INTERVALS THROUGHOUT THE GROWING SEASON. GRASS HEIGHT SHOULD NOT EXCEED 4 INCHES BEFORE CUTTING. MOWER BLADES SHALL BE SET AT 3 INCHES UNLESS OTHERWISE DIRECTED.

6. PLANT PROTECTION: AVOID EXCESS INTRUSION INTO THE ROOT ZONE AREA OF ESTABLISHED PLANTINGS.

7. WATERING: UNLESS STATED OTHERWISE IN THESE DOCUMENTS, PROVIDE APPROXIMATELY 1-INCH OF RAINFALL/WATER PER WEEK THROUGHOUT THE GROWING SEASON FOR THE FIRST YEAR.

PERENNIAL AND GROUNDCOVER MAINTENANCE

1. WEED CONTROL CAN BE A PROBLEM UNTIL THE GROUNDCOVERS/ PERENNIALS HAVE SPREAD AND FILLED IN THE AREA. CONTROL OF PERSISTENT, PERENNIAL WEEDS, SUCH AS BERMUDAGRASS AND NUTGRASS SHOULD BE ACHIEVED BEFORE PLANTING. USE A NONSELECTIVE HERBICIDE, SUCH AS ROUNDUP. A MULCH APPLIED AFTER PLANTING AND REPLENISHED AS NEEDED TO MAINTAIN A DEPTH OF 3 INCHES WILL REDUCE THE NEED TO WEED BY HAND. PRE-EMERGENCE HERBICIDES CAN BE USED ON MANY TYPES OF GROUNDCOVER TO AID WEED CONTROL; READ THE LABEL CAREFULLY BEFORE APPLYING. AS THE GROUNDCOVER FILLS IN WEEDS WILL BECOME LESS OF A PROBLEM BECAUSE OF THE SHADED SOIL. SOME HAND WEEDING WILL MOST LIKELY BE NEEDED.

2. FERTILIZER - MOST GROUNDCOVERS WILL BENEFIT FROM AN APPLICATION OF FERTILIZER IN LATE WINTER TO EARLY SPRING. USE 2 TO 4 POUNDS OF A COMPLETE FERTILIZER PER 1,000 SQUARE FEET. WATER OR BRUSH FERTILIZER OFF THE FOLIAGE AFTER BROADCASTING.

NOTES:

1. USE DIGGING FORK NOT SPADE TO PREVENT **GLAZING OF PIT EDGES**

- PRUNE DEAD AND DAMAGED BRANCHES IN 2. ACCORDANCE WITH RECOGNIZED HORTICULTURAL PRACTICES.
- DO NOT PRUNE LEADER
- SET PLANTS PLUMB AND FACE TO GIVE THE BEST APPEARANCE OR RELATIONSHIP TO ADJACENT AREAS
- COMPLETELY REMOVE ALL TREE WRAP AFTER INSTALLATION
- ONLY STAKE TREES OVER 8 FT. HEIGHT OR ON **SLOPES GREATER THAN 4:1**
- ALL NON-BIODEGRADABLE MATERIALS INCLUDING WIRE BASKETS SHALL BE REMOVED COMPLETELY FROM THE ROOTBALL


BREAK DOWN SIDES OF PLANTING PIT WHEN BACKFILLING

PLANT TO BE PLACED ON UNDISTURBED SUBGRADE.

NOTES:


- 1. USE DIGGING FORK NOT SPADE TO


- THE BEST APPEARANCE OR
- AFTER INSTALLATION
- REMOVED COMPLETELY FROM THE




NOT TO SCALE

TREE PLANTING









ROCK CONSTRUCTION ENTRANCE INLET PROTECTION EROSION CONTROL MATTING

NOTE: THESE PLANS INDICATE CRITICAL AREAS FOR EROSION AND SEDIMENTATION CONTROL PLACEMENT BUT DO NOT RELIEVE THE CONTRACTOR FROM PROVIDING ADDITIONAL CONTROLS AS SITE CONDITIONS WARRANT. THE ENVIRONMENTAL COMPLIANCE MANAGER FOR THE PROJECT AND/OR CONSERVATION DISTRICT MAY DIRECT THE CONTRACTOR TO INSTALL E&S BMPS NOT DEPICTED ON THESE DRAWINGS IN ORDER TO PROTECT DOWN GRADIENT AREAS FROM EROSION AND SEDIMENTATION DURING CONSTRUCTION.

3405 AND 3401 NORTH FROM SILES VENTICED & ALL DIMENSIONS MUST BE VERTIFIED BY CONTRACTOR SUSCIENTANIA TOWNELLE SUSCIENTANIA TOWNELLE SUSCIENTANIA TOWNELLE SUSCIENTANIA TOWNELLE SUSCIENTANIA TOWNELLE SUSCIENTANIA TOWNELLE SUSCIENTANIA		Pennoni		PENNONI ASSOCIATES INC.	5072 Ritter Road, Suite 102 Mechanicshirg PA 17055	T 717.975.6481 F 717.975.6480
QN 505E QN NOISOUS QN 100 SOUS QN NOISOUS QN 100 SOUS QN 100 SOUS PROJECT LINLO20003 DATE 2021-03-05 DATE AS SHOWN	ALL DIMENSIONS MUST BE VERIFIED BY CONTRACTOR AND OWNER MUST BE NOTIFIED OF ANY DISCREPANCIES BEFORE PROCEEDING WITH WORK	P	PROF			
Image:	_	SUSQUEHANNA TOWNSHIP DAUPHIN COUNTY, PENNSYLVANIA	EROSION AND SEDIMENTATION CONTROL PLAN			LEMOYNE, PENNSYLVANIA 17043
Image: Sector						BY
ALL DOCUMENTS PREPARED BY PENNONI ASSOCIATES ARE INSTRUMENTS OF SERVICE IN RESPECT OF THE PROJECT. THEY ARE NOT INTENDED OR REPRESENTED TO BE SUITABLE FOR REUSE BY OWNER OR OTHERS ON THE EXTENSIONS OF THE PROJECT OR ON ANY OTHER PROJECT. ANY REUSE WITHOUT WRITTEN VERIFICATION OR ADAPTATION BY PENNONI ASSOCIATES FOR THE SPECIFIC PURPOSE INTENDED WILL BE AT OWNERS SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO PENNONI ASSOCIATES; AND OWNER SHALL INDEMNIFY AND HOLD HARMLESS PENNONI ASSOCIATES FROM ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES ARISING OUT OF OR RESULTING THEREFROM. PROJECT LINLO20003 DATE 2021-03-05 DRAWING SCALE AS SHOWN						REVISIONS
ARE INSTRUMENTS OF SERVICE IN RESPECT OF THE PROJECT. THEY ARE NOT INTENDED OR REPRESENTED TO BE SUITABLE FOR REUSE BY OWNER OR OTHERS ON THE EXTENSIONS OF THE PROJECT OR ON ANY OTHER PROJECT. ANY REUSE WITHOUT WRITTEN VERIFICATION OR ADAPTATION BY PENNONI ASSOCIATES FOR THE SPECIFIC PURPOSE INTENDED WILL BE AT OWNERS SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO PENNONI ASSOCIATES; AND OWNER SHALL INDEMNIFY AND HOLD HARMLESS PENNONI ASSOCIATES FROM ALL CLAIMS, DAMAGES, LOSSES AND PROJECT LINLO200003 DATE 2021-03-05 DRAWING SCALE AS SHOWN						DATE
DATE 2021-03-05 DRAWING SCALE AS SHOWN	ARE INST PROJECT. TO BE SUIT THE EXTE PROJECT. OR ADAF SPECIFIC SOLE EXPOSU SHALL I ASSOCIATE	TRUMENTS THEY ARE TABLE FOP NSIONS O ANY REUS PTATION B C PURPOS RISK AND IRE TO PE NDEMNIFY ES FROM /	S OF SERVIC E NOT INTEN R REUSE BY F THE PROJ SE WITHOUT Y PENNONI Y PENNONI WITHOUT L NNONI ASSC (AND HOLD ALL CLAIMS,	CE IN RESPENDED OR RE OWNER OF IECT OR ON WRITTEN N ASSOCIATE UWILL BE A JABILITY OF OCIATES; AN HARMLESS DAMAGES,	ECT OF 1 PRESEI ANY OT /ERIFIC/ S FOR 1 T OWNE & LEGAL D OWN PENNO LOSSES	THE NTED SON HER ATION THE RS ER NI S AND
			LI			
	DRAWING S	3CALE			HOW	'N

SHEET 14 OF 21

STANDARD EROSION AND SEDIMENT CONTROL PLAN **NOTES**

- 1. NOTIFY THE DAUPHIN COUNTY CONSERVATION DISTRICT TEN (10) WORK DAYS IN ADVANCE OF ANY EARTH DISTURBANCE ACTIVITIES AT THE UTILITY LINE INSTALLATION REQUIREMENTS FOLLOWING ADDRESS: DAUPHIN COUNTY CONSERVATION DISTRICT EXPOSED TRENCH EXCAVATIONS HAVE HIGH POTENTIAL FOR ACCELERATED EROSION AND SEDIMENT POLLUTION. SINCE THESE 1451 PETERS MOUNTAIN ROAD EXCAVATIONS ARE USUALLY LOCATED AT LOWER ELEVATIONS ALONG OR ACROSS EARTH DISTURBANCE SITED. OPEN TRENCHES DAUPHIN, PA 17018 SERVE TO CONCENTRATE SEDIMENT-LADEN RUNOFF AND CONVEY IT TO SITE BOUNDARIES OR WATERWAYS. THE MOST IMPORTANT TELEPHONE: 717-921-8100 EROSION AND SEDIMENT POLLUTION CONTROL CONSIDERATION FOR TRENCH CONSTRUCTION IS THE LIMITING AND SPECIFIC SCHEDULING OF WORK ACTIVITIES. 2. CONTRACTORS INVOLVED IN ANY EARTH DISTURBANCE ACTIVITIES SHALL NOTIFY THE PENNSYLVANIA ONE-CALL SYSTEM, INCORPORATED, AT 1-800-242-1776, TO LOCATE BURIED UTILITIES. 2. ADVANCED CLEARING AND GRUBBING OPERATIONS FOR STRIP UTILITY LINE INSTALLATIONS SHALL BE LIMITED TO A DISTANCE EQUAL 3. EARTH MOVING STOCKPILE HEIGHTS MUST NOT EXCEED 35 FEET; EARTH MOVING STOCKPILE SLOPES MUST BE 2H:1V OR FLATTER. TO TWO TIMES THE LENGTH OF PIPE INSTALLATION THAT CAN BE COMPLETED IN ONE DAY. 4. CONTRACTOR SHALL ASSURE THAT THE APPROVED EROSION AND SEDIMENT (E&S) CONTROL PLAN IS PROPERLY AND COMPLETELY 3. DAILY TRENCH EXCAVATION SHALL BE LIMITED TO THE LENGTH OF PIPE PLACEMENT, PLUG INSTALLATION AND BACKFILLING THAT CAN IMPLEMENTED. BE COMPLETED THE SAME DAY. ENVIRONMENT PROTECTION POLICY "MANAGEMENT OF FILL". UNTIL THE SITE ACHIEVES FINAL STABILIZATION. CONTRACTOR SHALL ASSURE THAT THE BEST MANAGEMENT PRACTICES (BMPs) ARE IMPLEMENTED, OPERATED, AND MAINTAINED PROPERLY AND COMPLETELY. MAINTENANCE SHALL INCLUDE INSPECTIONS OF ALL BEST 4. TRENCH PLUGS WILL BE SPACED AND CONSTRUCTED IN ACCORDANCE TO THE DETAILS SHOWN ON PLANS. THE PLUGS MAY BE MANAGEMENT PRACTICE FACILITIES AND MAINTAIN AND MAKE AVAILABLE TO THE DAUPHIN COUNTY CONSERVATION DISTRICT COMPLETE, TEMPORARILY REMOVED WHEN PLACING THE PIPE, BUT THEN REPLACED. WRITTEN INSPECTION LOGS OF ALL THOSE INSPECTIONS. ALL MAINTENANCE WORK, INCLUDING CLEANING, REPAIR, REPLACEMENT. REGRADING, AND RESTABILIZATION SHALL BE PERFORMED IMMEDIATELY 5. WATER WHICH ACCUMULATES IN THE OPEN TRENCH MUST BE COMPLETELY REMOVED BY PUMPING INTO A FILTER BAG, PRIOR TO PIPE PLACEMENT OR BACKFILLING OPERATIONS. IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.) POLLUTION, CONTRACTOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION. (EXAMPLE, THE IMPLEMENTATION OF SILT FENCE SHOULD A SECTION OF COMPOST FILTER SOCK BE ON THE DAY FOLLOWING PIPE PLACEMENT AND TRENCH BACKFILLING, THE DISTURBED AREA SHALL BE GRADED TO FINAL CONTOURS DAMAGED.) AND APPROPRIATE TEMPORARY EROSION AND SEDIMENT POLLUTION CONTROL MEASURES/FACILITIES WILL BE INSTALLED. SEEDING AND MULCHING OF ALL DISTURBED AREAS WILL BE DONE AT THE END OF EACH WEEK. BEFORE INITIATING ANY REVISIONS TO THE APPROVED EROSION AND SEDIMENT CONTROL PLAN OR REVISIONS TO OTHER PLANS WHICH MAY A. EXCEPTIONS - IN CERTAIN CASES, TRENCHES CANNOT BE BACKFILLED UNTIL THE PIPE IS HYDROSTATICALLY TESTED, OR ANCHORS AFFECT THE EFFECTIVENESS OF THE APPROVED E&S CONTROL PLAN, CONTRACTOR MUST RECEIVE APPROVAL OF THE REVISIONS FROM THE AND OTHER PERMANENT FEATURES ARE INSTALLED. IN THESE CASES, ALL OF THE REQUIREMENTS LISTED UNDER ITEM B. WILL APPLICABLE. DAUPHIN COUNTY CONSERVATION DISTRICT REMAIN IN EFFECT WITH THE FOLLOWING BEING AMENDED: B. DAILY BACKFILLING OF THE TRENCH MAY BE DELAYED FOR SIX DAYS. ALL PRESSURE TESTING AND THE COMPLETE BACKFILLING 8. CONTRACTOR SHALL ASSURE THAT AN EROSION AND SEDIMENT CONTROL PLAN HAS BEEN PREPARED, APPROVED BY THE DAUPHIN COUNTY OF THE OPEN TRENCH MUST BE COMPLETED BY THE SEVENTH WORKING DAY. CONSERVATION DISTRICT, AND IS BEING IMPLEMENTED AND MAINTAINED FOR ALL SOIL AND/OR ROCK SPOIL AND BORROW AREAS. SUBSTANCE HAS OCCURRED. REGARDLESS OF THEIR LOCATIONS. C. IF DAILY BACKFILLING IS DELAYED. THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS. APPROPRIATE TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES/FACILITIES WILL BE INSTALLED, AND THE AREAS SEEDED AND MULCHED WITHIN THE 9. ALL PUMPING OF SEDIMENT LADEN WATER SHALL BE THROUGH A SEDIMENT CONTROL BEST MANAGEMENT PRACTICE (BMP), SUCH AS A **DESIGN APPROACH** NEXT TWO CALENDAR DAYS. PUMPED WATER FILTER BAG DISCHARGING OVER NON-DISTURBED AREAS. 7. STREAM OR WETLAND CROSSINGS: THERE ARE NO PROPOSED STREAM OR WETLAND CROSSINGS ASSOCIATED WITH THIS PROJECT. 10. CONTRACTOR IS ADVISED TO BECOME THOROUGHLY FAMILIAR WITH THE PROVISIONS OF APPENDIX 64, EROSION CONTROL RULES AND 1. MINIMIZES EXTENT AND DURATION OF EARTH DISTURBANCE: REGULATIONS, TITLE 25, PART 1, PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION, SUBPART C, PROTECTION OF NATURAL GENERAL CONSTRUCTION SEQUENCE RESOURCES, ARTICLE III, WATER RESOURCES, CHAPTER 102, EROSION CONTROL. 11. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN MUST BE AVAILABLE AT THE PROJECT SITE AT ALL TIMES. THE GENERAL SEQUENCE OF EARTHMOVING ACTIVITIES FOR THE CONSTRUCTION OF THE BMP IS AS FOLLOWS 2. MAXIMIZING THE PROTECTION OF EXISTING DRAINAGE FEATURES AND EXISTING VEGETATION 12. ONLY LIMITED DISTURBANCE WILL BE PERMITTED TO PROVIDE ACCESS FOR GRADING AND ACQUIRING BORROW TO CONSTRUCT THOSE BMPS DO NOT CLEAR AND GRUB THE PROJECT SITE UNTIL THE PERIMETER SEDIMENT CONTROLS ARE INSTALLED OR CONSTRUCTED AND DRAINAGE AREAS AND VEGETATION, AND PROTECT EXISTING DRAINAGE FEATURES. 13. EROSION AND SEDIMENT CONTROL BMPs MUST BE CONSTRUCTED, STABILIZED, AND FUNCTIONAL BEFORE SITE DISTURBANCE BEGINS WITHIN FUNCTIONAL. THE TRIBUTARY AREAS OF THOSE BMPs. SCHEDULE AND ATTEND REQUIRED PRE-CONSTRUCTION MEETING AS STATED PREVIOUSLY 14. AFTER FINAL SITE STABILIZATION HAS BEEN ACHIEVED, TEMPORARY EROSION AND SEDIMENT BMP CONTROLS MUST BE REMOVED. AREAS DISTURBED DURING REMOVAL OF THE BMPs MUST BE STABILIZED IMMEDIATELY. NON-DISCHARGE ALTERNATIVES ARE PROPOSED. 2. FIELD MARK THE LIMITS OF DISTURBANCE. 15. AT LEAST SEVEN (7) WORK DAYS BEFORE EARTH DISTURBANCE ACTIVITIES, THE CONTRACTOR SHALL UNITE THE LANDOWNER, ALL APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND SEDIMENT CONTROL PLAN PREPARER, AND DAUPHIN COUNTY CONSERVATION 3. INSTALL FILTER BAG INLET PROTECTION AT ALL EXISTING STORM SEWER INLETS AS SHOWN ON THE PLANS **TOPSOIL APPLICATION** DISTRICT TO AN ON-SITE MEETING. ALSO, AT LEAST THREE (3) WORK DAYS BEFORE STARTING ANY EARTH DISTURBANCE ACTIVITIES, ALL CONTRACTORS INVOLVED IN THOSE ACTIVITIES SHALL NOTIFY PENNSYLVANIA ONE CALL SYSTEM INCORPORATED AT 1-800-242-1776 FOR BURIED UTILITIES LOCATIONS. INSTALL THE ROCK CONSTRUCTION ENTRANCE(S) AS SHOWN ON THE PLANS. 16. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE PROVIDED SEQUENCE, EACH STAGE SHALL BE COMPLETED TO THE SURFACE AREAS AND TO PROVIDE A ROUGHENED SURFACE TO PREVENT TOPSOIL FROM SLIDING DOWN SLOPE. 5. INSTALL THE COMPOST FILTER SOCK AT THE LOCATIONS SHOWN ON THE PLANS. BEFORE ANY FOLLOWING STAGE IS INITIATED. CLEARING AND GRUBBING SHALL BE LIMITED ONLY TO THOSE AREAS DESCRIBED IN EACH STAGE. 17. IMMEDIATELY AFTER EARTH DISTURBANCE ACTIVITIES CEASE, CONTRACTOR SHALL STABILIZE ANY AREAS DISTURBED BY THE ACTIVITIES. DURING NON-GERMINATING PERIODS, MULCH MUST BE APPLIED AT THE SPECIFIED RATES. DISTURBED AREAS WHICH ARE NOT AT FINISHED DEMOLISH OR SALVAGE ALL ITEMS DEPICTED ON THE DEMOLITION PLANS. GRADE AND WHICH WILL BE REDISTURBED WITHIN ONE (1) YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE TEMPORARY VEGETATIVE STABILIZATION SPECIFICATIONS. DISTURBED AREAS WHICH ARE AT FINISHED GRADE OR WHICH WILL NOT BE REDISTURBED WITHIN ONE (1) UNDER THE SUPERVISION OF THE DESIGN PROFESSIONAL, CONSTRUCT THE PROPOSED UNDERGROUND DETENTION SYSTEM, OUTLET YEAR MUST BE STABILIZED IN ACCORDANCE WITH THE PERMANENT VEGETATIVE STABILIZATION SPECIFICATIONS. STRUCTURE, AND OUTLET PIPE AS SHOWN ON THE PLANS. COORDINATE AND ACCOUNT FOR UTILITY LINES THAT ARE TO REMAIN ACTIVE DURING CONSTRUCTION. 18. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND 8. STRIP ANY EXISTING TOPSOIL AND SPOIL ONSITE OR AT A STOCKPILE AT A PERMITTED LOCATION OFF-SITE AT THE CONVENIENCE OF SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS. THE CONTRACTOR. ANY OFF SITE BORROW/FILL AREAS MUST BE APPROVED BY THE DAUPHIN COUNTY CONSERVATION DISTRICT PRIOR COMPACTED SOILS SHOULD BE SCARIFIED 6 TO 12 INCHES ALONG CONTOUR WHEREVER POSSIBLE PRIOR TO SEEDING TO USE 19. HAY OR STRAW MULCH MUST BE APPLIED AT 3.0 TONS PER ACRE 20. MULCH WITH MULCH CONTROL NETTING OR EROSION CONTROL BLANKETS MUST BE INSTALLED ON ALL SLOPES 3H:1V AND STEEPER, IF 9. INSTALL NEW UTILITY SYSTEMS AS SHOWN ON THE DRAWINGS. APPLICABLE 21. CLEAN STRAW MULCH SHALL BE APPLIED IN LONG STRANDS, NOT CHOPPED OR FINELY BROKEN. 10. PERFORM THE GRADING FOR THE PROPOSED BUILDING AND DRIVEWAYS 22. UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENT CONTROL BMPs MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE 11. CONSTRUCT THE PROPOSED BUILDING. INSPECTIONS OF ALL EROSION AND SEDIMENT CONTROL BMPs AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING, MUST BE PERFORMED IMMEDIATELY. IF EROSION AND SEDIMENT CONTROL BMPs FAIL TO PERFORM AS EXPECTED, REPLACEMENT BMPs, OR 12. REMOVED AND PROPERLY DISPOSE OF THE ACCUMULATED SEDIMENT ON-SITE AS NEEDED OR OFF-SITE TO A PERMITTED SITE MODIFICATIONS OF THOSE INSTALLED SHALL BE REQUIRED. 23. SEDIMENT REMOVED FROM BMPs SHALL BE DISPOSED OF IN LANDSCAPED AREAS OUTSIDE OF STEEP SLOPES, WETLANDS, FLOOD PLAINS OR 13. COMPLETE THE FINAL GRADING AND FINAL LANDSCAPING. DRAINAGE SWALES AND IMMEDIATELY STABILIZED, OR PLACED IN TOPSOIL STOCKPILES. 14. WHEN THE PERMANENT VEGETATION HAS REACHED A MINIMUM 70% PERENNIAL VEGETATIVE COVER, REMOVE THE SEDIMENT 24. CONTRACTOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH THE CONTROL DEVICES. PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET SEQ., 271.1 ET SEQ., AND 287.1 ET SEQ. CONTRACTOR SHALL NOT ILLEGALLY BURY, DUMP, OR DISCHARGE ANY BUILDING MATERIAL OR WASTES AT THE SITE 15. PERMANENTLY STABILIZE ANY AREAS DISTURBED BY THE SEDIMENT CONTROL DEVICES. 25. ANY SEDIMENT THAT IS TRACKED ONTO THE ROADWAY MUST BE CLEANED OFF BEFORE THE END OF THE DAY. CONTRACTOR MUST INSTRUCT DRIVERS OF ALL VEHICLES TO REMOVE SOIL AND LOOSE MATERIAL FROM THEIR WHEELS AND UNDERCARRIAGES WHEN LEAVING THE WORK **WASTE MANAGEMENT & DISPOSAL** AREA. CONTRACTOR MUST REMOVE ALL SOIL, MISCELLANEOUS DEBRIS OR OTHER MATERIAL SPILLED, DUMPED, OR OTHERWISE DEPOSITED ON **SPECIFICATIONS** PUBLIC STREETS, HIGHWAYS, SIDEWALKS, OR OTHER PUBLIC THOROUGHFARES BY VEHICLES IN TRANSIT TO AND FROM THE WORK AREA. 26. FAILURE TO CORRECTLY INSTALL E&S BMPS, FAILURE TO PREVENT SEDIMENT-LADEN RUNOFF FROM LEAVING THE CONSTRUCTION SITE, OR ALL BUILDING MATERIALS AND WASTES SHALL BE REMOVED FROM THE SITE AND RECYCLED OR DISPOSED OF IN ACCORDANCE WITH THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 FOR TEMPORARY MEASURES FAILURE TO TAKE IMMEDIATE CORRECTIVE ACTION TO RESOLVE FAILURE OF E&S BMPS MAY RESULT IN ADMINISTRATIVE, CIVIL, AND/OR CRIMINAL PENALTIES BEING INSTITUTED BY THE DEPARTMENT AS DEFINED IN SECTION 602 OF THE PENNSYLVANIA CLEAN STREAMS LAW. THE CLEAN ET SEQ., 271.1, AND 287.1 ET. SEQ. NO BUILDING MATERIALS OR WASTES OR UNUSED BUILDING MATERIALS SHALL BE BURNED, BURIED. STREAMS LAW PROVIDES FOR UP TO \$10,000 PER DAY IN CIVIL PENALTIES, UP TO \$10,000 IN SUMMARY CRIMINAL PENALTIES, AND UP TO \$25,000 IN DUMPED, OR DISCHARGED AT THE SITE. SEED FORMULA: PENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PENNDOT) FORMULA E MISDEMEANOR CRIMINAL PENALTIES FOR EACH VIOLATION. 2. INDIVIDUALS RESPONSIBLE FOR EARTH DISTURBANCE ACTIVITIES MUST ENSURE THAT PROPER MECHANISMS ARE IN PLACE TO CONTROL WASTE MATERIALS. PROPER HOUSEKEEPING, MATERIAL MANAGEMENT AND LITTER CONTROL MEASURES MUST BE PLANNED 27. THERE IS POTENTIAL POLLUTION DUE TO ACCELERATED EROSION AND THE PROPOSED E&S BMPS ARE DESIGNED IN COMPLIANCE WITH DEP AND IMPLEMENTED. 1. APPLY FORMULA E: 100% ANNUAL RYEGRASS SEED AT 10.0 LB./1000 SQ.YD GUIDELINES TO PROTECT AGAINST THIS POTENTIAL. THESE BMPS INCLUDE COMPOST FILTER SOCK, INLET PROTECTION, CONCRETE WASHOUT, WASTE MATERIALS FROM THIS SITE ARE ANTICIPATED TO INCLUDE, BUT ARE NOT LIMITED TO ROCKS, ROOTS, AND STUMPS. BULK 2. APPLY HAY OR STRAW MULCH AT 3 TONS PER ACRE AND A ROCK CONSTRUCTION ENTRANCE. CONSTRUCTION WASTE MUST BE DISPOSED OF OFF-SITE AT A PERMITTED LOCATION. 3. PERFORM SEEDING BETWEEN MARCH 15 AND OCTOBER 15. **SEQUENCE OF EARTHMOVING OPERATIONS** 4. ALL OFF-SITE WASTE AND BORROW AREAS MUST HAVE AN EROSION AND SEDIMENT (E&S) CONTROL PLAN APPROVED BY DAUPHIN COUNTY CONSERVATION DISTRICT OR THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION FULLY IMPLEMENTED FOR PERMANENT MEASURES PRIOR TO BEING ACTIVATED. 1. ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE FOLLOWING SEQUENCE. EACH STAGE WILL BE COMPLETED IN CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ANY MATERIAL BROUGHT ON SITE IS CLEAN FILL. PENNSYLVANIA DEPARTMENT OF COMPLIANCE WITH PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION CHAPTER 102 REGULATIONS BEFORE ANY FOLLOWING ENVIRONMENTAL PROTECTION FORM FP-001 MUST BE RETAINED BY THE PROPERTY OWNER FOR ANY FILL MATERIAL AFFECTED BY A FOR SLOPES 3H:1V or FLATTER-STAGE IS INITIATED. SPILL OR RELEASE OF A REGULATED SUBSTANCE BUT QUALIFYING AS CLEAN FILL DUE TO ANALYTICAL TESTING. 6. ALL WATER PUMPING FROM ANY WORK AREA SHALL BE DONE ACCORDING TO THE PROCEDURE DESCRIBED IN THIS PLAN, OVER AT LEAST SEVEN (7) WORK DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, INCLUDING CLEARING AND GRUBBING, SEED FORMULA: PENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PENNDOT) FORMULA E UNDISTURBED VEGETATED AREAS. CONTRACTOR SHALL INVITE ALL SUB-CONTRACTORS, THE PROJECT OWNER, APPROPRIATE MUNICIPAL OFFICIALS, THE EROSION AND CONSTRUCTION ACTIVITY WASH WATER AND SANITARY WASTE SHALL NOT BE DISCHARGED TO THE STORMWATER SYSTEM NOR SHALL SEDIMENT (E&S) CONTROL PLAN PREPARER, THE POLLUTION CONTROL AND SEDIMENT MANAGEMENT (PCSM) PLAN PREPARER, THE LICENSED PROFESSIONAL RESPONSIBLE FOR OVERSIGHT OF CRITICAL STAGES OF IMPLEMENTATION OF THE PCSM PLAN, AND A REPRESENTATIVE FROM IT BE PERMITTED TO FLOW OVERLAND TO RECEIVING WATERS. 1. 20% PERENNIAL RYEGRASS MIXTURE AT 4.0 LB./SQ. YD SEDIMENT TRACKED ONTO ANY PUBLIC ROADWAY OR SIDEWALK SHALL BE RETURNED TO THE CONSTRUCTION SITE BY THE END OF DAUPHIN COUNTY CONSERVATION DISTRICT TO AN ON-SITE PRE-CONSTRUCTION MEETING. 30% CREEPING RED FESCUE OR CHEWINGS FESCUE AT 6.0 LB/SQ. YD EACH WORK DAY AND DISPOSED IN THE MANNER DESCRIBED IN THIS PLAN. IN NO CASE SHALL THE SEDIMENT BE WASHED, SHOVELED, AT LEAST THREE (3) WORK DAYS PRIOR TO STARTING ANY EARTH DISTURBANCE ACTIVITIES, OR EXPANDING INTO AN AREA PREVIOUSLY 50% KENTUCKY BLUEGRASS MIXTURE AT 11.0 LB/SQ. YD OR SWEPT INTO ANY ROADSIDE DITCH, STORM SEWER, OR SURFACE WATER. UNMARKED, CONTRACTOR SHALL NOTIFY THE PENNSYLVANIA ONE CALL SYSTEM INC. AT 1-800-242-1776 FOR THE LOCATION OF EXISTING 9. ALL SEDIMENT REMOVED FROM BEST MANAGEMENT PRACTICES (BMPs) SHALL BE DISPOSED OF IN THE MANNER DESCRIBED ON THE 2. APPLY GROUND LIMESTONE AT 800 LBS PER ACRE. UNDERGROUND UTILITIES. PLAN DRAWINGS. 3. APPLY FERTILIZER (10-10-20) AT 140 POUNDS PER 1000 SQUARE YARDS. CONCRETE WASH WATER SHALL BE HANDLED IN A SAFE MANNER. CONCRETE WASH WATER SHALL NOT BE ALLOWED TO ENTER THE ALL EARTH DISTURBANCE ACTIVITIES SHALL PROCEED IN ACCORDANCE WITH THE SEQUENCE PROVIDED ON THE PLAN DRAWINGS. DEVIATION 10. FROM THAT SEQUENCE MUST BE APPROVED IN WRITING BY THE DAUPHIN COUNTY CONSERVATION DISTRICT OR BY THE PENNSYLVANIA SURFACE OR GROUNDWATER SYSTEMS. CONTRACTOR SHALL MAINTAIN A WASH-WATER STATION ON-SITE AND A SPILL PREVENTION 4. APPLY HAY OR STRAW MULCH AT 3 TONS PER ACRE. DEPARTMENT OF ENVIRONMENTAL PROTECTION PRIOR TO IMPLEMENTATION. AND CONTINGENCY PLAN FOR THE WASH-WATER STATION. 5. PERFORM SEEDING BETWEEN MARCH 15 AND JUNE 1, AND AUGUST 1 AND OCTOBER 15. DEMOBILIZATION SEED FORMULA: PENNSYLVANIA DEPARTMENT OF TRANSPORTATION (PENNDOT) FORMULA D WHEN A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER. WITH A DENSITY CAPABLE OF RESISTING ACCELERATED EROSION AND 1. 70% TALL FESCUE AT 4.0 LB./SQ. YD SEDIMENTATION IS ESTABLISHED. CONTACT THE DAUPHIN COUNTY CONSERVATION DISTRICT FOR THEIR APPROVAL TO REMOVE THE CONTROL 30% CREEPING RED FESCUE OR CHEWINGS FESCUE AT 6.0 LB/SQ. YD MEASURES
- REMOVE INLET FILTER BAGS IN INLETS AND DISPOSE OF SEDIMENTS BY SPREADING ON STABILIZED SLOPE AREAS THAT DO NOT RECEIVE CONCENTRATED RUNOFF.
- ALL TOPSOIL STOCKPILE MATERIAL REMAINING SHALL BE SMOOTH GRADED TO PREVENT PONDING, THEN HAVE PERMANENT SEEDING AND MULCH APPLIED.
- 4. ALL COMPOST FILTER SOCKS SHALL BE SLIT AND MATERIAL SPREAD SMOOTH. APPLY PERMANENT SEEDING AND MULCH TO SPREAD MATERIAL

THERMAL IMPACTS

THERMAL IMPACTS RELATED TO THIS PROJECT ARE NOT EXPECTED TO BE SIGNIFICANT. RUNOFF FROM THE PROJECT SITE WILL BE INTERCEPTED AND DETAINED BY THE PROPOSED STORMWATER TREATMENT AREAS. WHICH WILL ACT AS A HEAT SINK TO COOL THE WATERS. PARKING LOT LANDSCAPING, WITH TREES, WILL PROVIDE SOME SHADING OF THE PAVED SURFACES.

CLEAN FILL & ENVIRONMENTAL DUE DILIGENCE

TABLE 11.1					
CUBIC YARDS OF TOP	CUBIC YARDS OF TOPSOIL REQUIRED FOR APPLICATION TO VARIOUS DEPTHS				
DEPTH (in)	PER 1,000 SQUARE FEET	PER ACRE			
1	3.1000	134			
2	6.2000	268			
3	9.3000	403			
4	12.4000	537			
5	15.5000	672			
6	18.6000	806			
7	21.7000	940			
8	24.8000	1074			

TEMPORARY & PERMANENT STABILIZATION

2. APPLY GROUND LIMESTONE AT 800 LBS PER ACRE. 3. APPLY FERTILIZER (10-10-20) AT 140 POUNDS PER 1000 SQUARE YARDS. 4. APPLY HAY OR STRAW MULCH AT 3 TONS PER ACRE. PERFORM SEEDING BETWEEN MARCH 15 AND JUNE 1, AND AUGUST 1 AND OCTOBER 15

THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT FOR THIS PROJECT, OF WHICH THIS EROSION AND SEDIMENTATION POLLUTION CONTROL PLAN IS A PART, COVERS THE "MOVING, DEPOSITING, STOCKPILING, OR STORING OF SOIL ROCK OR EARTH MATERIALS". IF THIS PROJECT WILL NEED FILL IMPORTED FROM AN OFF SITE LOCATION, THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND THE DETERMINATION OF CLEAN FILL SHALL RESIDE WITH THE CONTRACTOR.

2. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS, OR AUDITS,

3. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE.

4. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHALL BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE PENNSYLVANIA DEPARTMENT OF

5. CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL. THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, USED BRICK, BLOCK, OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH OF PENNSYLVANIA UNLESS OTHERWISE AUTHORIZED. (THE TERM

6. FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL WILL BE CONSIDERED REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL MANAGEMENT, IF

. FILL DETERMINATION IS NOT REQUIRED OF THE CONTRACTOR UNLESS THERE IS EVIDENCE THAT A SPILL OR RELEASE OF A REGULATED

A. A MAJORITY OF THE SUBJECT PARCEL IS TO BE DISTURBED DURING THE LENGTH OF THIS PROJECT, BUT THE CONSTRUCTION SCHEDULE FOR THIS PROJECT IS EXPECTED TO BE EXPEDITED, DUE TO THE TIME RESTRAINT OF THE EXPECTED SCHEDULE.

A. INSTALLATION OF COMPOST FILTER SOCKS AND INLET PROTECTION BAGS WILL MINIMIZE THE IMPACTS ON THE DOWNSTREAM

3. UTILIZES OTHER MEASURES OR CONTROLS THAT PREVENT OR MINIMIZE THE GENERATION OF INCREASED STORMWATER RUNOFF:

A. THE PROPOSED STORMWATER MANAGEMENT DESIGN PROTECTS AND UTILIZES THE EXISTING DRAINAGE PATTERN. NO OTHER

1. GRADED AREAS SHOULD BE SCARIFIED OR OTHERWISE LOOSENED TO A DEPTH OF 3 TO 5 INCHES TO PERMIT BONDING OF THE TOPSOIL

2. TOPSOIL SHOULD BE UNIFORMLY DISTRIBUTED ACROSS THE DISTURBED AREA TO A DEPTH OF 4 TO 8 INCHES MINIMUM - 2 INCHES ON FILL OUTSLOPES. SPREADING SHOULD BE DONE IN SUCH A MANNER THAT SODDING OR SEEDING CAN PROCEED WITH A MINIMUM OF ADDITIONAL PREPARATION OR TILLAGE. IRREGULARITIES IN THE SURFACE RESULTING FROM TOPSOIL PLACEMENT SHOULD BE CORRECTED IN ORDER TO PREVENT FORMATION OF DEPRESSIONS UNLESS SUCH DEPRESSION S ARE PART OF THE PCSM PLAN.

3. TOPSOIL SHOULD NOT BE PLACED WHILE THE TOPSOIL OR SUBSOIL IS IN A FROZEN OR MUDDY CONDITION, WHEN THE SUBSOIL IS EXCESSIVELY WET, OR IN A CONDITION THAT MAY OTHERWISE BE DETRIMENTAL TO PROPER GRADING AND SEEDBED PREPARATION.



MAINTENANCE & INSPECTION REQUIREMENTS				
GITE MAINTENANCE IS THE RESPONSIBILITY OF THE CONTRACTOR TABLE 1, EROSION AND FACILITIES MAINTENANCE REQUIREMENTS LISTS MINIMUM MAINTENANCE AND INSPECTION REQUIREMENTS DURING THE CONSTRUCTION PHASE. IF A BEST MANAGEMENT PRACTICE (BMP) DEVICE IS OBSERVED TO BE FAILING OR PERFORMING POORLY, IMMEDIATELY REPAIR AND/OR REPLACE.				
TAB	LE 1: EROSION AND SEDIMENT FACILITIES MAINTENANCE REQUIREMENTS			
ROCK CONSTRUCTION ENTRANCE (RCE)	CONTRACTOR SHALL MAINTAIN ROCK CONSTRUCTION ENTRANCE (RCE) DAILY AND AS REQUIRED TO PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN-OUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED BY END OF DAY.			
COMPOST FILTER SOCKS	COMPOST FILTER SOCKS ARE TO BE CHECKED WEEKLY AND AFTER EACH RAINFALL EVENT . REMOVE SEDIMENT BUILDING UP ONCE IT REACHES $\frac{1}{3}$ THE HEIGHT OF THE COMPOST FILTER SOCKS. IF THE COMPOST FILTER SOCK IS OVERTOPPED OR FAILS TO EFFECTIVELY FILTER SEDIMENT, REPLACE FAILED FENCE SECTION WITH A ROCK FILTER OUTLET. REPAIR SOCK OR REPLACE WITH ROCK FILTER OUTLET WITHIN 24 HOURS.			
INLET FILTER BAGS AND PUMPED WATER BAGS	CHECK DAILY AND REMOVE SEDIMENT WHEN HALF FULL, OR AS NEEDED TO PREVENT CLOGGING BY SEDIMENT AND PONDING. MAINTAIN WITHIN 24 HOURS OF OBSERVED FAILURE OR SEDIMENT BUILD-UP.			
TEMPORARY STOCKPILES	STOCKPILES SHALL BE MAINTAINED SO AS NOT TO EXCEED 35 FEET IN HEIGHT OR 2H:1V IN SLOPE. THESE AREAS SHALL BE SEEDED AND MULCHED IN ACCORDANCE WITH SPECIFICATIONS. 18-INCH COMPOST FILTER SOCK SHALL BE INSTALLED AROUND THE PERIMETER.			
TEMPORARY SEEDING AREAS	THESE AREAS SHALL BE SEEDED AND MULCHED IN ACCORDANCE WITH THE SPECIFICATIONS. ANY BARE OR DEAD PATCHES SHALL BE REPLACED IMMEDIATELY			
COMPOST SOCK CONCRETE WASHOUT	WASHOUT SHALL BE REPLACED WHEN ACCUMULATIONS REACH HALF OF THE HEIGHT OF THE COMPOST FILTER SOCK.			
TEMPORARY PROTECTION FENCE	CONTRACTOR SHALL INSPECT WEEKLY. REPAIR ANY DAMAGED FENCE WITHIN 24 HOURS.			

NOTE: UNLESS MORE FREQUENT MAINTENANCE REQUIREMENTS ARE SPECIFIED ABOVE, ALL EROSION AND SEDIMENT (E&S) CONTROL MEASURES SHALL BE INSPECTED WEEKLY AND AFTER EACH RAINFALL EVENT. INSPECTION, MAINTENANCE, AND REMOVAL OF E&S FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR. A WRITTEN LOG, USING DEP FORM 3150-FM-BWEW0083, OF E & S RELATED INSPECTIONS, REPAIR, AND MAINTENANCE ACTIVITIES SHALL BE MAINTAINED AT ALL TIMES ON SITE.

MAINTENANCE PROGRAM

THE CONTRACTOR IS REQUIRED TO INCORPORATE ALL TEMPORARY AND PERMANENT CONTROL MEASURES AND FACILITIES INDICATED IN THE APPROVED PLAN INTO THE PROJECT AT THE EARLIEST PRACTICABLE TIME. THE CONTRACTOR IS RESPONSIBLE FOR APPLYING, CLEANING, AND MAINTAINING ALL CONTROL FEATURES DURING CONSTRUCTION. APPROPRIATE EROSION AND SEDIMENT POLLUTION CONTROL FEATURES SHALL BE APPLIED TO SECTIONS SUCH AS BORROW PITS AND MATERIAL STORAGE AREAS UNFORESEEN PRIOR TO CONSTRUCTION. PERMANENT EROSION CONTROL FACILITIES WILL BE MAINTAINED BY THE OWNER.

THE TEMPORARY FACILITIES FOR EROSION AND SEDIMENT POLLUTION CONTROL SHALL BE INSPECTED A MINIMUM OF ONCE PER WEEK AND AFTER EVERY RAINFALL EVENT. SEDIMENT SHALL BE REMOVED WHEN ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF COMPOST SILT SOCK AND 1/3 THE ABOVE GROUND HEIGHT OF THE ROCK FILTER. ANY SILT SOCK SECTION THAT HAS BEEN UNDERMINED OR OVERTOPPED MUST BE IMMEDIATELY REPLACED WITH A AN OVERLAPPING ADJACENT UPSLOPE-SIDE OF NEW COMPOST SILT COCK OF 2 TIME THE LENGTH OF THE BREACHED/FAILED SECTION. AS CONSTRUCTION PROGRESSES AND DISTURBED AREAS HAVE BEEN STABILIZED, TEMPORARY EROSION CONTROL STRUCTURES ARE TO BE CLEANED AND REMOVED.

SEE EROSION AND SEDIMENTATION CONTROL PLAN DETAIL DRAWINGS FOR A TABULATED MAINTENANCE SCHEDULE.

A PROJECT INSPECTION LOG USING DEP FORM 3150-FM-BWEW0083 IS TO BE COMPLETED BY THE PERMITTEE AND KEPT ON SITE FOR REVIEW AT ALL TIMES


WEEKLY AND AFTER EVERY RUNOFF EVENT, THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL FACILITIES FOR DAMAGE, CLOGGING, SEDIMENT ACCUMULATION, OR STRUCTURAL DETERIORATION.

IF A BMP FAILS DURING A RUNOFF EVENT, THE CONTRACTOR SHALL REPLACE/FIX THE DAMAGED BMP WITHIN 24 HOURS OF THE FAILURE OCCURRENCE.

WHEN CLEANING EXCESS SEDIMENT FROM THE E&S CONTROL FACILITIES, PLACE SEDIMENTS IN GRASS AREAS WHICH DO NOT RECEIVE CONCENTRATED STORM FLOWS AND ARE CONTROLLED BY BMP'S (WITHIN LIMITS OF DISTURBANCE). THEN SEED OVER AREA USING SEEDING SPECIFICATIONS.

IL HDPE 5 MIL HI HOTO-RADEABLE PHOTODEGRADE 12" 12" 12" 18" 18" 24" 3/8" 3/8" 3/8" 3/8" 3/8" 3/8" 1000 HR. 23% AT 10 10NTHS 9 MONT	O- EABLE DEGRADE 12" 18" 24" 32" 5i 26 psi 000 HR.	(MFPP) PHOTO- DEGRADEA 12" 18" 24" 32" 3/8"	MULTI-FILAMENT POLYPROPYLENE (HDMFPP) - PHOTO- ABLE DEGRADEABLE 12" 18" 24" 32" 3/8" 202 psi			
RADEABLE DEGRADE 12" 12" 18" 24" 3/8" 3/8" 3/8" 26 ps T 1000 HR. 23% AT 10 10NTHS 9 MONT	EABLE DEGRADE	EABLE DEGRADEA 12" 18" 24" 32" 3/8" 5i 44 psi	ABLE DEGRADEABLE 12" 18" 24" 32" 3/8" 202 psi			
12" 18" 18" 24" 3/8" 3/8" 3/8" 26 ps AT 1000 HR. 23% AT 10 10NTHS 9 MONT	18" 24" 32" 3/8" si 26 psi 000 HR.	18" 24" 32" 3/8" si 44 psi	18" 24" 32" 3/8" 202 psi			
26 ps T 1000 HR. 23% AT 10 10NTHS 9 MONT	si 26 psi 000 HR.	si 44 psi	202 psi			
T 1000 HR. 23% AT 10 10NTHS 9 MONT	000 HR.					
IONTHS 9 MONT		100% AT 100	0 HR. 100% AT 1000 HR			
	THS 6 MONT					
T		THS 1 YEAR	2 YEARS			
	WO-PLY SYSTEMS	I				
		HDPE BIAXIAI	LNET			
INNER CONTAINMENT NETTING			CONTINUOUSLY WOUND			
			FUSION-WELDED JUNCTURES			
		³ ⁄4" X ³ ⁄4" MAX. APEF				
OUTER FILTRATION MESH			COMPOSITE POLYPROPYLENE FABRIC (WOVEN LAYER AND NON- WOVEN FLEECE MECHANICALLY FUSED VIA NEEDLE PUNCH) ³ /16" MAX. APERTURE SIZE			
OMPOSED OF BURLAP N		18				
F	RATION MESH	C (WOVEN LA	RATION MESH FUSION-WELDED J 3/4" X 3/4" MAX. APER COMPOSITE POLYPRO (WOVEN LAYER AND NON- WOVE FUSED VIA NEEDI			

ORGANIC MATTER CONTENT 25% - 100% (DRY WEIGHT LOSS) FIBROUS AND ELONGATED **ORGANIC PORTION** 5.5 - 8.5 pН MOISTURE CONTENT 30% - 50% PARTICLE SIZE 30% - 50% PASS THROUGH ³/₈" SIEVE SOLUBLE SALT CONCENTRATION 5.0 dS/m (mmhos/cm) MAXIMUM



NOTES

SOCK FABRIC SHALL MEET STANDARDS OF TABLE 4.1 OF THE PA DEP EROSION CONTROL MANUAL. COMPOST SHALL MEET THE STANDARDS OF TABLE 4.2 OF THE PA DEP EROSION CONTROL MANUAL.

COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE BARRIER SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN BARRIER ALIGNMENT. MAXIMUM SLOPE LENGTH ABOVE ANY BARRIER SHALL NOT EXCEED THAT SPECIFIED FOR THE SIZE OF THE SOCK AND THE SLOPE OF ITS TRIBUTARY AREA.

TRAFFIC SHALL NOT BE PERMITTED TO CROSS COMPOST FILTER SOCKS.

ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE BARRIER AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.


COMPOST FILTER SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.

BIODEGRADABLE COMPOST FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS. UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN

PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

COMPOST FILTER SOCK

NOT TO SCALE



NOTES:

MAXIMUM DRAINAGE AREA = 1/2 ACRE.

SECTION VIEW

INLET PROTECTION SHALL NOT BE REQUIRED FOR INLET TRIBUTARY TO SEDIMENT BASIN OR TRAP. BERMS SHALL BE REQUIRED FOR ALL INSTALLATIONS.

ROLLED EARTHEN BERM IN ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS STONED. ROAD SUBBASE BERM ON ROADWAY SHALL BE MAINTAINED UNTIL ROADWAY IS PAVED. EARTHEN BERM IN CHANNEL SHALL BE MAINTAINED UNTIL PERMANENT STABILIZATION IS COMPLETED OR REMAIN PERMANENTLY.

AT A MINIMUM, THE FABRIC SHALL HAVE A MINIMUM GRAB TENSILE STRENGTH OF 120 LBS., A MINIMUM BURST STRENGTH OF 200 PSI, AND A MINIMUM TRAPEZOIDAL TEAR STRENGTH OF 50 LBS. FILTER BAGS SHALL BE CAPABLE OF TRAPPING ALL PARTICLES NOT PASSING A NO. 40 SIEVE.

INLET FILTER BAGS SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EACH RUNOFF EVENT. BAGS SHALL BE EMPTIED AND RINSED OR REPLACED WHEN HALF FULL OR WHEN FLOW CAPACITY HAS BEEN REDUCED SO AS TO CAUSE FLOODING OR BYPASSING OF THE INLET. DAMAGED OR CLOGGED BAGS SHALL BE REPLACED. A SUPPLY SHALL BE MAINTAINED ON SITE FOR REPLACEMENT OF BAGS. ALL NEEDED REPAIRS SHALL BE INITIATED IMMEDIATELY AFTER THE INSPECTION. DISPOSE ACCUMULATED SEDIMENT AS WELL AS ALL USED BAGS ACCORDING TO THE PLAN NOTES.

DO NOT USE ON MAJOR PAVED ROADWAYS WHERE PONDING MAY CAUSE TRAFFIC HAZARDS.

STANDARD CONSTRUCTION DETAIL #4-16 FILTER BAG INLET PROTECTION - TYPE M INLET NOT TO SCALE

NOTES:

SIEVE.


NOTES:

A٧	/G.	V
		ł


UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.

RESUME UNTIL THE PROBLEM IS CORRECTED.





SHEET 16 OF 21



NOT TO SCALE

IS NOT ACCEPTABLE.





OPERATION AND MAINTENANCE NOTES

PCSM RESPONSIBLE PARTY: LINLO MONTROSE PARK, LLC

150 CORPORATE CIRCLE, SUITE 100 LEMOYNE, PA 17043

- 1. THE FOLLOWING PERMANENT BEST MANAGEMENT PRACTICES (BMPs) ARE PROPOSED FOR THIS SITE: SUBSURFACE DETENTION BASIN.
- 2. LINLO MONTROSE PARK, LLC (HEREAFTER "OWNER") IS RESPONSIBLE FOR THE OPERATIONS AND MAINTENANCE OF ANY AND ALL BMPs LOCATED WITHIN THE OWNER'S PROPERTY AS OUTLINED IN THE DRAINAGE COVENANT.
- 3. ON A BIANNUAL BASIS, TYPICALLY IN THE SPRING AND FALL, ALL THE INLETS AND PIPES ARE TO BE INSPECTED AND ALL SEDIMENT AND TRASH IS TO BE REMOVED. ALL INLET GRATES AND PIPE INVERTS ARE TO BE CLEARED OF ALL SEDIMENT AND DEBRIS.
- 4. TO KEEP THE SUBSURFACE DETENTION BASIN FUNCTIONAL, THE PENNSYLVANIA STORMWATER BEST MANAGEMENT PRACTICES MANUAL REQUIRES THAT THE SUBSURFACE DETENTION BASIN SHOULD BE INSPECTED AT A MINIMUM OF ONE TIME A YEAR OR AFTER MAJOR RAIN EVENTS IF NECESSARY. CLEANING SHOULD BE DONE AT THE DISCRETION OF THE INDIVIDUALS RESPONSIBLE TO MAINTAIN PROPER STORAGE AND FLOW. WHILE MAINTENANCE CAN GENERALLY BE PERFORMED YEAR-ROUND, IT SHOULD BE SCHEDULED DURING A RELATIVELY DRY SEASON.
- TREES SHALL BE INSPECTED TWICE PER YEAR TO EVALUATE THE HEALTH OF THE VEGETATION. DURING PERIODS OF EXTENDED DROUGHT, VEGETATION MAY REQUIRE WATERING. WHILE VEGETATION IS BEING ESTABLISHED, PRUNING AND WEEDING WILL BE REQUIRED.
- 6. ADDITIONAL MAINTENANCE REQUIREMENTS: OWNER SHALL MAINTAIN DRAINAGE OF THE SITE. THIS INCLUDES LAWN MAINTENANCE, INCLUDING PROPER WATERING AND MOWING AND THE REPLACEMENT OF ANY VEGETATION THAT HAS ERODED; REGULAR INSPECTION AND MAINTENANCE OF ROOF DRAINS; AND REGULARLY CLEANING DEBRIS FROM GUTTERS AND DOWNSPOUTS. OWNER SHALL MAINTAIN THE STORM SEWER SYSTEM INCLUDING THE HEADWALLS AND PIPES. INLETS AND HEADWALLS SHALL BE INSPECTED ONCE PER MONTH FOR DEBRIS OR TRASH AND THE PIPES SHALL BE CLEANED IF NECESSARY. ANY EROSION AT OUTLETS SHALL BE REPAIRED IMMEDIATELY WITH THE APPROPRIATELY SIZED RIPRAP APRON OR CABLE CONCRETE AS NECESSARY.
- OWNER SHALL ENSURE THAT ALL MATERIALS TRANSPORTED ON AND OFF OF THE SITE AND STORED ON THE SITE ARE HANDLED AND STORED PROPERLY TO PREVENT SPILLAGE AND CONTAMINATION OF DOWNSTREAM WATERS. IN THE EVENT OF A SPILL, OWNER SHALL IMMEDIATELY CLEAN ALL AFFECTED AREAS AND MITIGATE ALL DOWNSTREAM IMPACTS. OWNER SHALL ENSURE THAT ALL TENANTS WITHIN THE SITE HAVE AN EMERGENCY PLAN PREPARED FOR IMMEDIATE IMPLEMENTATION UPON A SPILL OF ANY MATERIALS UNDER THEIR CONTROL. ALL TENANTS SHALL ENSURE THAT THE EMERGENCY PLAN IS POSTED AND THAT ALL STAFF ARE TRAINED IN ITS IMPLEMENTATION.
- 8. ALL WASTES AND MATERIALS DEPOSITED IN AND REMOVED FROM POST-CONSTRUCTION STORMWATER MANAGEMENT (PCSM) BMP FACILITIES AND FROM IMPERVIOUS AREA DURING OPERATION AND MAINTENANCE SHALL BE REMOVED FROM THE SITE AND PROPERLY DISPOSED OF IN ACCORDANCE WITH THE DEPARTMENT'S SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA. CODE 260.1 ET.SEQ., 271.1., AND 287.1 ET. SEQ. NO WASTE MATERIALS SHALL BE BURNED, BURIED, DUMPED, OR DISCHARGED AT THE SITE.

9. SEE OPERATION AND MAINTENANCE NOTES AND SCHEDULE ON SHEET CS6022 FOR MORE DETAILS.

RECYCLING AND DISPOSAL NOTE

CONTRACTOR SHALL REMOVE FROM THE SITE, RECYCLE, OR DISPOSE OF ALL BUILDING MATERIALS AND WASTES IN ACCORDANCE WITH COMMONWEALTH OF PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION SOLID WASTE MANAGEMENT REGULATIONS AT 25 PA CODE 260.1 et seq. AND 287.1 et seq.

CONSTRUCTION SEQUENCE

SUBSURFACE DETENTION BASIN:


COORDINATE TIMING WITH GENERAL CONSTRUCTION SEQUENCE:

THE GENERAL SEQUENCE OF EARTHMOVING ACTIVITIES FOR THE CONSTRUCTION OF THE BMP IS AS FOLLOWS:


- SCHEDULE AND ATTEND REQUIRED PRE-CONSTRUCTION MEETING AS STATED IN THE "SEQUENCE OF EARTHMOVING OPERATIONS."
- 2. FIELD MARK THE LIMITS OF DISTURBANCE.
- 3. INSTALL THE COMPOST FILTER SOCK AT THE LOCATIONS SHOWN ON THE E&S PLANS.
- 4. INSTALL THE ROCK CONSTRUCTION ENTRANCE(S) AS SHOWN ON THE PLANS.
- DEMOLISH OR SALVAGE ALL ITEMS DEPICTED ON THE DEMOLITION PLANS 6. STRIP TOPSOIL IN AREA OF PARKING LOTS.
- 7. PERFORM THE GRADING FOR THE PROPOSED PARKING LOTS.
 - a. CONSTRUCT SLOPES.
 - b. APPLY GEOTEXTILE AND GRAVEL AS SOON AS FINAL GRADING IS ACHIEVED.
 - c. UPON COMPLETION OF FINAL GRADING, SEED EXPOSED AREAS AND MULCH TO DETER EROSION.
 - d. UTILIZE EROSION CONTROL BLANKETS/MULCHES ON SLOPES STEEPER THAN 3H:1V OR IN AREAS WITHIN 100 FEET OF SURFACE WATER.
- 8. INSTALL ALL DIVERSION BERMS.
- 9. INSTALL ALL INLETS STORM PIPING AND SUBSURFACE INFILTRATION AS SHOWN ON THE PLANS BEGINNING DOWNSTREAM.
- 10. COMPLETE THE FINAL GRADING AND INSTALL LANDSCAPING. 11. WHEN THE PERMANENT VEGETATION HAS REACHED A MINIMUM 70% PERENNIAL VEGETATIVE COVER, REMOVE ANY REMAINING SEDIMENT CONTROL DEVICES.
- 12. PERMANENTLY STABILIZE ANY AREAS DISTURBED BY THE SEDIMENT CONTROL DEVICES.
- 13. REMOVE ALL ACCUMULATED SEDIMENT FROM REMAINING E&S BMPS.
- 14. FILTER SOCK COMPOST MATERIAL SHALL BE DISPOSED OF PROPERLY. STABILIZE THE AREAS WHERE THE BMPS WERE LOCATED. DISPOSE OF ANY EXCESS SEDIMENT AS OUTLINES IN MAINTENANCE NOTES.
- 15. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM UNIFORM 70% PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING AND OTHER MOVEMENTS.
- 16. THE SITE PREPARATION CONTRACTOR SHALL CONTACT DAUPHIN COUNTY CONSERVATION DISTRICT (TELEPHONE: 717-921-8100) FOR APPROVAL THAT THE SITE HAS BEEN ADEQUATELY STABILIZED. 17. SUBMIT AN NPDES NOTICE OF TERMINATION TO THE DAUPHIN COUNTY CONSERVATION DISTRICT, FOR EACH CO-PERMITTEE.

THERMAL IMPACTS


THERMAL IMPACTS RELATED TO THIS PROJECT ARE NOT EXPECTED TO BE SIGNIFICANT. RUNOFF FROM THE PROJECT SITE WILL BE INTERCEPTED AND DETAINED BY THE PROPOSED STORMWATER TREATMENT AREAS, WHICH WILL ACT AS A HEAT SINK TO COOL THE WATERS. PARKING LOT LANDSCAPING, WITH TREES, WILL PROVIDE SOME SHADING OF THE PAVED SURFACES.







ANTI-SEEP COLLAR NOT TO SCALE




TYPE M FRAME (CAST IRON SHOWN)

GRADE ADJUSTMENT RING - INLET BOX

NOTES: 1. PROVIDE A MINIMUM OF 1' THICK BACKFILL LAYER OF R-3 AGGREGATE AGAINST INLET BOX. 2. INLET FRAMES AND GRATES TO BE STEEL 3. MANHOLE STEPS REQUIRED FOR ALL INLETS OVER 40" DEEP.

PENNDOT TYPE M INLET NOT TO SCALE

BICYCLE SAFE STRUCTURAL STEEL GRATE NOT TO SCALE



POST CONSTRUCTION STORMWATER MANAGEMENT (PCSM) STANDARD NOTES

PCSM REQUIREMENTS A LICENSED PROFESSIONAL OR A DESIGNEE SHALL BE PRESENT ONSITE AND BE RESPONSIBLE DURING CRITICAL STAGES OF IMPLEMENTATION OF THE APPROVED PCSM PLAN. THE CRITICAL S MAY INCLUDE THE INSTALLATION OF UNDERGROUND TREATMENT OR STORAGE BMPS, STRUCTURALLY ENGINEERED BMPS, OR OTHER BMPS AS DEEMED APPROPRIATE BY THE DEPARTMENT OF CONSERVATION DISTRICT. THE PCSM PLAN, INSPECTION REPORTS, AND MONITORING RECORDS SHALL BE AVAILABLE FOR REVIEW AND INSPECTION BY THE DEPARTMENT OR THE CONSERVATION DISTRICT

PCSM LONG TERM OPERATIONS AND MAINTENANCE REQUIREMENT THE PERMITTEE OR CO-PERMITTEE SHALL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS UNLESS A DIFFERENT PERSON IS IDENTIFIED IN THE NOT TERMINATION AND HAS AGREED TO LONG-TERM OPERATION AND MAINTENANCE OF PCSM BMPS. A PERMITTEE OR CO-PERMITTEE THAT FAILS TO TRANSFER LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP OR OTHERWISE FAILS TO COMPLY WITH THIS REQUIREMENT SHALL F JOINTLY AND SEVERALLY RESPONSIBLE WITH THE LANDOWNER FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS LOCATED ON THE PROPERTY.

PERMIT TERMINATIO

UPON PERMANENT STABILIZATION OF THE EARTH DISTURBANCE ACTIVITY AND INSTALLATION OF BMPS IN ACCORDANCE WITH AN APPROVED PLAN, THE PERMITTEE OR CO-PERMITTEE SHALL S A NOTICE OF TERMINATION TO THE DEPARTMENT OR CONSERVATION DISTRICT. THE NOTICE OF TERMINATION MUST INCLUDE:


- THE FACILITY NAME, ADDRESS AND LOCATION THE OPERATOR NAME AND ADDRESS
- THE NPDES PERMIT NUMBER
- THE REASON FOR PERMIT TERMINATION
- IDENTIFICATION OF THE PERSONS WHO HAVE AGREED TO AND WILL BE RESPONSIBLE FOR LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM COPY OF LEGAL INSTRUMENT: FOR ANY PROPERTY CONTAINING A PCSM BMP, THE PERMITTEE OR CO-PERMITTEE SHALL RECORD AN INSTRUMENT WITH THE RECORDER OF DEEDS WHIC ASSURE DISCLOSURE OF THE PCSM BMP AND RELATED OBLIGATIONS IN THE ORDINARY COURSE OF A TITLE SEARCH OF THE SUBJECT PROPERTY. THE RECORDED INSTRUMENT MUST ID
- THE PCSM BMP, PROVIDE FOR NECESSARY ACCESS RELATED TO LONG-TERM OPERATION AND MAINTENANCE FOR PCSM BMPS AND PROVIDE NOTICE THAT THE RESPONSIBILIT LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMP IS A COVENANT THAT RUNS WITH THE LAND THAT IS BINDING UPON AND ENFORCEABLE BY SUBSEQUENT GRANTEE PROVIDE PROOF OF FILING WITH THE NOTICE OF TERMINATION. FINAL CERTIFICATION: THE PERMITTEE SHALL INCLUDE WITH THE NOTICE OF TERMINATION "RECORD DRAWINGS" WITH A FINAL CERTIFICATION STATEMENT FROM A LICENSED PROFESS WHICH READS AS FOLLOWS:
- "I (NAME) DO HEREBY CERTIFY PURSUANT TO THE PENALTIES OF 18 PA. C.S.A. 4904 TO THE BEST OF MY KNOWLEDGE, INFORMATION AND BELIEF, THAT THE ACCOMPANYING RECORD DRA ACCURATELY REFLECT THE AS-BUILT CONDITIONS, ARE TRUE AND CORRECT, AND ARE IN CONFORMANCE WITH CHAPTER 102 OF THE RULES AND REGULATIONS OF THE DEPARTME ENVIRONMENTAL PROTECTION AND THAT THE PROJECT SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE APPROVED PCSM PLAN, ALL APPROVED PLAN CHANGES AND ACC CONSTRUCTION PRACTICES." (1)THE PERMITTEE SHALL RETAIN A COPY OF THE RECORD DRAWINGS AS A PART OF THE APPROVED PCSM PLAN.
- (2)THE PERMITTEE SHALL PROVIDE A COPY OF THE RECORD DRAWINGS AS PART OF THE APPROVED PCSM PLAN TO THE PERSON IDENTIFIED IN THIS SECTION AS BEING RESPO FOR THE LONG-TERM OPERATION AND MAINTENANCE OF THE PCSM BMPS.


SCHEDULE OF INSPECTIONS


- A DETAILED SCHEDULE OF INSPECTIONS, AS GENERALLY OUTLINED AS FOLLOWS, WHICH IS TAILORED FOR THE SITE UNDER CONSIDERATION. ALL INSPECTIONS SHALL BE CONDUCTED QUALIFIED PROFESSIONAL.
- 1. THE TOWNSHIP SHALL INSPECT THE IMPROVEMENTS DURING CONSTRUCTION. THE DEVELOPER SHALL PAY THE COST OF ANY SUCH INSPECTION. THE DEVELOPER SHALL PROVIDE AT LEAST TWENTY-FOUR (24) HOURS NOTICE PRIOR TO THE START OF CONSTRICTION OF ANY IMPROVEMENTS THAT ARE SUBJECT TO INSPECTION. ALL INSPECTIONS OF COMPLETED ITEMS SHALL BE REQUESTED, IN WRITING, AT LEAST FORTY-EIGHT (48) HOURS IN ADVANCE OF THE INSPECTION TIME AND DATE.
- 2. IT IS GENERALLY REQUIRED THAT THE FOLLOWING PHASES OF SITE CONSTRUCTION HAVE MANDATORY INSPECTIONS. THIS GENERAL LIST OF PHASES MAY BE AMENDED BY MUTUAL AGREEMENT OF THE TOWNSHIP AND DEVELOPER WHEN THE SITE REQUIRES SPECIAL CONSTRUCTION PROCEDURES. THE INSPECTION SCHEDULE MUST BE SHOWN ON THE APPROVED STORM WATER MANAGEMENT SITE PLAN. 3. GENERAL SITE CONSTRUCTION INSPECTIONS
 - a. UPON COMPLETION OF PRELIMINARY SITE PREPARATION INCLUDING STRIPPING OF VEGETATION, STOCKPILING OF TOPSOIL AND CONSTRUCTION OF TEMPORARY EROSION AND SEDIMENTATION CONTROL DEVICES.
 - b. UPON COMPLETION OF ROUGH GRADING, BUT PRIOR TO PLACING TOPSOIL, PERMANENT DRAINAGE, OR OTHER SITE DEVELOPMENT IMPROVEMENTS AND GROUND COVERS.
 - C. DURING THE CONSTRUCTION OF PERMANENT STORM WATER MANAGEMENT AND BMP FACILITIES.
 - d. UPON THE FINAL COMPLETION OF PERMANENT STORM WATER MANAGEMENT AND BMP FACILITIES, INCLUDING THE ESTABLISHMENT OF GROUND COVERS AND PLANTINGS.
 - e. AFTER REVIEW OF THE AS-BUILT DRAWINGS, REQUIRED BY SECTION 604, BUT PRIOR TO FINAL RELEASE OF THE FINANCIAL GUARANTEE TOR COMPLETION OF FINAL
- GRADING, VEGETATIVE CONTROLS REQUIRED BY THE BMP STANDARDS, OR OTHER SITE RESTORATION WORK. 4. IN ADDITION TO THE ABOVE OUTLINED OBSERVATIONS, ADDITIONAL OBSERVATIONS WILL BE MADE AT THE REQUEST OF THE DEVELOPER FOR REDUCTION OF FINANCIAL SECURITIES. RANDOM OBSERVATIONS SHOULD BE MADE AT THE FREQUENCY DESIRED BY THE MUNICIPALITY. AT THE TIME OF ANY OF THE ABOVE LISTED OBSERVATIONS, ALL ONGOING CONSTRUCTION (I.E. STORM DRAINAGE, SANITARY SEWER, WATER, EROSION CONTROL, ETC.) SHOULD ALSO BE CHECKED FOR COMPLIANCE WITH THE APPROVED PLANS AND THE FINDINGS REPORTED. SINCE THE ABOVE INSPECTIONS ARE MANDATORY, IT IS RECOMMENDED THAT REQUESTS FOR REDUCTION OF FINANCIAL GUARANTEE TO BE SUBMITTED TO COINCIDE WITH THE ABOVE
- INSPECTIONS. 5. MS4 DURING CONSTRUCTION BMP INSPECTION SCHEDULE. FOR THOSE SITES LOCATED WITHIN THE DESIGNATED MS4 AREA, THE REQUIRED MS4 INSPECTION SCHEDULE AND REQUIRED RECORD KEEPING SHALL BE NOTED ON THE APPROVED PLANS. THESE INSPECTIONS MAY INCLUDE BUT ARE NOT LIMITED TO:
 - a. THE SUBGRADE OF DETENTION FACILITIES
 - b. STONE AND/OR CONCRETE PLACEMENT
 - C. PLACEMENT OF LINERS d. R-TANK INSTALLATION
 - e. INSTALLATION OF PRETREATMENT/WATER QUALITY DEVICES
 - f. PERMANENT EROSION CONTROL MATTING INSTALLATION
 - g. GENERAL SITE GRADING
- h. DOWNSPOUT LOCATIONS. 6. POST-CONSTRUCTION STORM WATER MANAGEMENT BMP INSPECTION SCHEDULE.
 - a. THE BMP INSPECTION SCHEDULE SHALL BE DEVELOPED BY THE APPLICANT AND COMPLY WITH THE CURRENT MS4 REQUIREMENTS
 - b. THE INSPECTION SCHEDULE AND RECORD KEEPING REQUIREMENTS FOR THE INSTALLED BMP'S SHALL BE NOTED ON THE APPROVED PLANS. THE INSPECTIONS WILL INCLUDE ALL BMP'S SUCH AS RAIN GARDENS, RECAPTURE AND REUSE DEVICES, PLANTINGS, STORAGE DEVICES, UNDER AND ABOVE GROUND INFILTRATION FACILITIES, DOWNSPOUTS, PERVIOUS PAVING, INLET WATER QUALITY DEVICES, SWALES AND ANY OTHER BMP SPECIFIED ON THE PLANS.
 - C. THE MINIMUM BMP INSPECTION INTERVAL SHALL BE NOTED ON THE APPROVED PLANS:
 - i. DURING OR IMMEDIATELY AFTER EACH 10-YEAR FREQUENCY STORM EVENT IN ADDITION TO THOSE LISTED BELOW.
 - ii. ANNUALLY FOR THE FIRST 5 YEARS ALTER CONSTRUCTION.
 - iii. AFTER THE FIRST 5 YEARS, ONCE EVERY 3 YEARS.
 - iv. AT A GREATER FREQUENCY DETERMINED APPROPRIATE BY UNUSUAL SITE CONDITIONS, AS A RESULT OF CONFLICTS WITH OTHER PERMITTING REQUIREMENTS (SUCH AS NPDES) OR BASED ON THE JUDGMENT OF THE DESIGNER AND/OR TOWNSHIP ENGINEER.
 - d. A NOTE SHALL BE PLACED ON THE PLANS INDICATING THAT THE INSPECTION REPORTS GENERATED BY THIS SECTION SHALL BE SUBMITTED TO THE TOWNSHIP WITHIN 60 DAYS OF THE INSPECTION.
 - e. OPERATION AND MAINTENANCE REQUIREMENTS CAN BE FOUND IN ARTICLE VI.

EARLY MAINTENANCE ACTIVITY	FREQUENCY
INSPECT CONTROLS, OUTLET STRUCTURES, AND STORAGE AREAS FOR TRASH AND SEDIMENT ACCUMULATION	MONTHLY FOR THE FIRST YEAR AFTER INSTALLATION TO DETERMINE ONGOING MAINTENANCE FREQUENCY.
INSPECT EROSION CONTROL AND FLOW SPREADING DEVICES UNTIL SOIL SETTLEMENT AND STABILIZATION OF CONTRIBUTING AREAS HAVE OCCURRED	BIWEEKLY

	OPERATIONS AND MAINTENANCE SCHEDULE			
: I	ONGOING MAINTENANCE ACTIVITY	FREQUENCY		
	REGULARLY CLEAN OUT GUTTERS AND CATCH BASINS TO REDUCE SEDIMENT LOAD TO SYSTEM	BI-ANNUALLY OR AS NEEDED		
	CLEAN INTERMEDIATE SUMP BOXES IN DIRECT CONNECTION OF THE SYSTEM	BI-ANNUALLY OR AS NEEDED		
	KEEP INFLOW AREA AND OUTLET CONTROL STRUCTURE FREE AND CLEAR OF DEBRIS AND OBSTRUCTIONS	BI-ANNUALLY OR AS NEEDED		
	INSPECT AND CLEAN AS NEEDED ALL COMPONENTS AND CONNECTIONS TO SUBSURFACE DETENTION SYSTEM	EVERY 3 MONTHS		
	EVALUATE THE DRAIN-DOWN TIME OF THE SUBSURFACE DETENTION SYSTEM TO ENSURE THE DRAIN-DOWN TIME OF 24-72 HOURS	EVERY 3 MONTHS		
	VACUUM OR FLUSH PIPES AND UNDERGROUND CHAMBERS	BI-ANNUALLY OR AS NEEDED		
	MAINTAIN RECORDS OF ALL INSPECTIONS AND MAINTENANCE ACTIVITY	IN PERPETUITY		







ominal Diameter in (mm)	AASHTO Specification	Perforation Type	Diameter, max. in (mm)	Perforation Configuration
12 (300)	M294	Circular	0.375 (10)	E
15 (375)	M294	Circular	0.375 (10)	E
18 (450)	M294	Circular	0.375 (10)	E
24 (600)	M294	Circular	0.375 (10)	F
30 (750)	M294	Circular	0.375 (10)	H
36 (900)	M294	Circular	0.375 (10)	H
42 (1050)	M294	Circular	0.375 (10)	Н
48 (1200)	M294	Circular	0.375 (10)	Н
60 (1500)	M294	Circular	0.375 (10)	Н

