PHASE III FINAL LAND DEVELOPMENT PLANS FOR SUSQUEHANNA UNION GREEN 2020 BEFORE ME THE UNDERSIGNED

COMMONWEALTH OF PENNSYLVANIA COUNTY OF DAUPHIN

ON THIS THE _ DAY OF PERSONALLY APPEARED.

OWNER(S)

WHO BEING DULY SWORN ACCORDING TO LAW, DEPOSE AND SAY THAT THEY ARE THE OWNERS OF THE PROPERTY SHOWN ON THIS PLAN AND THAT THEY ACKNOWLEDGE THE SAME TO BE THEIR ACT AND DEED AND DESIRE THE SAME TO BE RECORDED AS SUCH ACCORDING TO LAW.

WITNESS MY HAND AND NOTORIAL SEAL THE DAY AND DATE ABOVE WRITTEN,

NOTARY PUBLIC

OWNER STATEMENT OF DEDICATION

IT IS HEREBY CERTIFIED THAT THE UNDERSIGNED ARE THE OWNERS OF THE PROPERTY SHOWN ON THIS PLAT AND THAT ALL STREETS OR PARTS THEREOF, IF NOT PREVIOUSLY DEDICATED, ARE HEREBY TENDERED FOR DEDICATION TO PUBLIC USE.

OWNER(S)

OWNER CERTIFICATION (STORMWATER)

IT IS HEREBY CERTIFIED THAT THE UNDERSIGNED ARE THE OWNERS OF THE PROPERTY SHOWN ON THIS PLAN AND THAT ALL STORMWATER BMPs ARE FIXTURES THAT CANNOT BE ALTERED OR REMOVED WITHOUT PRIOR APPROVAL BY SUSQUEHANNA TOWNSHIP.

OWNER(S)

ENGINEER CERTIFICATION

I HEREBY CERTIFY THIS PLAN TO BE CORRECT AS SHOWN.

(ENGINEER'S SIGNATURE AND SEAL)

SURVEYOR CERTIFICATION

I HEREBY CERTIFY TO THE BEST OF MY KNOWLEDGE, THE SURVEY AND PLAN SHOWN AND DESCRIBED HEREON IS TRUE AND CORRECT TO THE ACCURACY REQUIRED BY THE SUSQUEHANNA TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE.

(SURVEYOR'S SIGNATURE AND SEAL)

STORMWATER MANAGEMENT CERTIFICATION

BRYAN CLEMENT, HEREBY CERTIFY THAT THE STORMWATER MANAGEMENT SITE PLAN MEETS ALL DESIGN STANDARDS AND CRITERIA OF SUSQUEHANNA TOWNSHIP'S STORMWATER MANAGEMENT ORDINANCE.

WETLAND STATEMENT

_, HEREBY CERTIFY THAT THERE (ARE/ARE NOT) WETLANDS ON THE SUBJECT PROPERTY, THE PROPOSED PROJECT (WILL/WILL NOT) IMPACT OFF-SITE WETLANDS, AND PERMITS (ARE/ARE NOT) REQUIRED FROM THE STATE OR FEDERAL GOVERNMENT.

DAUPHIN COUNTY PLANNING COMMISSION REVIEW STATEMENT

THIS PLAN REVIEWED BY THE DAUPHIN COUNTY PLANNING COMMISSION _____ DAY OF _____, 2021

CHAIRMAN _____

SECRETARY _____

SUSQUEHANNA TOWNSHIP ENGINEER REVIEW STATEMENT

THIS PLAN REVIEWED BY THE SUSQUEHANNA TOWNSHIP ENGINEER THIS _____ DAY OF _____, 2021

TOWNSHIP ENGINEER

SUSQUEHANNA TOWNSHIP PLANNING COMMISSION APPROVAL STATEMENT

THIS PLAN RECOMMENDED FOR APPROVAL BY THE SUSQUEHANNA TOWNSHIP PLANNING COMMISSION THIS _____ DAY OF _____, 2021

CHAIRMAN _____

SECRETARY _____

SUSQUEHANNA TOWNSHIP BOARD OF COMMISSIONERS APPROVAL STATEMENT

THIS PLAN APPROVED BY THE SUSQUEHANNA TOWNSHIP BOARD OF COMMISSIONERS, AND ALL CONDITIONS IMPOSED WITH RESPECT TO SUCH APPROVAL WERE COMPLETED ON THIS ______ DAY OF _____, 2021

PRESIDENT _____

RECORDING STATEMENT

THIS PLAN RECORDED IN THE OFFICE OF THE RECORDER OF DEEDS IN AND FOR DAUPHIN COUNTY THIS ______ DAY OF ______, 2021 INSTRUMENT NUMBER

SECRETARY _____

MODIFICATIONS GRANTED THROUGH PRELIMINARY PLANNING APPROVAL: 22–507.9.3 REQUIRING SIDEWALKS ON BOTH SIDES OF STREET REQUIRING CLEAR SIGHT TRIANGLES IN ACCORDANCE 22-502.8 WITH SALDO EXHIBIT 6 22-405.2.M REQUIRING A PRELIMINARY GREENWAY/OPEN SPACE LANDS & COMMON FACILITIES OWNERSHIP AND MAINTENANCE PLAN 22-405.1.A.12 REQUIRING THE DESIGNATION OF PARCELS OF LAND INTENDED TO BE DEDICATED OR RESERVED FOR PUBLIC, SEMI-PUBLIC OR COMMUNITY PURPOSES

REQUIRING STREET SECTIONS IN ACCORDANCE WITH 507.10.4 DESIGN GUIDELINES



MY COMMISSION EXPIRES





APPLICANT: ZONING TOTAL SITE AREA: BULK AREA REQUIREMENTS MINIMUM TRACT AREA MULTIPLE FAMILY: PRINCIPAL FREE STANDING BUILDING: MINIMUM LOT AREA FOR IN LINE RETAIL: ACRES DEVOTED TO RESIDENTIAL USES SINGLE-FAMILY DETACHED MULTI-FAMILY MAXIMUM DWELLING UNITS PER GROSS ACRE SINGLE-FAMILY DETACHED BUILD TO LINES: MINIMUM SIDE YARD NON-RESIDENTIAL / MULTI-FAMILY: RESIDENTIAL: MAXIMUM IMPERVIOUS COVERAGE: MINIMUM GREEN SPACE CENTRAL GREEN: ADDITIONAL GREENS MINIMUM PRINCIPAL BUILDING HEIGHT: MAXIMUM PRINCIPAL BUILDING HEIGHT: NO. 62-013-056

20170009139

20130022125

TAX PARCEL: DEED INSTRUMENT NO. PLAN INSTRUMENT NO.

SUSQUEHANNA TOWNSHIP DAUPHIN COUNTY, PENNSYLVANIA JULY 9, 2021

PREPARED BY:







95 South Tenth Street Pittsburgh, Pennsylvania 15203 tel 412. 488. 8822 fax 412. 488.8825 Nature leads, art follows.




COMPANY Scalp Avenue ohnstown, PA 15904 hone: 814-269-9300 FAX: 814-269-9301

<u>SHEET NUMBER</u>
C000
C100
C200
L100
L101
L102
L103
L200
L201
L202
C300
C400
C401
C500
C600 TO C601
C602 TO C605
ES100
ES200 TO ES201
ES202
ES202

SHEET TITLE



HAWTHORNE SPE, LLC 3605 VARTAN WAY SUITE 301 HARRISBURG, PA 17110 MR. H. RALPH VARTAN - PRESIDENT (717) 657–0100 VARTAN GROUP INC. 3605 VARTAN WAY SUITE 301 HARRISBURG, PA 17110 MR. H. RALPH VARTAN (717) 657–0100 TRADITIONAL NEIGHBORHOOD DEVELOPMENT-1 (TND-1) 58.07 ACRES REQUIRED / PERMITTED PROVIDED 40,000 S.F. 40,000 S.F 10,000 S.F. 10,000 S.F. 1,000 S.F. 1,000 S.F. $37.8\% \times 36.24 \text{ AC.} = 13.70 \text{ AC.}$ 2.9 AC. MIN. (NO MAX.) $62.2\% \times 36.24 \text{ AC.} = 22.54 \text{ AC}$ 40 UNITS 10.2 AC. X 9 UNITS/AC. = 92 UNITS 12' MAXIMUM 12' 20' 20' 15' 15' 53.9% 55% 0.5 AC. 1 AC. EACH 0.56 AC. 3.70 AC 20' 55' 55' (4 STORIES)



INDEX OF SHEETS

<u>AUTHOR</u>

COVER SHEET	H.F. LENZ COMPANY
GENERAL INFORMATION SHEET	H.F. LENZ COMPANY
EXISTING CONDITIONS PLAN	H.F. LENZ COMPANY
PHASING PLAN	La QUATRA BONCI ASSOCIATES
REGULATING PLAN	La QUATRA BONCI ASSOCIATES
STREETSCAPE PLAN	La QUATRA BONCI ASSOCIATES
PUBLIC REALM PLAN	La QUATRA BONCI ASSOCIATES
SITE & LANDSCAPE REFERNECE PLAN	La QUATRA BONCI ASSOCIATES
ENLARGED SITE & LANDSCAPE PLAN-PHASE IIIA	La QUATRA BONCI ASSOCIATES
ENLARGED SITE & LANDSCAPE PLAN—PHASE IIIB	La QUATRA BONCI ASSOCIATES
SITE PLAN	H.F. LENZ COMPANY
GRADING AND DRAINAGE PLAN	H.F. LENZ COMPANY
STORM SEWER PROFILES	H.F. LENZ COMPANY
UTILITY PLAN	H.F. LENZ COMPANY
SITE DETAILS	H.F. LENZ COMPANY
UTILITY DETAILS	H.F. LENZ COMPANY
EROSION AND SEDIMENTATION CONTROL PLAN	H.F. LENZ COMPANY
EROSION AND SEDIMENTATION CONTROL GENERAL NOTES	H.F. LENZ COMPANY
EROSION AND SEDIMENTATION CONTROL NOTES & SYMBOLS	H.F. LENZ COMPANY
EROSION AND SEDIMENTATION CONTROL DETAILS	H.F. LENZ COMPANY

LaQuatra Bonci ASSOCIATES LANDSCAPE ARCHITECTURE 95 South Tenth Street Pittsburgh, Pennsylvania 15203 tel 412. 488. 8822 fax 412. 488.8825 Nature leads, art follows 1407 Scalp Avenue Johnstown, PA 15904 Phone: 814-269-930



Prepared for:

Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110

Susquehanna Union Green Susquehanna Township, Dauphin County, PA

Project Number: 210191.01

Drawn by: LBG/REA

Checked by LBG/BJC

Date: July 9, 2021

Revisions:

Scale:

Sheet Name:





Submission: Phase III Final Land Development Plans

Sheet Number:

Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of own

GENERAL NOTES:

- 1. THIS PLAN IS IN SUBSTANTIAL COMPLIANCE WITH THE SUSQUEHANNA TOWNSHIP ZONING. SUBDIVISION AND LAND DEVELOPMENT. AND STORMWATER MANAGEMENT ORDINANCES PURSUANT TO SECTION 507 OF THE PENNSYLVANIA MUNICIPALITIES PLANNING CODE (THE "MPC"). ANY DESIGN MODIFICATIONS MUST BE APPROVED BY THE SUSQUEHANNA TOWNSHIP BOARD OF COMMISSIONERS PRIOR TO FINAL PLAN APPROVAL PURSUANT TO SECTION 508(4) OF THE MPC.
- 2. PURSUANT TO 27-1912 OF THE SUSQUEHANNA TOWNSHIP ZONING ORDINANCE, THE BOARD OF COMMISSIONERS HEREBY MAKES THE FOLLOWING FINDINGS:
 - A. THIS PLAN IS CONSISTENT WITH THE "KEY DESIGN ELEMENTS" OF EXHIBIT A, THE "PRECEDENTS" OF EXHIBIT B, AND THE "REGULATING PLAN" OF EXHIBIT C OF PART 19 OF THE SUSQUEHANNA TOWNSHIP ZONING ORDINANCE.
 - THE MANUAL OF WRITTEN AND GRAPHIC DESIGN GUIDELINES Β. ACCOMPANYING THIS PLAN IS CONSISTENT WITH THE DESIGN GUIDELINES IN 22-507 OF THE SUSQUEHANNA TOWNSHIP SUBDIVISION AND LAND DEVELOPMENT ORDINANCE. C. DATE OF FINAL REVIEW BY BOARD OF COMMISSIONERS:

_____,2021

- 3. THE PROPOSED STREET AND SPEED LIMIT SIGNAGE SHALL BE CONSISTENT WITH THE SPECIFICATIONS OF SUSQUEHANNA TOWNSHIP.
- 4. ALL FIRE HYDRANTS SHALL HAVE SHUT OFF VALVES.
- 5. THE DEVELOPER/CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE A MINIMUM OF 48 HOURS NOTICE AND TO COORDINATE WITH THE TOWNSHIP/TOWNSHIP ENGINEER IN REGARDS TO ALL MUNICIPAL INSPECTION WORK REQUIRED ON THE PROJECT SITE.
- 6. THE DEVELOPER SHALL PROVIDE TWO (2) SETS OF RECORD DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES TO SUSQUEHANNA TOWNSHIP PRIOR TO OCCUPANCY OR THE RELEASE OF FINANCIAL SECURITY.
- 7. THE DEVELOPER SHALL PROVIDE TWO (2) SETS OF RECORD DRAWINGS TO THE SUSQUEHANNA TOWNSHIP AUTHORITY. THESE RECORD DRAWINGS SHALL BE PROVIDED AFTER THE STRUCTURES ARE CONSTRUCTED AND SHALL SHOW THE CONNECTION TO THE SEWER MAIN.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ANY NON-STANDARD HEADWALLS OR ENDWALLS STRUCTURALLY DESIGNED BY A PROFESSIONAL ENGINEER REGISTERED IN THE COMMONWEALTH OF PENNSYLVANIA. THE STRUCTURAL DESIGN CALCULATIONS SHALL BE SUBMITTED TO AND REVIEWED BY THE TOWNSHIP AND THEIR ENGINEER.
- 9. INSTALLATION OF STORM DRAINAGE PIPING THROUGH THE CORNER OF PRE-CAST INLETS (OR "KNOCKOUT CORNERS") IS PROHIBITED. ALL PIPE CONNECTIONS AT INLETS SHALL OCCUR AT THE SIDES OF THE INLET.
- 10. ALL STORMWATER INLET FRAMES, CONCRETE TOPS, AND GRADE ADJUSTMENT RINGS SHALL BE SET IN A FULL BED OF MORTAR.
- 11. ALL STORMWATER CONVEYANCE PIPING SHALL HAVE WATERTIGHT JOINTS.
- 12. ROADWAY AND/OR CURB UNDERDRAIN(S) SHALL BE INSPECTED BY THE MUNICIPAL ENGINEER OR HIS DESIGNATED AGENT AFTER COMPLETION OF ALL WORK, JUST PRIOR TO THE BASE COURSE APPLICATION.
- 13. THE TOWNSHIP STAFF HAS PERMISSION TO ACCESS THE DRAINAGE EASEMENTS FROM THE NEAREST PUBLIC RIGHT-OF-WAY.
- 14. SIDEWALKS SHALL BE INSPECTED BY THE MUNICIPAL ENGINEER OR HIS DESIGNATED AGENT AFTER THE FORMS HAVE BEEN PLACED, JUST PRIOR TO THE POURING OF CONCRETE AND AFTER THE COMPLETION OF ALL WORK.
- 15. ALL STREET ADDRESS NUMBERS SHALL BE DISPLAYED IN ACCORDANCE WITH ORDINANCE SECTION 22-1112 REQUIREMENTS.
- 16. EASEMENTS AND RESERVATIONS OF COMMON AREAS INCLUDING ACCESS DRIVES, PARKING AREAS, AND COMMON OPEN SPACES WILL BE PROVIDED IN CONDOMINIUM DOCUMENTS AT THE TIME OF FINAL DEVELOPMENT.
- 17. AS DEFINED BY FEMA FLOODPLAIN PANEL 42043C0330D, THERE IS NO FEMA DELINEATED FLOODPLAIN LOCATED WITHIN THE SUBJECT SITE.
- 18. IN A LETTER DATED SEPTEMBER 7, 2017, THE TOWNSHIP ACKNOWLEDGES RECEIPT AND APPROVAL OF THE CONCEPT/SKETCH PLAN MEETING THE REQUIREMENTS AS NOTED IN THE TND-1 ZONING ORDINANCE.
- 19. STORMWATER OPERATIONS AND MAINTENANCE (O&M) AGREEMENT IS PART OF THE STORMWATER MANAGEMENT SITE PLAN. OPERATIONS AND MAINTENANCE AGREEMENTS SHALL BE RECORDED WITH THE FINAL LAND DEVELOPMENT STORMWATER MANAGEMENT PLAN.
- 20. ALL STREET LIGHTS AND OUTDOOR LIGHTING SHALL UTILIZE LIGHT EMITTING DIODE (LED) TECHNOLOGY.
- 21. WHERE APPLICABLE, ALL CONSTRUCTION SHALL CONFORM TO PENNDOT PUBLICATIONS 408 AND 72 STANDARDS, SUSQUEHANNA TOWNSHIP ORDINANCES, AND SUSQUEHANNA TOWNSHIP AUTHORITY MANUAL FOR SEWER EXTENSION CONSTRUCTION.
- 22. BMPS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH THE PA STORMWATER BMP MANUAL. BMPS SHALL BE SEQUENCED RELATIVE TO PROJECT PHASING PLAN AND PER FINAL PLAN APPROVALS.
- 23. DO NOT SCALE DRAWINGS.

CAUTION NOTICE TO CONTRACTOR:

- THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. ALL BURIED UTILITIES ARE NOT NECESSARY SHOWN. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY IN ACCORDANCE WITH PA ACT 38 OF 1991 BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.
- THE CONTRACTOR SHALL CONFIRM ALL FINAL CONNECTION POINTS TO EXISTING UTILITIES WITH THE RESPECTIVE UTILITY COMPANY PRIOR TO CONSTRUCTION.

- 24. PROPOSED CONSTRUCTION SHALL CONFORM TO ALL APPLI AND LOCAL STANDARDS, SPECIFICATIONS AND REQUIREMEN
- 25. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITION SITE.
- 26. ALL MAPPING AND LOCATION OF EXISTING UTILITIES WERE OBTAINED FROM THE UTILITY COMPANIES LISTED UNDER "UTILITY CONTACTS". ALL DATA CONCERNING THESE EXISTING CONDITIONS WAS ACQUIRED BY THE H.F. LENZ COMPANY FOR USE IN DESIGNING THIS PROJECT. ITS ACCURACY OR COMPLETENESS IS NOT GUARANTEED BY THE H.F. LENZ COMPANY AND IN NO EVENT IS IT TO BE CONSIDERED A PART OF THE CONTRACT DOCUMENTS. CONTRACTORS MUST ASSUME ALL RISKS PERTAINING TO EXISTING SITE CONDITIONS.
- 27. THE CONTRACTOR SHALL EXERCISE CAUTION AND EMPLOY CAREFUL EXCAVATION METHODS DURING INSTALLATION OF THE FACILITIES TO AVOID DAMAGE TO OR CONFLICT WITH EXITING UTILITIES. THE CONTRACTOR SHALL PERFORM EXPLORATORY EXCAVATIONS AS DIRECTED AND/OR REQUIRED BY THE ENGINEER TO ASCERTAIN THE HORIZONTAL AND VERTICAL ALIGNMENT OF OF EXISTING UTILITIES PRIOR TO CONSTRUCTION IN AFFECTED AREAS AND MAKE THE APPROPRIATE ADJUSTMENTS IN THE FIELD IF CONFLICTS OCCUR. NO SEPARATE PAYMENT SHALL BE MADE FOR THE HEREIN DESCRIBED PROVISIONS AND SHALL BE INCLUDED IN THE COST OF THOSE ITEMS FOR WHICH PAYMENT SHALL BE MADE IN THE BID SCHEDULE.
- 28. CONTRACTOR IS RESPONSIBLE TO MAINTAIN USE OF ALL UTILITIES WITHIN THE IMMEDIATE WORK AREA DURING CONSTRUCTION WHEN WORK IS IN PROGRESS AT ALL TIMES.
- 29. CONTRACTOR IS RESPONSIBLE TO STABILIZE AND MAINTAIN ALL UTILITY POLES WITHIN THE IMMEDIATE WORK AREA THAT MAY BE AFFECTED BY THE CONSTRUCTION OPERATIONS.
- 30. PROVIDE, ERECT AND MAINTAIN BARRICADES, LIGHTING AND GUIDE RAILS AS REQUIRED BY APPLICABLE REGULATORY AGENCIES TO PROTECT THE PUBLIC AND WORKMAN.
- 31. ALL DISTURBED AREAS EXCEEDING THE LIMITS OF WORK SHALL BE RESTORED TO EXISTING CONDITIONS AT THE FULL EXPENSE OF THE CONTRACTOR UNLESS OTHERWISE DIRECTED BY THE OWNER.
- 32. ALL CONCRETE WORK SHALL COMPLY WITH THE SPECIFICATIONS AND THE AMERICAN CONCRETE INSTITUTE'S "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE", ACI 318-89 OR THE LATEST REVISION THERETO.
- 33. ALL CONCRETE TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT THE END OF 28 DAYS.
- 34. ALL REINFORCEMENT STEEL TO BE GRADE 60 DEFORMED BARS.
- 35. MINIMUM SPLICE FOR REINFORCEMENT STEEL IS 30 BAR DIAMETERS UNLESS OTHERWISE NOTED.
- 36. WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A-185 SPECIFICATIONS.
- 37. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK NECESSARY TO ESTABLISH LINES, LOCATION, GRADES, DIMENSIONS AND ELEVATIONS OF THE WORK FROM EXISTING FACILITIES.
- 38. THE CONTRACTOR SHALL EXCAVATE TO THE LINES AND GRADES AS SHOWN ON THESE DRAWINGS. THE CONTRACTOR SHALL PERFORM ALL EXCAVATION OF EVERY DESCRIPTION AND OF WHATEVER SUBSTANCES ENCOUNTERED TO THE DEPTHS INDICATED. ALL EXCAVATED MATERIAL NOT REQUIRED OR UNSUITABLE FOR FILL SHALL BE REMOVED AND WASTED OFF SITE.
- 39. UNLESS OTHERWISE INDICATED ON THESE DRAWINGS, REMOVE TREES, SHRUBS, GRASS AND OTHER VEGETATION INTERFERING WITH INSTALLATION OF NEW CONSTRUCTION. REMOVAL INCLUDES DIGGING OUT STUMPS AND ROOTS.
- 40. DURING EXCAVATION EXTREME CARE SHOULD BE TAKEN BY THE CONTRACTOR TO AVOID UNNECESSARY CUTTING OF ROOTS. WHEN ROOTS ARE CUT THEY SHOULD BE PROPERLY DRESSED SO AS NOT TO KILL THE TREE.
- 41. ALL TRENCH EXCAVATION SIDE WALLS GREATER THAN 5 FEET IN DEPTH SHALL BE SLOPED, SHORED, SHEETED, BRACED, OR OTHERWISE SUPPORTED BY MEANS OF THE SUFFICIENT STRENGTH TO PROTECT THE WORKMAN WITHIN THEM IN ACCORDANCE WITH APPLICABLE RULES AND REGULATIONS ESTABLISHED FOR CONSTRUCTION BY THE DEPARTMENT OF LABOR, OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA), AND BY LOCAL ORDINANCES. LATERAL TRAVEL DISTANCES TO AN EXIT LADDER OR STEPS SHALL NOT BE GREATER THAN 25 FEET IN TRENCHES 4 FEET OR DEEPER.
- 42. ALL TRAFFIC LINE PAINTING TO BE PADOT TYPE 1, IN ACCORDANCE WITH THE LATEST EDITION OF THE PADOT 408, SECTION 962.
- 43. ALL TRAFFIC SIGNS TO BE IN ACCORDANCE WITH THE LATEST EDITION OF THE PADOT 408, SECTION 1103.
- 44. THE DESIGN REVIEW COMMITTEE MUST REVIEW THE CONSTRUCTION DRAWINGS FOR COMPLIANCE WITH THE DESIGN GUIDELINES PRIOR TO ISSUANCE OF A BUILDING PERMIT.
- 45. CONTRACTOR SHALL NOTIFY SUSQUEHANNA TOWNSHIP AND THEIR ONSITE REPRESENTATIVE A MINIMUM OF 24 HOURS PRIOR TO THE PLACEMENT OF ENGINEERED FILL OVER PREVIOUSLY INSTALLED PIPE TRENCHES.
- 46. ALL ELECTRICAL, TELEPHONE AND CABLE LINES MUST BE PLACED UNDERGROUND.

CONFORMITY WITH DESIGN GUIDELINES:

- PROPOSED WALKING TRAILS SHALL BE IN ACCORDANCE WITH THE DESIGN GUIDELINES
- ALL PLANTERS SHALL BE IN ACCORDANCE WITH SECTION 507 SITE ELEMENTS OF THE DESIGN GUIDELINES
- HARDSCAPE SHALL BE IN ACCORDANCE WITH SECTION 503- PEDESTRIAN GATHERING AREAS, PEDESTRIAN MEWS & CENTRAL GREEN OF THE DESIGN GUIDELINES
- PARKING SHALL BE SCREENED AND BUFFERED FROM ADJACENT STREETS USE STREET WALL #2 AS PER SECTIONS 505 AND 507 OF THE DESIGN GUIDELINES
- ALL LIGHTING SHALL BE IN ACCORDANCE WITH SECTION 506- SITE LIGHTING OF THE DESIGN GUIDELINES
- STREETS AND SIDEWALKS SHALL BE IN ACCORDANCE WITH SECTION 502 -STREETSCAPE OF THE DESIGN GUIDELINES
- PROPOSED BENCHES SHALL BE IN ACCORDANCE WITH SECTION 507- SITE ELEMENTS OF THE DESIGN GUIDELINES
- ALL LANDSCAPING SHALL BE IN ACCORDANCE WITH SECTION 502 AND 508 OF THE DESIGN GUIDELINES

CABLE NTS.	STATE
ONS A	T THE

NOTE:



SYMBOL	AND	ABBRE

	EXISTING
100	CONTOUR LINE
W	WATERLINE
G	GAS LINE
SS	SANITARY SEWER
S7	STORM SEWER
STE	STEAM LINE
EU	UNDERGROUND ELEC TELE CABLE
<i>TU</i>	UNDERGROUND TELEPHONE
CTVU	UNDERGROUND CABLE
——————————————————————————————————————	OVERHEAD ELECTRIC
<i>T</i>	OVERHEAD TELEPHONE
CTV	OVERHEAD CABLE
OHW	OVERHEAD WIRES
C	CONDUIT
F0/C0M	FIBER OPTICS / COMMUNICATIONS
\heartsuit_{FH}	FIRE HYDRANT
	POWER POLE
0	SIGN (EXISTING)
	PROPOSED
100	CONTOUR LINE
	WATERLINE
G	GAS LINE
<u> </u>	SANITARY SEWER
ST	STORM SEWER
	DOWNSPOUT COLLECTOR PIPE
STE	STEAM LINE
EU	UNDERGROUND ELEC TELE CABLE
TU	UNDERGROUND TELEPHONE
CTVU	UNDERGROUND CABLE
F0/C0M	FIBER OPTICS/COMMUNICATIONS
Е	OVERHEAD ELECTRIC
—т—	OVERHEAD TELEPHONE
сту	OVERHEAD CABLE
C	CONDUIT
●FH	FIRE HYDRANT
PP	POWER POLE
SL 🗶	STREET LIGHT
	SIGN
., ., .,	

-X-X-X- FENCE

NUMBER OF PARKING SPACES

(00)

AC	ACRE	EMH	ELECTR
AC	AIR CONDITIONER	EM	ELECTR
AASHTO	AMERICAN ASSOCIATION OF STATE	EL/ELEV	ELEVAT
	HIGHWAYS AND TRANSPORTATION	EQ	EQUAL
	OFFICIALS	EXP	EXPANS
ACI	AMERICAN CONCRETE TRANSPORTATION	EX	EXISTIN
	OFFICIALS	FFE	FINISH
ASTM	AMERICAN SOCIETY FOR TESTING AND	FH	FIRE HY
	MATERIALS	GM	GAS ME
0	AT	GV	GAS VA
Æ	BASELINE	HP	HIGH P
BC	BOTTOM OF CURB	HORIZ	HORIZO
BW	BOTTOM OF WALL	INC	INCORP
BY/4"	BROKEN YELLOW PAVEMENT LINE/WIDTH	INV	INVERT
BLDG	BUILDING	LP	LIGHT F
Ę	CENTERLINE	МН	MANHOL
cc c/c	CENTER TO CENTER	MAX	MAXIMU
CLR	CLEAR	MIN	MINIMUN
CONC	CONCRETE	MPH	MILES F
	CONSTRUCTION	Ν	NORTH
СМР	CORRUGATED METAL PIPE	NPDES	
CPP	CORRUGATED POLYETHYLENE PIPE		ELIMINA
DIA	DIAMETER	No/#	NUMBEF
DI	DUCTILE IRON	PM	PARKIN
DS	DOWN SPOUT	OC	ON CEN
EOB	EDGE OF BERM	PADOT	PENNSY
EOP	EDGE OF PAVEMENT		TRANSP
ELEC	ELECTRIC	PERF	PERFOR

CTSI LLC 100 CTE DR DALLAS, PA 18612 (888) 278-8783

SUEZ WATER PENNSYLVAN 4211 EAST PARK CIRCLE HARRISBURG, PA 17111 (717) 554-3664

VERIZON PENNSYLVANIA 11 FLOOR STRAWBERRY HARRISBURG, PA 17101 (800) 821-0088

PA COMMONWEALTH OF C GOVERNORS OFFICE OF A 207 FINANCE BUILDING HARRISBURG, PA 17120 (717) 787–9945

PPL ELECTRIC UTILITIES CORPORATION 1801 BROOKWOOD ST HARRISBURG, PA 171042222 (800) 342-5775



ANY FUTURE LAND DEVELOPMENT, LAND DISTURBANCE ACTIVITY. AND/OR BUILDING OR OCCUPANCY PERMIT APPLICATION WILL REQUIRE AN APPROVED STORMWATER MANAGEMENT PLAN AND VERIFY THAT IT COMPLIES WITH THE APPROVED STORMWATER MANAGEMENT DESIGN PRIOR TO COMMENCEMENT OR APPROVAL

CONSTRUCTION DOCUMENTS SHALL BE SUBMITTED TO THE TOWNSHIP AND REVIEWED BY THE DESIGN REVIEW COMMITTEE PRIOR TO ISSUING OF ANY BUILDING PERMITS.

VIATION SCHEDULE

ΡE

PUB

PSI

PP

PVC

RCP

R/W

SCH

SEC

SEG

STA

SR

ST

SRL

SF

SY

TC

ΤW

TYP

WM

WV

WWF

XF

RIC MANHOLE RIC METER TION ISION NG FLOOR ELEVATION IYDRANT **IETER** /ALVE POINT ONTAL PORATED POLE OLE UM IM PER HOUR NAL POLLUTANT DISCHARGE ATION SYSTEM NG METER INTER SYLVANIA DEPARTMENT OF SPORTATION RATED

POLYETHYLENE PUBLICATION POUNDS PER SQUARE INCH POWER POLE POLYVINYL CHLORIDE PROPERTY LINE RADIUS REINF REINFORCEMENT REINFORCED CONCRETE PIPE RIGHT-OF-WAY SCHEDULE SECTION SEGMENT SLCPP SMOOTH LINED CORRUGATED PLASTIC PIPE STATION STATE ROUTE STREET SKID RESISTANCE LEVEL SOUTH SQUARE FEET SQUARE YARD TOP OF CURB TOP OF WALL TRANSFORMER TYPICAL WATER METER WATER VALVE WELDED WIRE FABRIC W/4" WHITE PAVEMENT LINE/WIDTH

LIST OF PUBLIC UTILITIES AND CONTACTS

	COMCAST CABLE COMMUNICATIONS INC 4601 SMITH ST HARRISBURG, PA 17109 (800) 266–2278
NIA INC	UGI UTILITIES INC 1500 PAXTON ST HARRISBURG, PA 17104 (800) 609–4844
INC SQUARE	SUSQUEHANNA TWP AUTH/SUSQUEHANNA TWP 1900 LINGLESTOWN RD HARRISBURG, PA 171103301 (717) 545–0116
OFFICE OF ADMIN ADMIN	ZAYO BANDWIDTH FORMERLY PPL TELECOM LLC 7010 SNOWDRIFT ROAD ALLENTOWN, PA 18106 (866) 364-6033

CALL BEFORE YOU DIG!

PENNSYLVANIA LAW REQUIRES 3 WORKING DAYS NOTICE FOR CONSTRUCTION PHASE AND 10 WORKING DAYS IN DESIGN STAGE - STOP CALL

> POCS SERIAL NUMBER 20171141544

TONO Prepared for: Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110

> Susquehanna Union Green Susquehanna Township, Dauphin County, PA

LaQuatra Bonci

ASSOCIATES

LANDSCAPE ARCHITECTURE

Nature leads, art follows.

COMF

GROUP

1407 Scalp Avenue

Phone: 814-269-930 FAX: 814-269-930


lohnstown, PA 15904

95 South Tenth Street

tel 412. 488. 8822

fax 412. 488.8825

Pittsburgh, Pennsylvania 15203



Project Number: 210191.01 Drawn by:

Checked by LBG/BJC

LBG/REA

Date: July 9, 2021

Revisions:

Scale:

General Information Sheet


Submission


Sheet Name:

Phase III Final Land Development Plans

Sheet Number:

Copyright 2019 by LaQuatra Bonci Associates All rights reserved. No part of these drawing may be copied or reproduced in whole or part without the express written consent of





Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.

Phasing Plan





Progress & Linglestown: TND

Legend




Mixed-Use Compliance Table

Use	Acreage	% of Site	Required/ Permitted
Commercial Use	(+/-) 21.04	36%	50% Max.
Residential Use	(+/-) 36.24	62%	40% Min.
Total Tract	(+/-) 58.07	100%	
Green Space	(+/-) 17.22	30%	25% Min.
Residential Single Family Detached	(+/-) 13.70 GROSS	24%	5% Min.
Residential Multi-Family	(+/-) 22.54 GROSS	39%	5% Min./40% Max.

GENERAL NOTES:

- 1. All property lines are build-to lines with the except of R-1 (single family detached
- residences). Consult Design Guidelines for build-to lines for R-1. 2. Consult Design Guidelines, Section 500 for sidewalk details, scoring patterns, crosswalk dimensions, and trail details.
- 3. Consult Design Guidelines, Section 500 for street wall dimensions and details.
- 4. Consult Design Guidelines, Section 500 for site lighting specifications and details. 5. Consult Design Guidelines, Section 500 for street trees, stormwater screening, buffer yards, and landscaping design.
- 6. Dimensions of all thoroughfares are provided on the Layout Plans C4.00A, C4.00B and C4.01-4.04. Consult the Design Guidelines, Section 500 for all thoroughfare pavement materials and design details. 7. Single family housing unit footprints are shown for representation only.







Project Number: 21023:1


Drawn by: DM

Checked by:

Date: July 9, 2021

Revisions:

Scale: 1"=100'



Sheet Name: Regulating Plan

Submission:

Phase III Final Land Development Plans

Sheet Number:

.10 Copyright 2021 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.



LANDSCAPE ARCHITECTURE 95 South Tenth Street Pittsburgh, Pennsylvania 15203 tel 412. 488. 8822 fax 412. 488.8825 Nature leads, art follows. $\frac{\text{H.F. LENZ}}{\text{COMPANY}}$ COMPANY 407 Scalp Avenue ohnstown, PA 15904 Phone: 814-269-9300 FAX: 814-269-9301 TONO GROUP

LaQuatra Bonci

Prepared for:

Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110

Susquehanna Union Green

Susquehanna Township, Dauphin County, PA



Project Number: 21023:1 Drawn by:


DM Checked by:

FB/DM Date:

July 9, 2021

Revisions:

Scale: 1"=100'



Sheet Name: Streetscape Plan

Submission:

Phase III Final Land Development Plans

Sheet Number:

_102 Copyright 2021 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.





	Provided	Acreage	Required/Permitted
Green Space	30%	17.22	25% min.
Greens	7%	4.26	3% min.



Revisions:

July 9, 2021

Scale: 1"=100'

SCALE: 1

Sheet Name: Public Realm Plan


Submission:

Sheet Number:

Phase III Final Land Development Plans

_103 Copyright 2021 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.





Progress & Linglestown: TND

Legend



GENERAL NOTES:

- 1. All property lines are build-to lines with the except of R-1 (single family detached
- residences). Consult Design Guidelines for build-to lines for R-1.2. Consult Design Guidelines, Section 500 for sidewalk details, scoring patterns, crosswalk dimensions, and trail details.
- 3. Consult Design Guidelines, Section 500 for street wall dimensions and details.
- Consult Design Guidelines, Section 500 for site lighting specifications and details.
 Consult Design Guidelines, Section 500 for street trees, stormwater screening, buffer yards, and landscaping design.
- 6. Dimensions of all thoroughfares are provided on the Layout Plans C4.00A, C4.00B and C4.01-4.04. Consult the Design Guidelines, Section 500 for all thoroughfare pavement materials and design details.
- Current tree count subject to change during contruction document design phase. All tree species will meet the Design Guideline requirements.
 Phase III A/B Tree Count:

Canopy/Shade Tree: 34 Understory/Ornamental Tree: 24



Susquehanna Union Green ^{Susquehanna} Township, Dauphin County, PA



Project Number: 21023:1 Drawn by: DM Checked by: FB/DM Date: July 9, 2021

Revisions:

Scale: 1"=20'

SCALE: 1" = 20'-0

Sheet Name: Enlarged Site & Landscape Plan - Phase III A Submission: Phase III Final Land Development Plans

Sheet Number:

L201 Copyright 2021 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.



Progress & Linglestown: TND

Legend



GENERAL NOTES:

- 1. All property lines are build-to lines with the except of R-1 (single family detached
- residences). Consult Design Guidelines for build-to lines for R-1.2. Consult Design Guidelines, Section 500 for sidewalk details, scoring patterns, crosswalk dimensions, and trail details.
- 3. Consult Design Guidelines, Section 500 for street wall dimensions and details.
- Consult Design Guidelines, Section 500 for site lighting specifications and details.
 Consult Design Guidelines, Section 500 for street trees, stormwater screening, buffer yards, and landscaping design.
- 6. Dimensions of all thoroughfares are provided on the Layout Plans C4.00A, C4.00B and C4.01-4.04. Consult the Design Guidelines, Section 500 for all thoroughfare pavement materials and design details.
- Current tree count subject to change during contruction document design phase. All tree species will meet the Design Guideline requirements.

Phase III A/B Tree Count: Canopy/Shade Tree: 34

Understory/Ornamental Tree: 24



Susquehanna Township, Dauphin County, PA



Project Number: 21023:1 Drawn by: DM Checked by: FB/DM Date: July 9, 2021

Revisions:


Scale: 1"=20'


SCALE: 1" = 20'-Sheet Name:

Enlarged Site & Landscape Plan - Phase III B Submission: Phase III Final Land Development Plans

Sheet Number:

L2002 Copyright 2021 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.






Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.



I:\Projects\2021\210100\210191x01\CADD\Civil\Dwgs\C400.dwg

Str	Structure Table			
Structure Name	Structure Details	Pipe Direction		
EX STM MH-15	T/RIM = 470.68 INV IN (30") = 457.64 INV OUT (30") = 457.64	TO STM MH 3-1		
EX STM MH-16	T/RIM = 444.15 INV IN (30") = 434.50 INV OUT (30") = 434.50	FROM INLET 3-9		
INLET 3–1 PADOT TYPE C STD BOX	T/RIM = 466.62 INV IN (12") = 461.20 INV OUT (18") = 461.00	FROM RL BLDG B TO MH 3-1		
INLET 3–2 PADOT TYPE C STD BOX	T/RIM = 462.97 INV IN (12") = 452.80 INV OUT (18") = 452.60	FROM RL BLDG B TO MH3-2		
INLET 3–3 PADOT TYPE C TYPE 4 BOX	T/RIM = 460.40 INV IN (30") = 451.05 INV IN (18") = 453.17 INV IN (12") = 456.40 INV OUT (30") = 450.85	FROM MH 3-2 FROM MH 3-4 FROM RL BLDG C TO INLET 3-5		
INLET 3-4 PADOT TYPE C STD BOX	T/RIM = 461.67 INV OUT (18") = 454.67	TO INLET 3-3		
INLET 3–5 PADOT TYPE C TYPE 4 BOX	T/RIM = 455.14 INV IN (30") = 446.89 INV IN (12") = 446.89 INV IN (18") = 446.89 INV OUT (30") = 446.69	FROM INLET 3-3 FROM RL BLDG C FROM INLET 3-6 TO INLET 3-7		
INLET 3-6 PADOT TYPE C STD BOX	T/RIM = 456.40 INV OUT (18") = 450.40	TO INLET 3-5		
INLET 3–7 PADOT TYPE C TYPE 4 BOX	T/RIM = 452.44 INV IN (30") = 444.92 INV IN (18") = 445.14 INV OUT (30") = 444.72	FROM INLET 3–5 FROM INLET 3–8 TO INLET 3–9		
INLET 3-8 PADOT TYPE C STD BOX	T/RIM = 453.40 INV OUT (18") = 446.86	TO INLET 3-7		
INLET 3–9 PADOT TYPE C TYPE 4 BOX	T/RIM = 447.17 INV IN (30") = 438.25 INV IN (12") = 438.25 INV IN (18") = 442.11 INV OUT (30") = 438.05	FROM INLET 3-7 FROM RL BLDG D FROM INLET 3-10 TO EX MH-16		
INLET 3-10 PADOT TYPE C STD BOX	T/RIM = 446.94 INV IN (12") = 442.40 INV OUT (18") = 442.40	FROM RL BLDG-E TO INLET 3-9		
STM MH 3–1 5' DIAMETER	T/RIM = 467.10 INV IN (30") = 457.27 INV IN (18") = 460.86 INV OUT (30") = 457.07	FROM EX MH-15 FROM INLET 3-1 TO STM MH 3-2		
STM MH 3–2 5' DIAMETER	T/RIM = 463.71 INV IN (30") = 452.47 INV IN (12") = 459.01 INV IN (18") = 452.47 INV OUT (30") = 452.27	FROM ST MH 3–1 FROM RL BLDG A FROM INLET 3–2 TO INLET 3–3		

 ALL DOWNSPOUT COLLECTOR PIPES (RL) ARE 12" SLCPP @ 0.5% MIN





Drainage Plan Submission: Phase III Final Land Development

Sheet Number:


Plans


Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.







without the express written consent of owner










ACCESSIBLE PARKING SPACES

NOT TO SCALE




ACCESSIBLE PARKING SIGN

NOT TO SCALE


REPLACEABLE DETECTABLE WARNING PANELS

may be copied or reproduced in whole or part without the express written consent of own

NOT TO SCALE




NOT TO SCALE



REQUIRED FOR UNIFORMITY AND INTERCHANGEABILITY. IT


NOT TO SCALE



- NOTES: 1. FOR ALL DEPTHS OF COVER LESS THAN TWO (2) FEET, PIPE MUST BE SCHEDULE 40 PVC. FOR DEPTHS OF COVER GREATER THAN TWO (2) FEET, FLEXIBLE PIPE MAY BE USED. REFER TO SPECIFICATIONS FOR ALLOWABLE PIPE TYPES.
- 2. A WATERTIGHT CONNECTION SHALL BE MAINTAINED WITH ANY TRANSITION 2. FROM SCHEDULE 40 PVC PIPE TO ANY OTHER PIPE TYPE.
- 3. THE DOWNSPOUT COLLECTOR DRAIN SHALL BE INSTALLED BEFORE THE DOWNSPOUTS ARE INSTALLED ON THE BUILDING. SITEWORK CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK TO AND INCLUDING THE RODENT SCREEN. BUILDING CONTRACTOR SHALL BE RESPONSIBLE FOR THE CONNECTION AT THE POINT OF THE RODENT SCREEN.

DOWNSPOUT COLLECTOR DETAIL

NOT TO SCALE



WATER LINE INSTALLATION

WATER LINE INSTALLATION (BEDDING AND BACKFILL) TO BE IN ACCORDANCE WITH SUEZ WATER PENNSYLVANIA, INC GUIDELINES. ALL LAYING, JOINING, AND TESTING SHALL BE PERFORMED IN THE PRESENCE OF THE WATER COMPANY AND SHALL BE SUBJECT TO ITS APPROVAL BEFORE ACCEPTANCE. WATERLINE MUST BE INSPECTED AND APPROVED BY THE WATER COMPANY PRIOR TO BACKFILLING. THE CONTRACTOR MUST NOTIFY THE WATER COMPANY THREE (3) WORKING DAYS PRIOR TO CONSTRUCTION SO THEY CAN SCHEDULE AN INSPECTOR TO OVERSEE CONSTRUCTION. ALL COSTS ASSOCIATED WITH THE REQUIRED INSPECTOR SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.


ALL WATER LINES MUST SUCCESSFULLY PASS A PRESSURE TEST AND BACTERIA TEST IN THE PRESENCE OF THE WATER COMPANY'S INSPECTOR PRIOR TO THE LINES BEING PLACED INTO SERVICE.

EXISTING WATER MAINS ARE SHOWN FOR GENERAL INFORMATION ONLY, BASED ON LIMITED DATA. NO GUARANTEE IS MADE CONCERNING HORIZONTAL OR VERTICAL ALIGNMENT, PIPE SIZE, OR PIPE TYPE. CONTRACTOR SHALL PERFORM EXPLORATORY EXCAVATIONS AT ALL POINTS OF CONNECTION.


CONTRACTOR SHALL DETERMINE PIPE SIZES, TYPES AND HORIZONTAL AND VERTICAL ALIGNMENT PRIOR TO ORDERING ANY COUPLINGS, FITTINGS, ETC. CONTRACTOR SHALL COORDINATE ANY REQUIRED WATER SHUTDOWNS AND TAP TO EXISTING SYSTEM WITH THE WATER COMPANY.


MAINTAIN A MINIMUM DEPTH OF 5'-0" FROM INVERT OF NEW WATER LINE TO FINISHED GRADE.

CONTRACTOR TO SUBMIT SHOP DRAWINGS OF THE MATERIALS TO BE USED FOR THE WATER SYSTEM TO WATER COMPANY AND SUSQUEHANNA TOWNSHIP OR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION. MEGA LUG RETAINER GLAND SETS MUST BE USED ON ALL FITTINGS.




TRENCH RESTORATION DETAIL NOT TO SCALE








Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of own
















	THRUST BLOCK BEARING AREA					
THRU	THRUST BLOCKING AT 100 PSI WORKING PRESSURE					
PIPE SIZE	MIN	. BEARING	SURFACE RE	EQUIRED –	S.F.	
INCHES	11 1/4° BEND	22 1/2° BEND	45° BEND	90° BEND	TEES & PLUGS	
4	1.0	1.0	1.0	1.0	1.0	
6	1.0	1.0	1.5	2.5	2.0	
8	1.0	1.5	2.5	4.0	3.0	
10	1.0	2.0	3.5	6.5	5.0	
12	1.5	2.5	5.0	9.0	7.0	
r						
THRUST BLOCKING AT 150 PSI WORKING PRESSURE						


SIZE	MIN. BEARING SURFACE REQUIRED - S.F.				
INCHES	11 1/4° BEND	22 1/2° BEND	45° BEND	90° BEND	TEES & PLUGS
4	1.5	1.5	1.5	1.5	1.5
6	1.5	1.5	2.0	4.0	3.0
8	1.5	2.0	4.0	7.0	5.0
10	1.5	3.0	5.5	10.5	7.5
12	2.0	4.0	8.0	14.5	10.5

THRU	THRUST BLOCKING AT 200 PSI WORKING PRESSURE					
PIPE SIZE	MIN. BEARING SURFACE REQUIRED – S.F.					
INCHES	11 1/4° BEND	22 1/2° BEND	45° BEND	90° BEND	TEES & PLUGS	
4	2.0	2.0	2.0	2.0	2.0	
6	2.0	2.0	3.0	5.5	4.0	
8	2.0	2.5	5.0	9.0	6.5	
10	2.0	4.0	7.5	14.0	10.0	
12	3.0	5.5	10.5	19.5	14.0	



Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110

Susquehanna Union Green Susquehanna Township, Dauphin County, PA



Project Number: 210191.01

Drawn by: LBG/REA

Checked by: LBG/BJC

Date: July 9, 2021

Revisions:

Scale:


Sheet Name: Site Utility Details

Submission:


Phase III Final Land Development Plans

Sheet Number:

C603 Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.








ALL TRENCHING AND BACKFILL BY CONTRACTOR. GAS COMPANY IS RESPONSIBLE FOR SUPPLYING PIPE AND INSTALLATION, CONTRACTOR TO COORDINATE.





SITE ELECTRIC, TELECOMMUNICATION DUCT BANK

GENERAL NOTES


• THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIES UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. ALL BURIED UTILITIES ARE NOT NECESSARY SHOWN. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY IN ACCORDANCE WITH PA ACT 38 OF 1991 BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS.

DUCTBANK NOTES:


• BACKFILL TO BE TAMPED TO AVOID SETTLING.

TRENCHING TO OBTAIN WARNING TAPE.

- CONTRACTOR SHALL PROVIDE UTILITY LATERALS TO EACH LOT. SIZE AND TYPE OF LATERAL AS INDICATED, EXTEND LATERAL TO RIGHT-OF-WAY/EASEMENT LINE, CAP AND MARK END.
- CONTRACTOR SHALL COORDINATE ALL WORK AND INSPECTION WITH THE UTILITY PROVIDER HAVING JURISDICTION.




NOT TO SCALE









Project Number: 210191.01 Drawn by: LBG/REA Checked by:

LBG/BJC Date: July 9, 2021

Revisions:

Scale:

Sheet Name: Site Utility Details

Sheet Number:

Submission: Phase III Final Land Development Plans

C605

Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.



SOIL TYPES SUMMARY				
LABEL	SLOPE			
At	ATKINS SILT LOAM 0 TO 3			
BkB2	2 BERKS SHALY SILT LOAM 3 TO 8			
BhC2	BERKS CHANNERY SILT LOAM	8 TO 15		
BkD2	BERKS CHANNERY SILT LOAM	15 TO 25		
BtB2	BRINKERTON & ARMAGH SILT LOAMS 3 TO 8			
CoB2	COMLY SILT LOAM	2 TO 8		
Ph	PHILO SILT LOAM	0 TO 2		
WeE2	WEIKERT SHALY SILT LOAM	25 TO 50		

NOTE:

- CONTRACTOR IS RESPONSIBLE FOR CLEANING MUD, DIRT AND DEBRIS CARRIED ONTO PUBLIC ROADWAYS FROM THE JOB SITE ON A DAILY BASIS OR AS DIRECTED BY SUSQUEHANNA TOWNSHIP REPRESENTATIVES.
- THE OWNER IS RESPONSIBLE FOR FORWARDING COPIES OF ALL COUNTY CONSERVATION DISTRICT INSPECTION REPORTS AND NOTICES ISSUED FOR THIS REPORTS TO CHECKENING TOWNOUND PROJECT TO SUSQUEHANNA TOWNSHIP.

NOTE

REFER TO SHEET No. ES200, ES201, ES202, ES203 & ES204 FOR ALL EROSION AND SEDIMENTATION CONTROL DETAILS.






Prepared for:

Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110


Susquehanna Union Green Susquehanna Township, Dauphin County, PA



Project Number: 210191.01 Drawn by: LBG/REA Checked by: LBG/BJC

Date: July 9, 2021

Revisions:



ES100 Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of owner.

INTERIM STABILIZATION

INTERIM STABILIZATION MUST BE IMPLEMENTED IMMEDIATELY TO ANY DISTURBED AREA ON WHICH EARTH MOVING ACTIVITIES HAVE CEASED. INTERIM STABILIZATION IN THE EVENT OF PLANNED OR UNPLANNED PROJECT SUSPENSION WILL CONSIST OF MULCHING OF DISTURBED AREAS DURING WINTER OR NONGROWING SEASONS. GROWING SEASONS STABILIZATION WILL CONSIST OF TEMPORARY SEEDING ACCORDING TO PROVIDED SPECIFICATIONS, AND MULCHING OF THE DISTURBED AREAS. FALL CUTOFF FOR SEEDING WILL BE APPROXIMATELY THE END OF OCTOBER, DEPENDING UPON LOCAL WEATHER CONDITIONS. DISTURBED AREAS WHICH ARE NOT AT FINISHED GRADE AND WHICH WILL BE REDISTURBED WITHIN ONE (1) YEAR MUST BE STABILIZED IN ACCORDANCE WITH TEMPORARY SEEDING SPECIFICATIONS. DISTURBED AREAS WHICH ARE EITHER AT FINISHED GRADE OR WILL NOT BE REDISTURBED WITHIN ONE (1) YEAR MUST BE STABILIZED IN ACCORDANCE WITH PERMANENT SEEDING SPECIFICATIONS.

TEMPORARY SEEDING SPECIFICATIONS

MULCH - CLEAN OAT OR WHEAT STRAW SHALL BE FREE FROM MANURE, SEED-BEARING STALKS OR ROOTS OF PROHIBITED OR NOXIOUS WEEDS AS DEFINED BY THE PENNSYLVANIA SEED ACT 1947. APPLY AT A RATE OF 3 BALES PER 1,000 SQUARE FEET (3 TONS PER ACRE). PRECAUTIONS SHALL BE TAKEN TO STABILIZE THE MULCH UNTIL THE VEGETATIVE COVER IS ESTABLISHED. STRAW SHALL BE SUITABLE FOR SPREADING WITH THE STANDARD MULCH BLOWER EQUIPMENT

SEED MIXTURE - SHALL BEAR A GUARANTEED STATEMENT OF ANALYSIS AND SHALL BE COMPOSED OF THE VARIETIES FOLLOWING AND MIXED IN THE PROPORTIONS SPECIFIED. TEMPORARY SEED MIXTURE % BY MINIMUM % MAXIMUM % SEEDING RATE

- WEIGHT PURITY GERMINATION WEED SEED LBS. PER 1000 SY PADOT FORMULA E ANNUAL RYEGRASS 100 95 0.10 90
- (Lolium multiflorum) TEMPORARY SEEDING APPLICATION SHALL BE IN ACCORDANCE WITH THE MOST CURRENT EDITION OF PADO PUB. 408 AND ALL SUPPLEMENTS THERETO.
- ALL AREAS TO BE SEEDED SHALL BE LOOSENED TO A DEPTH OF AT LEAST TWO INCHES BY
- MECHANICAL MEANS. MULCH SEEDED AREAS IMMEDIATELY AFTER SEEDING.
- FERTILIZER USE DRY FORMULATIONS OF 10-10-10 ANALYSIS FOR SEEDED AREAS AND APPLY • AT A RATE OF 100 LB PER 1000 SQ. YD. (500 LB PER ACRE).

PERMANENT SEEDING SPECIFICATIONS

SEED - UNLESS OTHERWISE SPECIFIED ON DRAWINGS, CONTRACTOR SHALL PROVIDE MODIFIED PADOT FORMULA "B" FOR ALL LAWN AREAS WITH SLOPES LESS THAN 3:1, AND FORMULA "L" FOR ALL SLOPE AREAS EQUAL TO OR STEEPER THAN 3:1. SEEDING QUALITY REQUIREMENTS SHALL BE IN ACCORDANCE WITH SECTION 804, TABLE A OF THE PADOT FORM 408, MOST CURRENT EDITION.

- MULCH ALL MULCH SHALL BE AIR-DRIED AND REASONABLY FREE OF NOXIOUS WEEDS AND SEEDS, USE PEAT PROCESSED PINE OR HEMLOCK BARK, WELL ROTTED AND SEASONED, AS APPROVED. STRAW SHALL BE STALKS OF RYE, OATS OR WHEAT, STRAW SHALL BE SUITABLE FOR SPREADING WITH STANDARD MULCH BLOWER EQUIPMENT. APPLY AT A RATE OF 1200 POUNDS PER 1000 SQUARE YARDS. MULCH TO CONFORM TO REQUIREMENTS OF PADOT FORM 408, SECTION 805, MOST CURRENT EDITION.
- SEED MIXTURE SHALL BEAR A GUARANTEED STATEMENT OF ANALYSIS AND SHALL BE COMPOSED OF THE VARIETIES FOLLOWING AND MIXED IN THE PROPORTIONS SPECIFIED.
- TOPSOIL MUST BE PLACED A MINIMUM OF 2" ON FILL OUTSLOPES AND A 4" MINIMUM ON ALL AREAS TO RECEIVE VEGETATIVE STABILIZATION IN ORDER TO ENSURE PROPER GROWTH.

PERMANENT SEED MIXTURE	% BY WEIGH T	MINIMI PURITY GE		MAXIMUM % WEED SEED	SEEDING RATE LBS./1000 SY
PADOT FORMULA B					44.0 TOTAL
PERENNIAL RYEGRASS MIXTURE (Lolium perenne)	20	97	90	0.10	8.5
CREEPING RED FESCUE OR CHEWINGS FESCUE (Festuca rubra OR Festuca rubra spp commutata)	30	97	85	0.10	12.5
KENTUCKY BLUEGRASS MIXTURE (Poa pratensis)	45	97	80	0.15	21.0
ANNUAL RYEGRASS (Lolium Multiflorum)	5	95	90	0.10	2.0
PADOT FORMULA L (SLOPES STEEPER THAN 3:1)					48.0 TOTAL
HARD FESCUE MIXTURE (Festuca longifolia)	55	97	85	0.10	26.4
CREEPING RED FESCUE (Festuca rubra)	35	97	85	0.10	16.8
ANNUAL RYEGRASS (Lolium Multiflorum)	10	95	90	0.10	4.8

- •• SOIL SUPPLEMENTS (PULVERIZED AGRICULTURAL LIMESTONE) SHALL BE APPLIED AT A RATE OF 800 POUNDS PER 1000 SQUARE YARDS OVER ALL SEEDED AREAS.
- •• ALL AREAS TO BE SEEDED SHALL BE LOOSENED TO A DEPTH OF AT LEAST THREE INCHES BY MECHANICAL MEANS.
- MULCH AND LIME SEEDED AREAS IMMEDIATELY AFTER SEEDING.
- FERTILIZER USE DRY FORMULATIONS OF 10-20-20 ANALYSIS, COMMERCIAL FERTILIZER SHALL 1. CONTRACTOR SHALL IMPLEMENT THE EROSION AND SEDIMENT POLLUTION CONTROL PLAN IN ACCORDANCE WITH THE DRAWINGS. BE APPLIED AT A RATE OF 140 LB/1000 SY FOR SEEDED AND SODDED AREAS. FERTILIZER TO CONFORM TO REQUIREMENTS OF PADOT FORM 408, SECTION 804, MOST CURRENT EDITION.

DOCUMENTATION OF BMP INSPECTION, **REPAIR & REPLACEMENT**

THE CONTRACTOR SHALL KEEP WRITTEN RECORDS DOCUMENTING THE INSPECTION, REPAIR AND REPLACEMENT OF ALL BMP'S AND SHALL PROVIDE COPIES TO THE OWNER AND DAUPHIN COUNTY CONSERVATION DISTRICT UPON REQUEST.

RECYCLING AND/OR DISPOSAL OF PROJECT WASTE

PROJECT CONSTRUCTION WASTES SHALL CONSIST OF UNSUITABLE MATERIAL FOR USE AS A FILL OR BACKFILL MATERIAL. SUCH MATERIAL SHALL CONSIST OF CLAY, ROCK, EXCESS MATERIAL, TRASH AND DEBRIS. ALL WASTE MATERIAL SHALL BE STOCKPILED AND PROPERLY STABILIZED UNTIL THE WASTE CAN BE PROPERLY RECYCLED OR DISPOSED OF OFF SITE AT A WASTE DISPOSAL SITE THAT HAS BEEN APPROVED BY THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION. OTHER WASTE ITEMS SUCH AS GLASS. PLASTIC, OR METALS MUST BE DISPOSED OF IN ACCORDANCE WITH ANY LOCAL RECYCLING PROGRAM. A CONCRETE WASHOUT FACILITY SHALL BE PROVIDED FOR THE CLEANING OF CHUTES, MIXERS AND HOPPERS OF DELIVERY TRUCKS.

RECEIVING WATERS OF THE COMMONWEALTH

WATERS OF THE COMMONWEALTH WHICH MAY RECEIVE RUNOFE FROM THE PROJECT INCLUDE BLACK RUN WHICH IS LISTED BY CHAPTER 93 AS WARM WATER FISHES (WWF).

PROJECT STORM WATER RUNOFF

RECEIVING WATER - BLACK RUN WARM WATER FISHES — WWF

OFFSITE WASTE AND BORROW AREAS OFFSITE WASTE AND BORROW AREAS SHALL REQUIRE AN INDIVIDUAL EROSION AND

CONSERVATION DISTRICT.

CLEAN FILL AND ENVIRONMENTAL DUE DILIGENCE

THE NPDES PERMIT, WHERE THE EROSION AND SEDIMENTATION POLLUTION CONTROL PLAN IS PART OF, COVERS THE "MOVING, DEPOSITING, STOCKPILING, OR STORING OF SOIL, ROCK OR EARTH MATERIALS". IF THIS PROJECT WILL NEED FILL IMPORTED FROM AN OFF SITE LOCATION, THE RESPONSIBILITY FOR PERFORMING ENVIRONMENTAL DUE DILIGENCE AND THE DETERMINATION OF CLEAN FILL WILL RESIDE WITH THE CONTRACTOR. ENVIRONMENTAL DUE DILIGENCE IS DEFINED AS: INVESTIGATIVE TECHNIQUES, INCLUDING, BUT NOT LIMITED TO, VISUAL PROPERTY INSPECTIONS, ELECTRONIC DATA BASE SEARCHES, REVIEW OF PROPERTY OWNERSHIP, REVIEW OF PROPERTY USE HISTORY, SANBORN MAPS, ENVIRONMENTAL QUESTIONNAIRES, TRANSACTION SCREENS, ANALYTICAL TESTING, ENVIRONMENTAL ASSESSMENTS OR AUDITS. ANALYTICAL TESTING IS NOT A REQUIRED PART OF DUE DILIGENCE UNLESS VISUAL INSPECTION AND/OR REVIEW OF THE PAST LAND USE OF THE PROPERTY INDICATES THAT THE FILL MAY HAVE BEEN SUBJECTED TO A SPILL OR RELEASE OF REGULATED SUBSTANCE. IF THE FILL MAY HAVE BEEN AFFECTED BY A SPILL OR RELEASE OF A REGULATED SUBSTANCE, IT MUST BE TESTED TO DETERMINE IF IT QUALIFIES AS CLEAN FILL. TESTING SHOULD BE PERFORMED IN ACCORDANCE WITH APPENDIX A OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION'S POLICY "MANAGEMENT OF FILL". CLEAN FILL IS DEFINED AS: UNCONTAMINATED, NON-WATER SOLUBLE, NON-DECOMPOSABLE, INERT, SOLID MATERIAL, THE TERM INCLUDES SOIL, ROCK, STONE, DREDGED MATERIAL, USED ASPHALT, AND BRICK, BLOCK OR CONCRETE FROM CONSTRUCTION AND DEMOLITION ACTIVITIES THAT IS SEPARATE FROM OTHER WASTE AND IS RECOGNIZABLE AS SUCH. THE TERM DOES NOT INCLUDE MATERIALS PLACED IN OR ON THE WATERS OF THE COMMONWEALTH UNLESS OTHERWISE AUTHORIZED. (THE TERM "USED ASPHALT" DOES NOT INCLUDE MILLED ASPHALT OR ASPHALT THAT HAS BEEN PROCESSED FOR RE-USE.) FILL MATERIAL THAT DOES NOT QUALIFY AS CLEAN FILL IS REGULATED FILL. REGULATED FILL IS WASTE AND MUST BE MANAGED IN ACCORDANCE WITH THE DEPARTMENT OF ENVIRONMENTAL PROTECTION'S MUNICIPAL OR RESIDUAL WASTE REGULATIONS BASED ON 25 PA. CODE CHAPTERS 287 RESIDUAL WASTE MANAGEMENT OR 271 MUNICIPAL WASTE MANAGEMENT, WHICHEVER IS APPLICABLE. AS ALL CUT AND FILL MATERIALS FOR THIS PROJECT WILL BE USED ON SITE, A CLEAN FILL DETERMINATION IS NOT REQUIRED BY THE CONTRACTOR UNLESS THERE IS A BELIEF THAT A SPILL OR RELEASE OF A REGULATED SUBSTANCE HAS OCCURRED.

MAINTENANCE/OWNER'S RESPONSIBILITIES

1. MAINTENANCE OF ALL PERMANENT STORM WATER AND EROSION AND SEDIMENTATION CONTROL FACILITIES BECOMES THE RESPONSIBILITY OF THE OWNER IN PERPETUITY UPON COMPLETION OF CONSTRUCTION AND ACCEPTANCE BY OWNER, SUBJECT TO THE TERMS OF THE WARRANTY PERIOD SPECIFIED IN THE CONTRACT DOCUMENTS.

MEASURES PROVIDED TO AVOID/MINIMIZE/MITIGATE

POTENTIAL THERMAL IMPACTS RUNOFF FROM THE PROJECT SITE AREA WILL BE DIRECTED TOWARD PREDEVELOPMENT DISCHARGE LOCATIONS. THIS WILL MINIMIZE/MITIGATE THERMAL IMPACTS TO RECEIVING OFF SITE SURFACE WATERS. TREES AND SHRUBS ON SITE PROMOTE EVAPOTRANSIPRATION, WHICH HELPS FURTHER MITIGATE THERMAL IMPACTS.

WATER WILL BE ALSO BE DIRECTED TO AN INFILTRATION BASIN. HELPING TO FURTHER MINIMIZE THERMAL IMPACTS TO RECEIVING OFF SITE SURFACE WATERS.

- VEGETATION

GEOLOGIC ASSESSMENT & FORMATIONS/SOIL CONDITIONS POTENTIAL TO CAUSE POLLUTION

THE SITE DOES NOT CONTAIN ANY GEOLOGIC FORMATIONS OR SOIL CONDITIONS THAT HAVE THE POTENTIAL TO CAUSE POLLUTION. IF DURING CONSTRUCTION AN AREA IS LOCATED AND/OR UNCOVERED THAT MAY CAUSE POLLUTION TO THE SITE THE MATERIA WILL BE REMOVED. DISPOSED OR TREATED ACCORDING TO ALL STATE AND FEDERAL REGULATIONS. THE PROPOSED DETENTION FACILITY IS NOT UNDERLAIN BY CARBONATE GEOLOGY

CRITICAL STAGES OF BMP INSTALLATION

THE CRITICAL STAGE OF THE PLAN WHERE A LICENSED PROFESSIONAL SHALL BE ON-SITE FOR INSPECTIONS IS THE INSTALLATION OF THE UNDERGROUND DETENTION /INFILTRATION SYSTEMS, INFILTRATION TRENCHES, AND THE INFILTRATION BASINS.

MAINTENANCE

- WITH THE FOLLOWING:
- RESOWN, AND MULCH REAPPLIED.
- REACHES ONE-HALF THE HEIGHT OF THE COMPOST FILTER SOCKS.

- THE DEFICIENCY.

SEDIMENTATION CONTROL PLAN, AND SHALL BE APPROVED BY THE DAUPHIN COUNTY

GENERAL EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN

MINIMIZE EXTENT AND DURATION OF EARTH DISTURBANCE

MAXIMIZE PROTECTION OF EXISTING DRAINAGE FEATURES AND

MINIMIZE SOIL COMPACTION

UTILIZE OTHER MEASURES OR CONTROLS THAT PREVENT OR MINIMIZE GENERATION OF INCREASED STORMWATER RUNOFF

2. ALL EROSION AND SEDIMENTATION CONTROL BMP'S SHALL BE INSPECTED ON A WEEKLY BASIS AND FOLLOWING PRECIPITATION EVENTS. ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN. AND IN THE STORM WATER POLLUTION PREVENTION PLAN. SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED IN ACCORDANCE

a. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED, WATERED, AND RESEEDED AS NEEDED. ANY PERMANENTLY SEEDED AREAS THAT BECOME ERODED WILL HAVE THE TOPSOIL REPLACED, THE EROSION CONTROL MATTING REPLACED (IF APPLICABLE), THE GRASS

b. COMPOST FILTER SOCKS SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE COMPOST FILTER SOCKS WHEN IT

THE ROCK CONSTRUCTION ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCE AS CONDITIONS DEMAND.

d. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AND STORAGE AREA AS CONDITIONS DEMAND.

e. ALL NECESSARY REPAIRS AND/OR REPLACEMENT TO EROSION AND SEDIMENTATION CONTROL BMP'S SHALL BE MADE IMMEDIATELY AFTER THE INSPECTION WHICH IDENTIFIED THE DEFICIENCY. IN NO INSTANCE SHALL THE REPAIR AND/OR REPLACEMENT OF A BMP EXTEND BEYOND 24 HOURS FROM THE TIME OF THE INSPECTION WHICH IDENTIFIED

3. AT NO TIME WILL SEDIMENT BE ALLOWED TO LEAVE THE SITE AND ENTER COMMONWEALTH WATERS.

4. A COPY OF THIS PLAN MUST BE KEPT AVAILABLE FOR INSPECTION ON THE CONSTRUCTION SITE AT ALL TIMES THROUGHOUT THE TERM OF THE PROJECT.


5. THE INTENT OF THIS PLAN/NARRATIVE IS TO INDICATE GENERAL MEANS OF COMPLIANCE WITH THE REQUIREMENTS OF THE RULES AND REGULATIONS OF CHAPTER 102 OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION (AS AUTHORIZED UNDER THE CLEAN STREAMS LAW). IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO IMPLEMENT THESE METHODS. PLUS ADDITIONAL PROCEDURES IN ORDER TO ASSURE COMPLIANCE WITH APPLICABLE LAW. IT WILL FURTHER BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN ALL EROSION AND SEDIMENT CONTROL FACILITIES SO THAT THEY PERFORM AS REQUIRED BY APPLICABLE LAW.

6. FINES AND RELATED COSTS RESULTING FROM THE CONTRACTOR'S FAILURE TO PROVIDE ADEQUATE PROTECTION AGAINST SOIL EROSION AND FOR ANY VIOLATIONS OF THE CLEAN STREAMS LAW AND THE RULES AND REGULATIONS PROMULGATED THEREUNDER SHALL BE BORNE BY THE CONTRACTOR.


OSION AN	ND SEDIMEN	TATION CONTROL	MAINTENANCE SCHEDU
CONTROL MEASURE	INSPECT	PROBLEMS TO LOOK FOR	POSSIBLE REMEDIES
VEGETATION	ONCE A WEEK		CHECK FOR TOP-OF-SLOPE
	AND AFTER EVERY		DIVERSION AND INSTALL IF NEEDED
	STORM/SNOW MELT		
	RUNOFF EVENT	RILLS AND GULLIES FORMING	
			GULLIED SLOPES
		BARE SOIL PATCHES	RESEED, FERTILIZE AND MULCH BARE AREAS
ROCK	DAILY	SINK HOLES OR RUTS	AREAS ADD ROCK TO BRING TO SPECIFIED
	AND AFTER EVERY	SINK HOLES OK RUTS	DIMENSIONS
	STORM/SNOW MELT		
	, RUNOFF EVENT	SEDIMENT ON PUBLIC AND	SWEEP MATERIAL BACK TO PROJECT
		PRIVATE ROADWAYS	SITE. DO NOT WASH ROADWAY
			WITH WATER.
SILT SACK	ONCE A WEEK	SEDIMENT ACCUMULATION	REMOVE SEDIMENT AND DISPOSE
INLET	AND AFTER EVERY		ON SITE
PROTECTION	STORM/SNOW MELT		DEMONE SEDIMENT AND DISDOSE
	RUNOFF EVENT	RUNOFF ESCAPING AROUND	REMOVE SEDIMENT AND DISPOSE ON SITE
		INLET	
		RUNOFF ESCAPING	PLACE ADDITIONAL SAND
		THROUGH OPEN THROAT	BAGS, WEIGHTED SEDIMENT
		OF PADOT TYPE "C" TOP	FILTER TUBE, OR SEDIMENT
			LOGS TO DIRECT RUNOFF INTO
			THE OPEN GRATE
COMPOST	ONCE A WEEK	UNDERCUTTING OF SOCK	ADD SECTION OF SOCK
FILTER SOCK	AND AFTER EVERY		
	STORM/SNOW MELT	SOCK COLLAPSING	REPLACE WITH PYRAMID OF SOCKS
	RUNOFF EVENT		
		TORN SOCK	REPLACE WITH CONTINUOUS NEW
			SOCK FROM POST TO POST.
			SECURELY ANCHOR WITH PROPER
			STAPLES
		RUNOFF ESCAPING AROUND	
		INLET	EXTEND SOCK
		SEDIMENT LEVEL NEAR TOP	REMOVE SEDIMENT WHEN LEVEL
	ONCE A WEEK	TORN OR COMPROMISED	REACHES HALF OF ITS HEIGHT
EROSION CONTROL	AND AFTER EVERY		REPLACE WITH A NEW PIECE OF EROSION CONTROL BLANKET AND
BLANKET	STORM/SNOW MELT		RESEED AND MULCH IF NEEDED
	RUNOFF EVENT		RESEED AND MOLCH IF NEEDED
		RILLS AND GULLIES FORMING	FILL RILLS AND REGRADE GULLIED
		UNDER BLANKET	SLOPES. REPLACE EROSION
			CONTROL BLANKET AFTER
			CORRECTION
PUMPED	DAILY	FILTER BAG FULL OF	REPLACE FILTER BAG WITH A NEW
WATER FILTER	AND AFTER EVERY		PUMPED WATER FILTER BAG. A
BAG	STORM/SNOW MELT		REPLACEMENT FILTER BAG SHOULD
	RUNOFF EVENT		BE AVAILABLE ON SITE AT ALL
			TIMES
		TORN OR DAMAGED FILTER	REPLACE FILTER BAG WITH A NEW
		BAG	PUMPED WATER FILTER BAG. A
			REPLACEMENT FILTER BAG SHOULD BE AVAILABLE ON SITE AT ALL
		1	TIMES
		RUNOFF FROM FILTER BAG	PLACE FILTER BAG IN A STABILIZED
		CREATING EROSION	AREA TO PREVENT ADDITIONAL
			EROSION FORMING FROM DISCHARGE
			LOCATION
			CONCRETE WASHOUT SHALL BE
CONCRETE	DAILY	DAMAGED OR LEAKING	CUNCRETE WASHOUT SHALL BE
	AND AFTER EVERY	WASHOUTS	DEACTIVATED AND REPAIRED OR
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS	
	AND AFTER EVERY	WASHOUTS	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE
	AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING
WASHOUT	AND AFTER EVERY STORM/SNOW MELT RUNOFF EVENT	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL PLASTIC LINER TORN	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY
RIPRAP	AND AFTER EVERY STORM/SNOW MELT RUNOFF EVENT	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL PLASTIC LINER TORN SINK HOLES OR RUTS	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY ADD ROCK TO BRING TO SPECIFIED
RIPRAP	AND AFTER EVERY STORM/SNOW MELT RUNOFF EVENT 	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL PLASTIC LINER TORN SINK HOLES OR RUTS RIPRAP MOVING FROM	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY
WASHOUT	AND AFTER EVERY STORM/SNOW MELT RUNOFF EVENT ONCE A WEEK AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL PLASTIC LINER TORN SINK HOLES OR RUTS	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY ADD ROCK TO BRING TO SPECIFIED
CONCRETE WASHOUT	AND AFTER EVERY STORM/SNOW MELT RUNOFF EVENT 	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL PLASTIC LINER TORN SINK HOLES OR RUTS RIPRAP MOVING FROM ORIGINAL LOCATION	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY ADD ROCK TO BRING TO SPECIFIED DIMENSIONS
RIPRAP	AND AFTER EVERY STORM/SNOW MELT RUNOFF EVENT ONCE A WEEK AND AFTER EVERY STORM/SNOW MELT	WASHOUTS CONCRETE WASHOUT FULL OF MATERIAL PLASTIC LINER TORN SINK HOLES OR RUTS RIPRAP MOVING FROM	DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY MATERIALS INSIDE CONCRETE WASHOUT SHALL BE REMOVED WHEN 75% OF CAPACITY IS REACHED PLASTIC LINERS SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY ADD ROCK TO BRING TO SPECIFIED

INSPECTIONS BY CONTRACTOR MUST BE LOGGED ONTO DEP FORM 3800-FM-BCW0271d DATED 12/2019 AND KEPT ON SITE AT ALL TIMES

EDAGIONI AND GEDINIENTATIONI CONITDOI MAINITENIANICE GOLIEDI II E



Copyright 2019 by LaQuatra Bonci Associate All rights reserved. No part of these drawing may be copied or reproduced in whole or par without the express written consent o





LOCATION MAP SCALE: 1"=2000'

SOILS MAP SCALE: 1'' = 500

GENERAL REQUIREMENTS FOR SOIL EROSION AND SEDIMENTATION CONTROL

- SOIL EROSION AND SEDIMENTATION CONTROL SHALL BE IMPLEMENTED PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITIES. COMPOST FILTER SOCK SHALL BE INSTALLED TO A MINIMUM AS SHOWN ON THESE DRAWINGS.
- EARTH MOVING OPERATIONS SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE ACCELERATED SOIL EROSION. IN ACCORDANCE WITH THE PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION'S "EROSION AND SEDIMENT POLLUTION CONTROL PROGRAM MANUAL", AND AS SHOWN ON THESE DRAWINGS.
- COMPOST FILTER SOCK SHALL BE INSTALLED DOWNSTREAM OF CONSTRUCTION AND STOCKPILE AREAS TO CONFINE SEDIMENT THAT MAY BE WASHED FROM NEW FILL OR CUT SLOPES.
- COMPOST FILTER SOCK MUST BE INSTALLED AT LEVEL GRADE. BOTH ENDS OF EACH FENCE SECTION MUST EXTEND AT LEAST 10 FEET UPSLOPE AT 45° TO THE MAIN SOCK ALIGNMENT.
- COMPOST FILTER SOCK SHALL BE INSPECTED ONCE A WEEK AND AFTER EACH RUNOFF EVENT. DAMAGE SHALL BE REPAIRED IMMEDIATELY. SEDIMENT ACCUMULATIONS SHALL BE REMOVED AND PLACED IN THE TOPSOIL STOCKPILE.
- COMPOST FILTER SOCK SHALL BE MAINTAINED UNTIL FINAL PROTECTIVE VEGETATION HAS BEEN ESTABLISHED, OR OTHER GROUND COVER MATERIALS HAVE BEEN PLACED.
- THE CONTRACTOR SHALL PLACE SEEDING, SOIL SUPPLEMENTS, AND MULCHING IN ALL DISTURBED AREAS IN ACCORDANCE WITH PADOT PUB. 408, LATEST EDITION.
- FILTER FABRIC MATERIAL SHALL BE PADOT CLASS 3 GEOTEXTILE IN ACCORDANCE WITH SECTION 735 OF THE PADOT PA. 408, LATEST EDITION.
- UNTIL THE SITE IS STABILIZED, ALL EROSION AND SEDIMENTATION MUST BE MAINTAINED PROPERLY. MAINTENANCE MUST INCLUDE INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROL AFTER EACH RUNOFF EVENT AND ON A WEEKLY BASIS. ALL PREVENTATIVE AND REMEDIAL MAINTENANCE WORK, INCLUDING CLEAN OUT, REPAIR, REPLACEMENT, REGRADING, RESEEDING, REMULCHING, AND RENETTING, MUST BE PERFORMED IMMEDIATELY.
- A STAMPED AND SIGNED SET OF APPROVED EROSION AND SEDIMENTATION CONTROL PLANS AND NARRATIVE SHALL REMAIN ON SITE FOR THE DURATION OF THE PROJECT.

GENERAL EROSION AND SEDIMENT CONTROL CONSTRUCTION SEQUENCE FOR **REQUIREMENTS FOR PIPELINE AND UTILITY** INSTALLATION

- LIMIT ADVANCE CLEARING AND GRUBBING OPERATIONS TO A DISTANCE EQUAL TO TWO TIMES THE LENGTH OF PIPE INSTALLATION THAT CAN BE COMPLETED IN ONE DAY.
- WORK CREWS AND EQUIPMENT FOR TRENCHING , PLACEMENT OF PIPE AND BACKFILLING WILL BE SELF CONTAINED AND SEPARATE FROM CLEARING AND GRUBBING, AND SITE RESTORATION AND STABILIZATION OPERATIONS.
- LIMIT DAILY TRENCH EXCAVATION TO THE LENGTH OF PIPE • PLACEMENT AND BACKFILLING THAT CAN BE COMPLETED THE SAME DAY. NO MORE THAN 50 LINEAR FEET OF OPEN TRENCH SHALL EXIST WHEN PIPELINE/UTILITY LINE INSTALLATION CEASES AT THE END OF THE WORK DAY.
- WATER WHICH ACCUMULATES IN THE OPEN TRENCH WILL BE COMPLETELY REMOVED BY PUMPING BEFORE PIPE PLACEMENT AND/OR BACKFILLING BEGINS. PUMPED WATER WILL BE DISCHARGED THROUGH A COMMERCIALLY AVAILABLE FILTER BAG (SEE DETAIL).
- ON THE DAY FOLLOWING PIPE PLACEMENT AND TRENCH BACKFILLING, THE DISTURBED AREA WILL BE GRADED TO FINAL CONTOURS, AND APPROPRIATE PERMANENT/TEMPOARARY EROSION AND SEDIMENT POLLUTION CONTROL MEASURES/FACILITIES WILL BE INSTALLED. SEEDING AND MULCHING OF ALL DISTURBED AREAS SHALL BE COMPLETED WITHIN SEVEN DAYS AFTER THE PIPELINE/UTILITY LINE IS INSTALLED.


INFILTRATION BED AND RAIN GARDEN INSTALLATION

- 1. INSTALL AND MAINTAIN ADEQUATE EROSION AND SEDIMENTATION CONTROL MEASURES DURING CONSTRUCTION
- 2. THE EXISTING SUBGRADE UNDER THE INFILTRATION BED SHOULD NOT BE COMPACTED OR SUBJECT TO EXCESSIVE CONSTRUCTION EQUIPMENT TRAFFIC PRIOR TO GEOTEXTILE AND STONE BED PLACEMENT. THESE AREAS ARE TO BE PROTECTED FROM THE CONSTRUCTION TRAFFIC WITH THE USE OF COMPOST FILTER SOCKS.
- 3. WHERE EROSION OF SUBGRADE HAS CAUSED ACCUMULATION OF FINE MATERIALS AND/OR SURFACE PONDING. THIS MATERIAL SHOULD BE REMOVED WITH LIGHT FOUPMENT AND THE UNDERLYING SOILS SCARIFIED TO A MINIMUM DEPTH OF 6 INCHES WITH A YORK RAKE OR EQUIVALENT AND LIGHT TRACTOR. ALL FINE GRADING SHOULD BE DONE BY HAND. ALL BED BOTTOMS SHOULD BE AT LEVEL GRADE.
- 4. GEOTEXTILE AND BED AGGREGATE SHOULD BE PLACED IMMEDIATELY AFTER APPROVAL OF SUBGRADE PREPARATION AND INSTALLATION OF STRUCTURES. GEOTEXTILES SHOULD BE PLACED IN ACCORDANCE WITH MANUFACTURER'S STANDARDS AND RECOMMENDATIONS. ADJACENT STRIPS OF GEOTEXTILE SHOULD OVERLAP A MINIMUM OF 16 INCHES. IT SHOULD ALSO BE SECURED AT LEAST 4 FEET OUTSIDE OF BED IN ORDER TO PREVENT ANY RUNOFF OR SEDIMENT FROM ENTERING THE STORAGE BED. THIS EDGE STRIP SHOULD REMAIN IN PLACE UNTIL ALL BARE SOILS CONTIGUOUS TO BEDS ARE STABILIZED. AS THE SITE IS FULLY STABILIZED, EXCESS GEOTEXTILE ALONG BED EDGES CAN BE CUT BACK TO THE EDGE OF THE BED.
- 5. ONCE STABILIZED, INSTALL PROPOSED STORMWATER CONVEYANCE SYSTEM AS INDICATED IN THE PLANS AND PER THE PROVIDED DETAILS.

A SEQUENCE OF BMP INSTALLATION AND REMOVAL IN RELATION TO THE SCHEDULING OF EARTH DISTURBANCE ACTIVITIES PRIOR TO, DURING, AND AFTER EARTH DISTURBANCE ACTIVITIES

ANTICIPATED CONSTRUCTION BEGIN DATE: SPRING 2021

- 1. INSTALL ROCK CONSTRUCTION ENTRANCES AT LOCATIONS INDICATED ON THE PLANS. 2. CESSATION OF CONSTRUCTION ACTIVITY FOR FOUR (4) OR MORE DAYS REQUIRES TEMPORARY
- STABILIZATION.
- 3. INSTALL CONSTRUCTION FENCE AROUND WETLANDS AND TREES AT LOCATIONS INDICATED ON THE PLANS. 4. INSTALL COMPOST FILTER SOCKS DOWNSLOPE OF THE PROPOSED WORK AREA. REFER TO THE PLANS FOR THE LOCATION OF THE COMPOST FILTER SOCKS. NO EARTHMOVING OPERATIONS SHALL BEGIN UNTIL ALL COMPOST FILTER SOCKS HAVE BEEN PROPERLY INSTALLED. NO COMPOST FILTER SOCKS SHALL BE REMOVED UNTIL THE CONTRIBUTORY AREA DRAINING TO A SECTION OF COMPOST FILTER SOCK IS STABILIZED. THE AREA SHALL BE CONSIDERED STABILIZED AS OUTLINED BELOW.
- 5. CLEAR AND GRUB PROJECT AREA. STRIP ALL THE TOPSOIL AND PLACE IN DESIGNATED TOPSOIL STOCKPILE AREAS. COMPOST FILTER SOCK SHALL BE PLACED ON THE DOWNSLOPE SIDE OF THE TOPSOIL STOCKPILE AS SHOWN ON THE PLAN. TEMPORARY SEEDING SHALL BE PLACED ON THE TOPSOIL STOCKPILE (REFER TO TEMPORARY SEEDING SPECIFICATIONS). MINIMIZE MOVING AND REPLACING COMPOST FILTER SOCK TO LIMIT DAMAGE TO THE SOCK.
- 6. PERFORM DEMOLITION OF EXISTING BUILDING FEATURES AND SITE FEATURES.
- THE CONCRETE WASHOUT SHALL BE INSTALLED.
- 8. BEGIN EARTHWORK FOR THE PAD DEVELOPMENT, INFILTRATION BASIN NO.2, ROADWAY AND SIDEWALK AREAS.
- 9. INSTALL COMPOST FILTER SOCK AROUND THE INFILTRATION BASINS AT LOCATIONS INDICATED ON THE PLANS.
- 10. REMOVE CONSTRUCTION FENCE FROM TREES THAT WILL BE DISTURBED AS PART OF THE DEVELOPMENT OF THIS PROJECT.
- 11. PERFORM GRADING TO BRING THE SITE TO FINAL GRADE ELEVATIONS. 12. INSTALL NEW STORM SEWER AS INDICATED ON THE PLANS. ANY NEWLY INSTALLED INLET SHALL RECEIVE SILT SACK INLET PROTECTION WITHIN 8 HOURS OF THE INLET BEING PLACED. NO INLET PROTECTION SHALL BE REMOVED UNTIL THE CONTRIBUTORY AREA DRAINING TO A SECTION OF INLET PROTECTION IS STABILIZED. THE AREA SHALL BE CONSIDERED STABILIZED AS OUTLINED BELOW.
- 13. INSTALL ALL UTILITIES ON SITE. 14. BEGIN CONSTRUCTION OF THE BITUMINOUS AREA AFTER ALL UTILITIES HAVE BEEN INSTALLED. AS SOON AS PRACTICAL, AFTER AREAS TO BE PAVED HAVE REACHED SUBGRADE ELEVATION, PLACE STONE SUBBASE. THESE AREAS SHALL BE CONSIDERED STABILIZED ONCE THE SUBBASE HAS BEEN INSTALLED.
- 15. COMPLETE THE INFILTRATION BASIN NO.2, WHEN THE AREA UPSLOPE IS CONSIDERED STABILIZED.
- 16. COMPLETE CONSTRUCTION ACTIVITIES FOR PHASE 5 OF THE PROJECT.
- 17. SPREAD TOPSOIL OVER ALL DISTURBED AREAS NOT TO BE PAVED. SEED IN ACCORDANCE TO PERMANENT SEEDING SPECIFICATIONS.
- 18. REMOVE TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES ONCE PERMANENT MEASURES ARE ESTABLISHED. PERMANENT CONTROL IS CONSIDERED ACHIEVED WHEN ROADWAYS ARE PAVED AND A 70% UNIFORM PERENNIAL VEGETATIVE COVER IS ESTABLISHED ON ALL SEEDED AREAS. ALL TEMPORARY EROSION AND SEDIMENTATION PLAN CONTROLS ARE TO BE ASSESSED /INSPECTED BY THE DAUPHIN COUNTY CONSERVATION DISTRICT/PENNSYLVANIA DEPARTMENT OF ENVIRONMENTAL PROTECTION PERSONNEL TO VERIFY THAT SUFFICIENT VEGETAL COVER HAS BEEN ATTAINED PRIOR TO THE REMOVAL OR CONVERSION OF EROSION AND SEDIMENTATION PLAN CONTROLS. ANY AREAS DISTURBED DURING THE REMOVAL OF THE TEMPORARY CONTROLS SHALL BE REPAIRED WITHIN 8 HOURS.
- 19. FINAL CLEANUP OF PROJECT SITE THE CONTRACTOR SHALL DISPOSE OF ALL WASTE MATERIAL OFF SITE IN A LAWFUL MANNER. ANTICIPATED CONSTRUCTION COMPLETION DATE: FALL 2021



NOT TO SCALE

SPECIFIC BMP MAINTENANCE INSTRUCTIONS

A. SOW ANNUAL RYE GRASS AT THE RATE OF 43 POUNDS PER ACRE, ONE POUND PER 1000 SQFT. BY BROADCASTING, DRILLING, OR HYDRAULIC APPLICATION; PLUS A STRAW MULCH ANCHORED TO PREVENT LOSS. B. COVER GRASS SEED WITH 1/4" (6MM) OF SOIL USING SUITABLE EQUIPMENT FOR THAT

C. MULCHING, WITHOUT SEEDING, IS TO BE USED AS AN INTERIM STABILIZATION CONTROL DURING NON-GROWING SEASONS OF THE YEAR

ROCK CONSTRUCTION ENTRANCE

PLAN AND CONSTRUCTED TO THE MINIMUM DIMENSIONS AS SHOWN ON THE DETAIL. TO THE SPECIFIED DIMENSION BY ADDING ROCK. A STOCKPILE OF ROCK MATERIAL

A. ROCK CONSTRUCTION ENTRANCE WILL BE PLACED AT THE LOCATION SHOWN ON THE B. THE ROCK CONSTRUCTION ENTRANCE THICKNESS WILL BE CONSTANTLY MAINTAINED

- WILL BE MAINTAINED ON SITE FOR THIS PURPOSE.

- SITE.

- SOCK.

- INLET PROTECTION

- RIPRAP APRONS

- EVENT.

TEMPORARY VEGETATIVE COVER

PURPOSE. ADD LIME AND FERTILIZER (LIME=1 TON/AC, FERTILIZER = 5:5:5 MIX).

C. AT THE END OF EACH CONSTRUCTION DAY, ALL SEDIMENT DEPOSITED ON PUBLIC AND PRIVATE ROADWAYS WILL BE REMOVED AND RETURNED TO THE CONSTRUCTION SITE. WASHING OF THE ROADWAYS IS NOT PERMITTED.

COMPOST FILTER SOCKS

A. COMPOST FILTER SOCKS WILL BE PLACED AS SHOWN ON THE PLAN TO INTERCEPT THE STORM WATER, AND FILTER THE RUNOFF BEFORE IT LEAVES THE CONSTRUCTION

B. COMPOST FILTER SOCKS ARE NOT PERMITTED IN ANY AREA OF CONCENTRATED FLOW SUCH AS DITCHES. SWALES. OR CHANNELS.

C. ADD SECTION OF COMPOST FILTER SOCK FROM POST TO POST WHEN UNDERCUTTING OF COMPOST FILTER SOCK OCCURS.

D. INSTALL COMPOST FILTER SOCKS IN ACCORDANCE WITH DETAILS AS SHOWN ON THE DRAWINGS.

E. INSPECT COMPOST FILTER SOCKS AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL EVENT. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.

F. ACCUMULATED SEDIMENT WILL BE REMOVED AS REQUIRED TO KEEP THE COMPOST FILTER SOCKS FUNCTIONAL. IN ALL CASES REMOVE DEPOSITS WHERE ACCUMULATIONS REACH 1/2 THE ABOVE GROUND HEIGHT OF THE COMPOST FILTER

G. THE REMOVED SEDIMENT IS TO BE USED FOR ON SITE GRADING, SEEDED, AND MULCHED.

H. ANY COMPOST FILTER SOCK SECTION WHICH HAS BEEN UNDERMINED OR TOPPED MUST BE IMMEDIATELY REPLACED WITH A NEW COMPOST FILTER SOCK.

I. ADHERE TO MANUFACTURERS RECOMMENDATIONS FOR REPLACING COMPOST FILTER SOCKS DUE TO WEATHERING.

J. AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED, REMOVE ALL COMPOST FILTER SOCKS AND UNSTABLE SEDIMENT DEPOSITS. BRING THE DISTURBED AREA TO GRADE AND STABILIZE.

A. INLET PROTECTION WILL BE PLACED IN EXISTING AND NEW INLETS AS DEPICTED ON THE PLANS.

B. INSTALL INLET PROTECTION IN ACCORDANCE WITH THE DETAIL ON THE DRAWING. C. INSPECT INLET PROTECTION AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL EVENT. MAKE ANY REQUIRED REPAIRS OR REPLACE IMMEDIATELY.

D. IN ALL CASES, REMOVE DEPOSITS AFTER EACH RAINFALL EVENT.

E. THE REMOVED SEDIMENT IS TO BE USED FOR ON SITE GRADING, SEEDED, AND MULCH. F. ADHERE TO MANUFACTURERS RECOMMENDATIONS FOR INSTALLATION OF INLET PROTECTION.

G. AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN PERMANENTLY STABILIZED, REMOVE INLET PROTECTION.

A. RIPRAP APRONS WILL BE PLACED IN INFILTRATION AREAS WHERE CONCENTRATED FLOW IS PRESENT AS DEPICTED ON THE PLANS.

B. INSTALL RIPRAP APRON IN ACCORDANCE WITH THE DETAIL ON THE DRAWING.

C. INSPECT RIPRAP APRON AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL EVENT. MAKE ANY REQUIRED REPAIRS OR REPLACE IMMEDIATELY.

D. IN ALL CASES, REMOVE DEPOSITS AFTER EACH RAINFALL

E. THE REMOVED SEDIMENT IS TO BE USED FOR ON SITE GRADING, SEEDED, AND MULCH.

F. IF NEEDED, ADD ROCK TO BRING THE RIPRAP APRON TO SPECIFIED DIMENSIONS.

G. ADD ROCK AND EXTEND THE RIP RAP APRON TO AVOID RUNOFF FROM ESCAPING AROUND THE RIPRAP APRON.






Prepared for:

Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110

Susquehanna Union Green Susquehanna Township, Dauphin County, PA



Project Number: 210191.01 Drawn by: LBG/REA Checked by

LBG/BJC Date:

Revisions:

July 9, 2021



Sheet Name: Erosion & Sedimentation **Control Plan Notes** Phase III Final Land Development Plans

Copyright 2019 by LaQuatra Bonci Associate All rights reserved. No part of these drawings may be copied or reproduced in whole or part

without the express written consent of c

Sheet Number:

THE TYPES, DEPTH, SLOPE, LOCATIONS, AND LIMITATIONS OF THE SOILS

SOIL TYPES

THE SOILS ON THE SITE AS DETERMINED BY THE USDA-SCS SOIL SURVEY OF DAUPHIN COUNTY, PENNSYLVANIA, CONSIST OF THE FOLLOWING TYPES. REFER TO THE ATTACHED SOILS INFORMATION IN APPENDIX B.

SOIL TYPE SOIL DESCRIPTION

At ATKINS SILT LOAM, 0 TO 3 PERCENT SLOPES. THE SOIL IS ON FLOOD PLAINS. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY LOW. DEPTH TO ROOT RESTRICTIVE LAYER, BEDROCK, OR LITHIC IS 60 TO 99 INCHES. THIS SOIL HAS A SLIGHT HAZARD OF EROSION AND SURFACE RUNOFF VERY HIGH. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS MODERATE. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS FREQUENTLY FLOODED. IT IS NOT PONDED SEASONAL WATER SATURATION IS AT A DEPTH OF 6 INCHES FROM NOVEMBER THROUGH JUNE. THIS SOIL BELONGS TO HYDROLOGIC GROUP B/D. THIS SOIL DOES MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE AND STEEL, FLOODING, HIGH SEASONAL WATER TABLE, HYDRIC INCLUSIONS, SLOW PERCOLATION RATES, LANDSLIDE PRONE, SOIL PIPING, FROST POTENTIAL, AND POOR SOURCE OF TOPSOIL, AND SOIL WETNESS.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING. USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

BkB2 BERKS SHALY LOAM, 3 TO 8 PERCENT SLOPES. THIS SOIL IS ON SHALE HILLSLOPES. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY HIGH. DEPTH TO ROOT RESTRICTIVE LAYER, BEDROCK, LITHIC IS 20 TO 40 INCHES. THIS SOIL HAS A SLIGHT HAZARD OF EROSION AND SURFACE RUNOFF IS LOW. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS VERY LOW. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS NOT FLOODED OR PONDED. THERE IS NO ZONE OF WATER SATURATION WITHIN A DEPTH OF 72 INCHES. THIS SOIL BELONGS TO HYDROLOGIC GROUP B. THIS SOIL DOES NOT MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE, DROUGHTY, EASILY ERODIBLE, HYDRIC INCLUSIONS. SLOW PERCOLATION, SOIL PIPING, AND A POOR SOURCE OF TOPSOIL.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

BhC2 BERKS CHANNERY SILT LOAM. 8 TO 15 PERCENT SLOPES. THIS SOIL IS ON RIDGES ON HILLS AND MOUNTAIN SLOPES ON MOUNTAINS. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY LOW. DEPTH TO ROOT RESTRICTIVE LAYER, BEDROCK, LITHIC IS 20 TO 40 INCHES. THIS SOIL HAS A SLIGHT HAZARD OF EROSION AND SURFACE RUNOFF IS MEDIUM. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS VERY LOW. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS NOT FLOODED OR PONDED. THERE IS NO ZONE OF WATER SATURATION WITHIN A DEPTH OF 72 INCHES. THIS SOIL BELONGS TO HYDROLOGIC GROUP B. THIS SOIL DOES NOT MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE, DROUGHTY, EASILY ERODIBLE, HYDRIC INCLUSIONS, SLOW PERCOLATION. SOIL PIPING, AND A POOR SOURCE OF TOPSOIL.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

BkD2 BERKS CHANNERY LOAM, 15 TO 25 PERCENT SLOPES. THIS SOIL IS ON RIDGES ON HILLS AND MOUNTAIN SLOPES ON MOUNTAINS. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY LOW. DEPTH TO ROOT RESTRICTIVE LAYER, BEDROCK, LITHIC IS 20 TO 40 INCHES. THIS SOIL HAS A MODERATE HAZARD OF EROSION AND SURFACE RUNOFF IS MEDIUM. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS VERY LOW. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS NOT FLOODED OR PONDED. THERE IS NO ZONE OF WATER SATURATION WITHIN A DEPTH OF 72 INCHES. THIS SOIL BELONGS TO HYDROLOGIC GROUP B. THIS SOIL DOES NOT MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE, DROUGHTY, EASILY ERODIBLE, HYDRIC INCLUSIONS, SLOW PERCOLATION, SOIL PIPING, AND A POOR SOURCE OF TOPSOIL.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

SOIL TYPE SOIL DESCRIPTION

THIS SOIL DOES MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE AND STEEL, DROUGHTY, EASILY ERODIBLE, HIGH SEASONAL WATER TABLE, HYDRIC INCLUSIONS, SLOW PERCOLATION RATES, LANDSLIDE PRONE, SOIL PIPING, FROST POTENTIAL, SHRINK-SWELL POTENTIAL, POOR SOURCE OF TOPSOIL AND SOIL WETNESS.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES. AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE, CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

CoB2 COMLY SILT LOAM, 2 TO 8 PERCENT SLOPES. THIS SOIL IS ON HILLS AND CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE AND STEEL, DROUGHTY, EASILY ERODIBLE, HIGH WATER TABLE, HYDRIC INCLUSIONS, SOIL PIPING, FROST POTENTIAL, AND A POOR SOURCE OF TOPSOIL.

- ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.
- MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE AND STEEL, EASILY ERODIBLE, FLOODING, HIGH WATER TABLE, HYDRIC INCLUSIONS, LANDSLIDE PRONE, SLOW PERCOLATION, SOIL PIPING, FROST POTENTIAL, POOR SOURCE OF TOPSOIL, AND SOIL WETNESS.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

WeE2 WEIKERT SHALY SILT LOAM, 25 TO 50 PERCENT SLOPES. THIS SOIL IS ON HILLS. SATURATION WITHIN A DEPTH OF 72 INCHES. THIS SOIL BELONGS TO HYDROLOGIC GROUP D. THIS SOIL DOES NOT MEET HYDRIC CRITERIA.

LIMITATIONS INCLUDE THE POTENTIAL OF CAVE-IN OF CUTBANKS, CORROSIVE TO CONCRETE AND STEEL, DROUGHTY, LANDSLIDE PRONE, HYDRIC INCLUSIONS, SLOW PERCOLATION, SOIL PIPING, FROST POTENTIAL, AND A POOR SOURCE OF TOPSOIL.

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO ENSURE SOIL IS AT PROPER MOISTURE CONTENT FOR COMPACTION.

BtB2 BRINKERTON AND ARMAGH SILT LOAMS, 3 TO 8 PERCENT SLOPES. THE SOIL IS ON DEPRESSIONS. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY LOW. DEPTH TO ROOT RESTRICTIVE LAYER, FRAGIPAN, BEDROCK LITHIC IS 11 TO 72 INCHES. THIS SOIL HAS A SLIGHT HAZARD OF EROSION AND SURFACE RUNOFF VERY HIGH. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS MODERATE. SHRINK SWELL POTENTIAL IS MODERATE. THIS SOIL IS NOT FLOODED OR PONDED. SEASONAL WATER SATURATION IS AT A DEPTH OF 3 INCHES FROM OCTOBER THROUGH JUNE. THIS SOIL BELONGS TO HYDROLOGIC GROUP C/D.

VALLEYS. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY HIGH. DEPTH TO ROOT RESTRICTIVE LAYER. FRAGIPAN IS 20 TO 35 INCHES. THIS SOIL HAS A SLIGHT HAZARD OF EROSION AND SURFACE RUNOFF IS MEDIUM AVAILABLE WATER TO A DEPTH OF 60 INCHES IS LOW. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS NOT FLOODED OR PONDED. A SEASONAL ZONE OF WATER SATURATION IS 24 INCHES FROM NOVEMBER THROUGH MARCH. THIS SOIL BELONGS TO HYDROLOGIC GROUP C. THIS SOIL DOES NOT MEET HYDRIC

CONSTRUCTION TECHNIQUES INCLUDE THE USE OF LADDERS IN EXCAVATION, TRENCH BOXES, AND EXCAVATIONS WITH SLOPES NOT CONDUCIVE TO CAVE-INS. PROTECTION SHALL BE USED AROUND CONCRETE TO PREVENT CORROSION. CARE SHOULD BE TAKEN TO STABILIZE SOILS AND PROVIDE SUFFICIENT EROSION AND SEDIMENTATION MEASURE SINCE THE SOILS ARE LANDSLIDE PRONE. SLOW PERCOLATION RATES MAY CAUSE WET SATURATED SOILS AND SOIL PIPING, USE CAUTION WHILE MOVING EQUIPMENT AROUND IN SATURATED SOILS. SOIL SHALL BE PROTECTED FROM THE ELEMENTS TO PREVENT FROST ACTION POTENTIAL. TOPSOIL SHOULD BE IMPORTED INTO THE SITE. CARE SHOULD BE TAKEN TO

Ph PHILO SILT LOAM, 0 TO 2 PERCENT SLOPES. THIS SOIL IS ON FLOOD PLAINS. WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS MODERATELY HIGH. DEPTH TO ROOT RESTRICTIVE LAYER IS GREATER THAN 60 INCHES. THIS SOIL HAS A SLIGHT HAZARD OF EROSION AND SURFACE RUNOFF IS MEDIUM. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS MODERATE. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS OCCASIONALLY FLOODED. IT IS NOT PONDED. A SEASONAL ZONE OF WATER SATURATION IS 21 INCHES FROM DECEMBER THROUGH APRIL. THIS SOIL BELONGS TO HYDROLOGIC GROUP B/D. THIS SOIL DOES NOT

WATER MOVEMENT IN THE MOST RESTRICTIVE LAYER IS HIGH. DEPTH TO ROOT RESTRICTIVE LAYER, BEDROCK, LITHIC IS 10 TO 20 INCHES. THIS SOIL HAS A SEVERE HAZARD OF EROSION AND SURFACE RUNOFF IS MEDIUM. AVAILABLE WATER TO A DEPTH OF 60 INCHES IS HIGH. SHRINK SWELL POTENTIAL IS LOW. THIS SOIL IS NOT FLOODED OR PONDED. THERE IS NO ZONE OF WATER

SYMBOL AND ABBREVIATION SCHEDULE

AC	ACRE	EX	EXISTING
AC	AIR CONDITIONER	FD	FLOOR DRAIN
AASHTO	AMERICAN ASSOCIATION OF STATE	FFE	FINISH FLOOR
	HIGHWAYS AND TRANSPORTATION	FH	FIRE HYDRANT
	OFFICIALS	GM	GAS METER
ACI	AMERICAN CONCRETE TRANSPORTATION	GV	GAS VALVE
	OFFICIALS	HP	HIGH POINT
ASTM	AMERICAN SOCIETY FOR TESTING AND	HORIZ	HORIZONTAL
	MATERIALS	INC	INCORPORATED
0	AT	INV	INVERT
Æ	BASELINE	LP	LIGHT POLE
BC	BOTTOM OF CURB	МН	MANHOLE
BW	BOTTOM OF WALL	MAX	MAXIMUM
BY/4"	BROKEN YELLOW PAVEMENT LINE/WIDTH	MIN	MINIMUM
BLDG	BUILDING	MPH	MILES PER HO
Ф.	CENTERLINE	Ν	NORTH
	CENTER TO CENTER	NPDES	NATIONAL POL
CLR	CLEAR		ELIMINATION S
CONC	CONCRETE	No/#	NUMBER
	CONSTRUCTION	РМ	PARKING METE
CMP	CORRUGATED METAL PIPE	OC	ON CENTER
CPP	CORRUGATED POLYETHYLENE PIPE	PADOT	PENNSYLVANIA
DIA	DIAMETER		TRANSPORTATI
DI	DUCTILE IRON	PERF	PERFORATED
EOB	EDGE OF BERM	PE	POLYETHYLENE
EOP	EDGE OF PAVEMENT	PUB	PUBLICATION
ELEC	ELECTRIC	PSI	POUNDS PER
ЕМН	ELECTRIC MANHOLE	PP	POWER POLE
EM	ELECTRIC METER	PVC	POLYVINYL CH
	ELEVATION	ዊ	PROPERTY LIN
EQ	EQUAL	R	RADIUS

LEGEND

	<u>EXISTING</u>	
W	WATERLINE	
G	GAS LINE	
	SANITARY SEWER	
ST	STORM SEWER	
S <i>TE</i>	STEAM LINE	
EU	UNDERGROUND ELEC TELE CABLE	
<i>TU</i>	UNDERGROUND TELEPHONE	
CTVU	UNDERGROUND CABLE	
—— <i>E</i> ——	OVERHEAD ELECTRIC	
<i>T</i>	OVERHEAD TELEPHONE	
CTV	OVERHEAD CABLE	
OH <i>W</i>	OVERHEAD WIRES	
C	CONDUIT	
F0/C0M	FIBER OPTICS / COMMUNICATIONS	
\heartsuit_{FH}	FIRE HYDRANT	
	POWER POLE	
0	SIGN (EXISTING)	

R DRAIN FLOOR ELEVATION HYDRANT RPORATED PER HOUR DNAL POLLUTANT DISCHARGE NATION SYSTEM ING METER SYLVANIA DEPARTMENT OF

RCP

R/W

SCH

SEC

SEG

STA

SR

ST

SRL

SF

SY

TC

ΤW

XF

TYP

WM

WV

WWF

W/4"

REINF REINFORCEMENT REINFORCED CONCRETE PIPE RIGHT-OF-WAY SCHEDULE SECTION SEGMENT SMOOTH LINED CORRUGATED PLASTIC PIPE SLCPP STATION STATE ROUTE STREET SKID RESISTANCE LEVEL SOUTH SQUARE FEET SQUARE YARD TOP OF CURB TOP OF WALL TRANSFORMER TYPICAL WATER METER WATER VALVE WELDED WIRE FABRIC WHITE PAVEMENT LINE/WIDTH

- SPORTATION ORATED
- ETHYLENE
- ICATION
- IDS PER SQUARE INCH
- VINYL CHLORIDE
- PERTY LINE

<u>PROPOSED</u> ──₩──── WATERLINE **—G**—— GAS LINE -----ST----- STORM SEWER -----EU----- UNDERGROUND ELEC TELE CABLE ----- TU----- UNDERGROUND TELEPHONE ----CTVU---- UNDERGROUND CABLE ---FO/COM--- FIBER OPTICS/COMMUNICATIONS -----E----- OVERHEAD ELECTRIC -----T----- OVERHEAD TELEPHONE -----CTV----- OVERHEAD CABLE -----C---- CONDUIT FIRE HYDRANT ●FH POWER POLE STREET LIGHT SL 🗶 SIGN -X-X-X- FENCE (00)NUMBER OF PARKING SPACES NEW CAST IRON DOWNSPOUT BOOT •_{DS}

AREA DRAIN \otimes CONNECT TO EXISTING




LaQuatra Bonci



Prepared for:

Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110


Susquehanna Union Green Susquehanna Township, Dauphin County, PA



Project Number: 210191.01 Drawn by: LBG/REA Checked by LBG/BJC Date:

July 9, 2021


Revisions:




Sheet Name: Erosion & Sedimentation **Control Plan Notes** Phase III Final Land Development Plans

Sheet Number:

Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of own





HEAVY DUTY MULTI-FILAMENT

POLYPROPYLENE

(HDMFPP)

РНОТО-

DEGRADABLE

12"

18"

24"

32"

1/8"

202 psi

100% AT

1000 HR.

2 YEARS

MULTI-FILAMENT

(MFPP)

PHOTO-

DEGRADABLE

12"

24"

3/8"

44 psi

100% AT

1000 HR.

1 YEAR

5 mil HOPE POLYPROPYLENE

- TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS.
- ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES 1/2 THE ABOVE GROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN
- SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
- BIODEGRADABLE FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- UPON STABILIZATION OF THE AREA TRIBUTARY TO THE SOCK, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.
- STAKES SPACED AT 10' MAXIMUM. USE 2"x 2" WOOD OR EQUIVALENT STEEL STAKES COMPOST FILTER SOCK


NOT TO SCALE


TABLE 4.1					
	COMPOST SOCK FABRIC MINIMUM SPECIFICATIONS				
MATERIAL TYPE	3 mil HOPE	5 mil HOPE	5 mil HOPE	MULTI-FIL POLYPROI (MFP	
MATERIAL CHARACTERISTICS	PHOTO– DEGRADABLE	PHOTO– DEGRADABLE	BIO- DEGRADABLE	PHOT DEGRAD	
SOCK DIAMETERS		12"	12"	12'	
	12"	18"	18"	18'	
	18"	24"	24"	24	
		32"	32"	32	
MESH OPENING	3/8"	3/8"	3/8"	3/8	
TENSILE STRENGTH		26 psi	26 psi	44 p	
ULTRAVIOLET STABILITY % ORIGINAL STRENGTH (ASTM G-155)	23% AT 1000 HR.	23% AT 1000 HR.		100% 1000	
MINIMUM FUNCTIONAL LONGEVITY	6 MONTHS	9 MONTHS	6 MONTHS	1 YE	
	TWO-PLY SYSTEMS				

INNER CONTAINMENT NETTING

OUTER FILTRATION MESH

SOCK FABRICS COMPOSED OF BURLAP MAY BE USE






Prepared for:

Vartan Group, Inc. 3605 Vartan Way, Suite 301 Harrisburg, PA 17110

Susquehanna Union Green Susquehanna Township, Dauphin County, PA



Project Number: 210191.01
Drawn by: LBG/REA
Checked by: LBG/BJC
Date:


July 9, 2021

Revisions: Scale: Sheet Name: Erosion & Sedimentation **Control Plan Details** Phase III Final Land Development Plans Sheet Number: FS2Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings

may be copied or reproduced in whole or part without the express written consent of owner

HOPE BIAXIAL NET				
CONTINUOUSLY WOUND				
FUSION-WELDED JUNCTURES				
3/4" X 3/4" MAX. APERTURE SIZE				
COMPOSITE POLYPROPYLENE FABRIC (WOVEN LAYER AND NON-WOVEN FLEECE MECHANICALLY FUSED VIA NEEDLE PUNCH)				
3/16" MAX. APERTURE SIZE				
D ON PROJECTS L ASTING 6 MONTHS OR LESS.				
4.2				
TANDARDS				
25% – 100% (DRY WEIGHT BASIS)				

_	E 4.2				
Ś	STANDARDS				
	25% – 100% (DRY WEIGHT BASIS)				
	FIBROUS AND ELONGATED				
	5.5 - 8.5				
	30% - 60%				
	30%-50% PASS THROUGH 3/8" SIEVE				
	5.0 dS/m (mmhos/cm) MAXIMUM				



LOW VOLUME FILTER BAGS SHALL BE MADE FORM NON-WOVEN GEOTEXTILE MATERIAL SEWN WITH HIGH STRENGTH, DOUBLE STITCHED "J" TYPE SEAMS. THEY SHALL BE CAPABLE OF TRAPPING PARTICLES LARGER THAN 150 MICRONS. HIGH VOLUME FILTER BAGS SHALL BE MADE FROM WOVEN GEOTEXTILES THAT MEET THE FOLLOWING STANDARDS:

PROPERTY	TEST METHOD	MINIMUM STANDARD
AVG. WIDE WIDTH STRENGTH	ASTM D-4884	60 LB/IN
GRAB TENSILE	ASTM D-4632	205 LB
PUNCTURE	ASTM D-4833	110 LB
MULLEN BURST	ASTM D-3786	350 PSI
UV RESISTANCE	ASTM D-4355	70%
AOS % RETAINED	ASTM D-4751	80 SIEVE

A SUITABLE MEANS OF ACCESSING THE BAG WITH MACHINERY REQUIRED FOR DISPOSAL PURPOSES SHALL BE PROVIDED. FILTER BAGS SHALL BE REPLACED WHEN THEY BECOME FULL OF SEDIMENT. SPARE BAGS SHALL BE KEPT AVAILABLE FOR REPLACEMENT OF THOSE THAT HAVE FAILED OR ARE FILLED. BAGS SHALL BE PLACED ON STRAPS TO FACILITATE REMOVAL UNLESS BAGS COME WITH LIFTING STRAPS ALREADY ATTACHED.

BAGS SHALL BE LOCATED IN WELL-VEGETATED (GRASSY) AREA, AND DISCHARGE ONTO STABLE, EROSION RESISTANT AREAS. WHERE THIS IS NOT POSSIBLE, A GEOTEXTILE UNDERLAYMENT AND FLOW PATH SHALL BE PROVIDED. BAGS MAY BE PLACED ON FILTER STONE TO INCREASE DISCHARGE CAPACITY. BAGS SHALL NOT BE PLACED ON SLOPES GREATER THAN 5%. FOR SLOPES EXCEEDING 5%, CLEAN ROCK OR OTHER NON-ERODIBLE AND NON-POLLUTING MATERIAL MAY BE PLACED UNDER THE BAG TO REDUCE SLOPE STEEPNESS.

NO DOWNSLOPE SEDIMENT BARRIER IS REQUIRED FOR MOST INSTALLATIONS. COMPOST BERM OR COMPOST FILTER SOCK SHALL BE INSTALLED BELOW BAGS LOCATED IN HQ OR EV WATERSHEDS, WITHIN 50 FEET OF ANY RECEIVING SURFACE WATER OR WHERE GRASSY AREA IS NOT AVAILABLE.


THE PUMP DISCHARGE HOSE SHALL BE INSERTED INTO THE BAGS IN THE MANNER SPECIFIED BY THE MANUFACTURER AND SECURELY CLAMPED. A PIECE OF PVC PIPE IS RECOMMENDED FOR THIS PURPOSE.

THE PUMPING RATE SHALL BE NO GREATER THAN 750 GPM OR ¹ THE MAXIMUM SPECIFIED BY THE MANUFACTURER, WHICHEVER IS LESS. PUMP INTAKES SHALL BE FLOATING AND SCREENED.

FILTER BAGS SHALL BE INSPECTED DAILY. IF ANY PROBLEM IS DETECTED, PUMPING SHALL CEASE IMMEDIATELY AND NOT RESUME UNTIL THE PROBLEM IS CORRECTED.

FILTER BAG DETAIL FOR PUMPED WATER

NOT TO SCALE



- AND SEED.
- ANCHOR TRENCH, STAPLE, BACKFILL, AND COMPACT SOIL. PER MANUFACTURES RECOMMENDATION.
- PREVIOUSLY INSTALLED BLANKET.
- ACROSS ENTIRE BLANKET WIDTH.
- <u>NOTES</u> PROPERLY SECURE THE BLANKETS.

- THE BLANKETS.
- 8. SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS, AND GRASS.

1. PREPARE SOIL (SEED BED) BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, 2. BEGIN AT THE TOP OF SLOPE. ROLL BLANKETS IN DIRECTION OF WATER FLOW. INSTALL BEGINNING OF ROLL IN 6"X6" 3. ROLL THE BLANKETS DOWN THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE AGAINST THE SOIL SURFACE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES/STAKES IN APPROPRIATE LOCATIONS AS 4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH MINIMUM 4" OVERLAP. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE SEAM STITCH ON THE 5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN MINIMUM 6" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, REFER TO MANUFACTURER RECOMMENDATION FOR STAPLE PATTERN 6. PLACE STAPLES/STAKES PER MANUFACTURE RECOMMENDATION FOR THE APPROPRIATE LENGTH OF SLOPE AND STEEPNESS BEING BLANKETED. THE BLANKET SHOULD NOT BE STRETCHED; IT MUST MAINTAIN GOOD SOIL CONTACT.

1. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" MAY BE NECESSARY TO

2. FOLLOW EROSION CONTROL TECHNOLOGY COUNCIL SPECIFICATION FOR PRODUCT SELECTION

3. SEED FILL SLOPES IN 15 FOOT INCREMENTS AS EMBANKMENT HEIGHT INCREASES.

4. EROSION CONTROL BLANKETS SHOULD BE USED ON ALL CUT AND FILL SLOPES 3:1 OR GREATER.

5. THE EROSION CONTROL BLANKET SHALL BE S75 AS MANUFACTURES BY NORTH AMERICAN GREEN OR APPROVED EQUAL.

6. SEED AND SOIL AMENDMENTS SHALL BE APPLIED ACCORDING TO THE RATES IN THE PLAN DRAWINGS PRIOR TO INSTALLING

7. PROVIDE ANCHOR TRENCH AT TOE OF SLOPE IN SIMILAR FASHION AS AT TOP OF SLOPE.


9. BLANKET SHALL HAVE GOOD CONTINUOUS CONTACT WITH UNDERLYING SOIL THROUGHOUT ENTIRE LENGTH. LAY BLANKET LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH SOIL. DO NOT STRETCH BLANKET.

10. THE BLANKET SHALL BE STAPLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.


11. BLANKETED AREAS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS SHALL BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

EROSION CONTROL BLANKET DETAIL

(SLOPE INSTALLATION) NOT TO SCALE



STAPLE PATTERN



Copyright 2019 by LaQuatra Bonci Associates. All rights reserved. No part of these drawings may be copied or reproduced in whole or part without the express written consent of own